

THE PROVINCE OF TRANSVAAL

MENIKO

DIE PROVINSIE TRANSVAAL

Official Gazette

(Registered at the Post Office as a Newspaper)



Offisiële Koerant

(As 'n Nuusblad by die Poskantoor Geregistreer)

PRICE: S.A. 15c Plus 1c G.S.T. OVERSEAS 20c

PRYS: S.A. 15c Plus 1c A.V.B. OORSEE 20c

VOL. 225

PRETORIA 4 MARCH,
4 MAART

1981

4132

Administrator's Notices

Administrator's Notice 159

11 February, 1981

TRANSVAAL BOARD FOR THE DEVELOPMENT OF PERI-URBAN AREAS: PROPOSED RAISING OF STATUS OF THE KOMATIPOORT LOCAL AREA COMMITTEE.

Notice is hereby given, in terms of section 10 of the Local Government Ordinance, 1939, that the Transvaal Board for the Development of Peri-Urban Areas has, in terms of section 9(1)(a) of the said Ordinance, submitted a petition to the Administrator to constitute a village council for the Komatiport Local Area Committee in lieu of the existing Local Area Committee.

The petition is open for inspection at the office of the Director of Local Government, 10th Floor, Merino Building, cor. Pretorius and Bosman Streets, Pretoria.

It shall be competent for all persons interested, within 30 days of the first publication hereof in the *Provincial Gazette*, to present to the Administrator a counterpetition setting forth the grounds of opposition to the said proposal.

PB. 3-6-5-2-165 Vol. 2

Administrator's Notice 160

11 February, 1981

KEMPTON PARK MUNICIPALITY: PROPOSED ALTERATION OF BOUNDARIES.

Notice is hereby given, in terms of section 10 of the Local Government Ordinance, 1939, that the Kempton Park Municipality has submitted a petition to the Administrator praying that he may in the exercise of the powers conferred on him by section 9(7) of the said Ordinance, alter the boundaries of Kempton Park Municipality by the inclusion therein of the area described in the Schedule hereto.

It shall be competent for any persons interested, within 30 days of the first publication hereof in the *Provincial Gazette*, to direct to the Director of Local Government, Private Bag X437, Pretoria a counterpetition requesting the Administrator to refrain from granting the said petition, either wholly or in part.

Further particulars of the application are open for inspection at the office of the Director of Local Government, Room B306A, Provincial Building, Pretorius Street, Pretoria and at the office of the Town Clerk of Kempton Park.

PB. 3-2-3-16 Vol. 3

Administrateurskennisgewings

Administrateurskennisgwing 159

11 Februarie 1981

TRANSVAALSE RAAD VIR DIE ONTWIKKELING VAN BUITESTEDELKE GEBIEDE: VOORGESTELDE VERHOGING VAN STATUS VAN DIE PLAASLIKE GEBIEDSKOMITEE VAN KOMATIPOORT.

Ingevolge artikel 10 van die Ordonnansie op Plaaslike Bestuur, 1939, word hierby bekend gemaak dat die Transvaalse Raad vir die Ontwikkeling van Buitestedelike Gebiede ingevolge artikel 9(1)(a) van genoemde Ordonnansie, 'n versoekskrif by die Administrateur ingedien het om 'n dorpsraad vir die Plaaslike Gebiedskomitee van Komatiport in die plek van die bestaande Plaaslike Gebiedskomitee in te stel.

Die versoekskrif is beskikbaar vir inspeksie by die kantoor van die Direkteur van Plaaslike Bestuur, 10de Verdieping, Merino Gebou, h/v. Pretorius- en Bosmanstraat, Pretoria.

Alle belanghebbende persone is bevoeg om binne 30 dae na die eerste publikasie hiervan in die *Provinsiale Koerant* aan die Administrateur 'n teenpetisie voor te lê met vermelding van die gronde van beswaar teen genoemde voorstel.

PB. 3-6-5-2-165 Vol. 2

Administrateurskennisgwing 160

11 Februarie 1981

MUNISIPALITEIT KEMPTONPARK: VOORGESTELDE VERANDERING VAN GRENSE.

Ingevolge artikel 10 van die Ordonnansie op Plaaslike Bestuur, 1939, word hierby bekend gemaak dat die Munisipaliteit van Kemptonpark 'n versoekskrif by die Administrateur ingedien het met die bede dat hy die bevoegdheid aan hom verleen by artikel 9(7) van genoemde Ordonnansie uitoeft en die grense van die Munisipaliteit van Kemptonpark verander deur die opneming daarin van die gebied wat in die Bylae hierby omskryf word.

Enige belanghebbende persone is bevoeg om binne 30 dae na die eerste publikasie hiervan in die *Provinsiale Koerant* aan die Direkteur van Plaaslike Bestuur, Privaatsak X437, Pretoria 'n teenpetisie te rig waarin die Administrateur versoek word om nie aan genoemde versoekskrif, in geheel of ten dele, te voldoen nie.

Verdere besonderhede van die aansoek lê in die kantoor van die Direkteur van Plaaslike Bestuur, Kamer B306A, Provinciale Gebou, Pretoriusstraat, Pretoria, en in die kantoor van die Stadsklerk Kemptonpark, ter insae.

PB. 3-2-3-16 Vol. 3

SCHEDULE.

- (a) Portion 9 (a portion of Portion 2) of the farm Kaalfontein 13-I.R., in extent 42,2048 ha. vide Diagram A.8988/48.
- (b) Portion 6 (a portion of Portion 1) of the farm Witfontein 16-I.R., in extent 37,8273 ha. vide Diagram A.2452/27.

Administrator's Notice 178

11 February, 1981

TOWN COUNCIL OF FOCHVILLE: WITHDRAWAL OF EXEMPTION FROM RATING.

The Administrator hereby notifies that the Town Council of Fochville has requested him to exercise the authority convened on him by section 9(10) of Ordinance 17 of 1939, and withdraw the existing exemption from the provisions of the Local Authorities Rating Ordinance, 1933, in respect of Portion 36 of the farm Kraalkop No. 147-I.Q., in the district of Potchefstroom.

All interested persons are entitled to submit reasons in writing to the Director of Local Government, Private Bag X437, Pretoria, within 30 days of the first publication of this notice why the request of the Town Council of Fochville should not be granted.

PB. 3-5-11-2-57

Administrator's Notice 179

11 February, 1981

TOWN COUNCIL OF WESTONARIA : WITHDRAWAL OF EXEMPTION FROM RATING.

The Administrator hereby notifies that the Town Council of Westonaria has requested him to exercise the authority convened on him by section 9(10) of Ordinance 17 of 1939, and withdraw the existing exemption from the provisions of the Local Authorities Rating Ordinance, 1933 in respect of the farm Panvlakte 291-I.Q.; Remaining Portion 17 and Portions 20, 22, 23, 29, 34 and 38 of the farm Elandsfontein 346-I.Q.; Remaining Portions 1 and 7 of Portion 26 of the farm Elandsfontein 346-I.Q.

All interested persons are entitled to submit reasons in writing to the Director of Local Government, Private Bag X437, Pretoria, within 30 days of the first publication of this notice why the request of the Town Council of Westonaria should not be granted.

PB. 3-5-11-2-38

Administrator's Notice 190

18 February, 1981

BRITS MUNICIPALITY: PROPOSED ALTERATION OF BOUNDARIES.

Notice is hereby given, in terms of section 10 of the Local Government Ordinance, 1939, that the Municipality of Brits has submitted a petition to the Administrator praying that he may in the exercise of the powers conferred on him by section 9(7) of the said Ordinance, alter the boundaries of Brits Municipality by the inclusion therein of the area described in the Schedule hereto.

BYLAE.

- (a) Gedeelte 9 ('n gedeelte van Gedeelte 2) van die plaas Kaalfontein 13-I.R., groot 42,2048 ha. volgens Kaart A.8988/48.
- (b) Gedeelte 6 ('n gedeelte van Gedeelte 1) van die plaas Witfontein 16-I.R., groot 37,8273 ha. volgens Kaart A.2452/27.

Administrateurskennisgewing 178 11 Februarie 1981

STADSRAAD VAN FOCHVILLE: INTREKKING VAN VRYSTELLING VAN EIENDOMSBELASTING.

Die Administrateur maak hierby bekend dat die Stadsraad van Fochville hom versoek het om die bevoegdheid aan hom verleen deur die bepalings van artikel 9(10) van Ordonnansie 17 van 1939, uit te oefen en die bestaande vrystelling van die bepalings van die Plaaslike Bestuur-Belasting Ordonnansie, 1933 ten opsigte van Gedeelte 36 van die plaas Kraalkop No. 147-I.Q., distrik Potchefstroom.

Alle belanghebbende persone is bevoeg om binne 30 dae na die eerste publikasie van hierdie kennisgewing skriftelik by die Direkteur van Plaaslike Bestuur, Pri-vaaitsak X437, Pretoria, redes aan te voer waarom daar nie aan die Stadsraad van Fochville se versoek voldoen moet word nie.

PB. 3-5-11-2-57

Administrateurskennisgewing 179 11 Februarie 1981

STADSRAAD VAN WESTONARIA: INTREKKING VAN VRYSTELLING VAN EIENDOMSBELASTING.

Die Administrateur maak hierby bekend dat die Stadsraad van Westonaria hom versoek het om die bevoegdheid aan hom verleen deur die bepalings van artikel 9(10) van Ordonnansie 17 van 1939, uit te oefen en die bestaande vrystelling van die Plaaslike Bestuur-Belasting-Ordonnansie, 1933 ten opsigte van die plaas Panvlakte 291-I.Q.; Resterende Gedeelte 17 en Gedeeltes 20, 22, 23, 29, 34, en 38 van die plaas Elandsfontein 346-I.Q.; Resterende Gedeeltes 1 en 7 van Gedeelte 26 van die plaas Elandsfontein 346-I.Q. in te trek.

Alle belanghebbende persone is bevoeg om binne 30 dae na die eerste publikasie van hierdie kennisgewing skriftelik by die Direkteur van Plaaslike Bestuur, Pri-vaaitsak X437, Pretoria, redes aan te voer waarom daar nie aan die Stadsraad van Westonaria se versoek voldoen moet word nie.

PB. 3-5-11-2-38

Administrateurskennisgewing 190 18 Februarie 1981

MUNISIPALITEIT BRITS: VOORGESTELDE VERANDERING VAN GRENSE.

Ingevolge artikel 101 van die Ordonnansie op Plaaslike Bestuur, 1939, word hierby bekend gemaak dat die Munisipaliteit van Brits 'n versoekskrif by die Administrateur ingedien het met die bede dat hy die bevoegdhede aan hom verleen by artikel 9(7) van genoemde Ordonnansie uitoefen en die grense van die Munisipaliteit Brits, verander deur die opneming daarin van die gebied wat in die Bylae hierby omskryf word.

It shall be competent for any persons interested, within 30 days of the first publication hereof in the *Provincial Gazette*, to direct to the Director of Local Government, Private Bag X437, Pretoria a counterpetition requesting the Administrator to refrain from granting the said petition, either wholly or in part.

Further particulars of the application are open for inspection at the office of the Director of Local Government, Room B306A, Provincial Building, Pretorius Street, Pretoria and at the office of the Town Clerk of Brits.

PB. 3-2-3-10

SCHEDULE.

1. Portion 411 (a portion of Portion 42) of the farm Krokodildrift 446-J.Q., in extent 5,5914 hectares vide Diagram A.4453/78.
2. Portion 412 (a portion of Portion 43) of the farm Krokodildrift 446-J.Q., in extent 6,6752 hectares vide Diagram A.4454/78.
3. Portion 413 (a portion of Portion 44) of the farm Krokodildrift 446-J.Q., in extent 6,2692 hectares vide Diagram A.4455/78.

Administrator's Notice 250

4 March, 1981

BRITS MUNICIPALITY: BY-LAWS RELATING TO THE STORAGE, USE AND HANDLING OF FLAMMABLE LIQUIDS AND SUBSTANCES.

The Administrator hereby, in terms of section 101 of the Local Government Ordinance, 1939, publishes the by-laws set forth hereinafter, which have been approved by him in terms of section 99 of the said Ordinance.

INDEX.

Section

1	Definitions
2—53	General
54—59	Stores
60—69	Bulk Depots
70—80	Transport of Flammable Liquids
81—95	Dry-cleaning Rooms: General
96—98	Special Provisions where Class A Flammable Liquids are used for Dry-cleaning
99—100	Special Provisions where Class B Flammable Liquids is used for Dry-cleaning
101—105	Spray Rooms
106—108	Mixing Rooms
109	Liquefied Petroleum Gases
110—123	Carbide
124	Offences and Penalties

Enige belanghebbende persone is bevoeg om binne 30 dae na die eerste publikasie hiervan in die *Provinsiale Koerant* aan die Direkteur van Plaaslike Bestuur, P.O. Box X437, Pretoria 'n teenpetisie te rig waarin die Administrateur versoek word om nie aan genoemde versoekskrif, in geheel of ten dele, te voldoen nie.

Verdere besonderhede van die aansoek lê in die kantoor van die Direkteur van Plaaslike Bestuur, Kamer B306A, Provinsiale Gebou, Pretoriussstraat, Pretoria, en in die kantoor van die Stadsklerk van Brits, ter insae.

PB. 3-2-3-10

BYLAE.

1. Gedeelte 411 ('n gedeelte van Gedeelte 42) van die plaas Krokodildrift 446-J.Q., groot 5,5914 hektaar volgens Kaart A.4452/78.
2. Gedeelte 412 ('n gedeelte van Gedeelte 43) van die plaas Krokodildrift 446-J.Q., groot 6,6752 hektaar volgens Kaart A.4454/78.
3. Gedeelte 413 ('n gedeelte van Gedeelte 44) van die plaas Krokodildrift 446-J.Q., groot 6,2692 hektaar volgens Kaart A.4455/78.

Administrateurskennisgewing 250

4 Maart 1981

MUNISIPALITEIT BRITS: VERORDENINGE BETREFFENDE DIE OPBERGING, GEBRUIK EN HANTERING VAN VLAMBARE VLOEISTOWWE EN STOWWE.

Die Administrateur publiseer hierby ingevolge artikel 101 van die Ordonnansie op Plaaslike Bestuur, 1939, die verordeninge hierna uiteengesit, wat deur hom ingevolge artikel 99 van genoemde Ordonnansie goedgekeur is.

INHOUDSOPGawe

Artikel		
1	Woordomskrywing	1
2—53	Algemeen	4
54—59	Pakkamers	18
60—69	Grootmaatdepots	20
70—80	Vervoer van Vlambare Vloeistowwe	24
81—95	Droogskoonmaaklokale: Algemeen	28
96—98	Spesiale Maatreëls waar Vlambare Vloeistowwe Klas A vir Droogskoonmaakdieleindes gebruik word	31
99—100	Spesiale Maatreëls waar Vlambare Vloeistowwe Klas B vir Droogskoonmaakdieleindes gebruik word	33
101—105	Spuitlokale	33
106—108	Menglokale	36
109	Vloeibare Petroleumgas	36
110—123	Karbied	36
124	Oortredings en Boetes	40

DEFINITIONS.

1. For the purpose of these by-laws, unless the context indicates otherwise —

“above ground storage tank” means a tank situated above or partly above ground and used or intended to be used for the storage of flammable liquid;

“authorized officer” means any officer of the Council acting within the scope of his duties;

“boundary line” means the perimeter of any premises in or on which flammable liquid is stored or used;

“bulk depot” means any premises used or intended to be used for the storage in bulk of flammable liquid whence flammable liquid is to be distributed mainly by road tank wagon or otherwise, and also includes any premises for the storage in bulk of packed products;

“bulk store” means any building or structure used or intended to be used in a bulk depot for the storage of flammable liquid in portable containers;

“carbide” means carbide or calcium;

“certificate of registration” means a certificate issued by the Council authorizing any person to use the premises therein specified either for the storage, use or handling of flammable liquid or for the storage of carbide, as the case may be;

“Chief Fire Officer” means the Chief Fire Officer of the Council, or in his absence, the person acting as Chief Fire Officer;

“container” means any case, tin, barrel, drum or other vessel used or intended to be used for the holding of flammable liquids but shall not include the fuel tank of a motor vehicle or stationary engine in normal use as such;

“Council” means the Town Council of Brits and includes the management committee of that Council or any officer employed by the Council, acting by virtue of any power vested in the Council in connection with these by-laws and delegated to him in terms of section 58 of the Local Government (Administration and Elections) Ordinance, 1960 (Ordinance 40 of 1960);

“dry-cleaning machinery” means any machines used or intended to be used for the cleaning or the treatment of garments or textiles with the aid of flammable liquid;

“dry-cleaning room” means any room or structure used or intended to be used for the cleaning or treatment for gain or reward of garments or textiles with the aid of flammable liquid;

“flammable liquids” —

‘Class A flammable liquid’ means any flammable liquid having a true flash-point of 23°C and lower;

‘Class B flammable liquid’ means any flammable liquid having a true flash-point of over 23°C up to and including 55°C.

‘Class C flammable liquid’ means any liquid, oil or other similar substance having a true flash-point of more than 55°C but under 90°C.

For the purposes of the definition of ‘flammable liquids’, flash-point shall be determined in accordance

WOORDOMSKRYWING

1. Vir die toepassing van hierdie verordeninge, tensy die sinsverband anders aandui, beteken —

“beskermde gebou” enige huis of gebou of ander bouwerk wat gebruik word of bedoel is om gebruik te word, of beskikbaar is vir menslike bewoning of openbare byeenkomste, en sluit skole, klubs en soortgelyke inrigtings in en omvat ook geboue ofstrukture vir die huisvesting van diere, maar sluit nie administrasiekantore, kleedkamers of eetlokale in ’n grootmaatdepot in nie;

“bewoonbare vertrek” ’n vertrek wat gebou of ingeing is om as ’n woonkamer of werkkamer te dien, en sluit winkels, werkinkels en kantore in, en die uitdrukking “woonvertrek” beteken dieselfde;

“bograndse opbergtenk” ’n tenk wat op of gedeeltelik bokant die grond geleë is, en wat gebruik word om vlambare vloeistof in op te berg, of wat bedoel is om as sodanig gebruik te word;

“Brandweerhoof” die Brandweerhoof van die Raad, of in sy afwesigheid, die persoon wat as waarnemende Brandweerhoof ageer;

“droogskoonmaaklokaal” ’n lokaal of bouwerk wat gebruik word of bedoel is om gebruik te word om vir wins of teen ’n vergoeding kledingstukke of tekstielware met behulp van vlambare vloeistof skoon te maak of te behandel;

“droogskoonmaakmasjinerie” enige masjinerie wat gebruik word of bedoel is om gebruik te word om kledingstukke of tekstielware met behulp van vlambare vloeistof skoon te maak of te behandel;

“gemagtigde beampie” ’n beampie van die Raad handelende binne die bestek van sy werkzaamhede;

“geregistreerde perseel” ’n perseel deur die Raad kragtens hierdie verordeninge geregistreer vir die opberging van karbied;

“grenslyn” die omtrek van ’n perseel waarop waarin vlambare vloeistowwe of stowwe opgeberg of gebruik word;

“grootmaatdepot” ’n perseel wat gebruik word of bedoel is om gebruik te word om vlambare vloeistof in grootmaat in op te berg, en waarvandaan die vlambare vloeistof hoofsaaklik deur middel van tenkvragmotors of op ’n ander wyse versprei word, en behels ook enige perseel waar verpakte ware in grootmaat opgeberg word;

“grootmaatpakhuis” ’n gebou of bouwerk in ’n grootmaatdepot wat gebruik word of bedoel is om gebruik te word om vlambare vloeistof in draagbare houers in op te berg;

“houer” ’n kis, blik, vaatjie, drom of ’n ander vat wat gebruik word of bedoel is om gebruik te word om vlambare vloeistof in te hou maar sluit nie die brandstoftenk van ’n motorvoertuig of van ’n vasstaande masjiën in normale gebruik as sodanig in nie;

“karbied” of karbied of kalsium;

“lugpypie” ’n pypie wat gemaak en aangebring is ten einde die dampe van vlambare vloeistof in die atmosfeer te laat ontsnap;

“menglokaal” enige lokaal of bouwerk wat gebruik word of bedoel is om gebruik te word vir die vervaardiging of voorbereiding van enige produk waarby die gebruik van vlambare vloeistowwe betrek word;

with the definition contained in the Code of Practice for the Petroleum Industry SABS 089; Part I — 1966;

“habitable room” means a room constructed or adapted to be used as a living room or workroom, and includes shops, workshops and offices, and the term “habitable” shall have a like meaning;

“liquid petroleum gas” means a gas, being a petroleum by-product which, when stored under pressure in cylinders, assumes a liquid state until the pressure has been reduced;

“mixing room” means any room or structure used or intended to be used for the manufacture or preparation of any product involving the use of flammable liquid;

“person” includes any individual, company or corporate body or partnership or other association of persons;

“protected work” means any house or building or other structure used or intended to be used or available for use for human habitation or public assembly and any school, club or similar institution and any building or structure housing animals, but shall not include any administrative office, change room or mess room in a bulk depot;

“pump” means any pump used or intended to be used for the supply, delivery, propulsion or pumping of flammable liquid or substances and includes all apparatus, pipes and appliances used for or in connection therewith, but shall not include pumps in bulk depots;

“registered premises” means premises registered by the Council in terms of these by-laws for the storage of carbide;

“road tank wagon” means a vehicle constructed and intended for the purpose of conveying flammable liquid for distribution principally or solely in a tank constructed as part of and firmly attached to such vehicle;

“spray booth” means any separate compartment constructed of metal and erected inside an existing building or any subdivision of any spray room when such subdivision or separate compartment is used or intended to be used for the purpose of spraying vehicles or articles with flammable liquid, and purposes incidental thereto;

“spray permit” means a permit issued by the Council authorizing any person to carry out the spraying of any article or thing with flammable liquid inside a building;

“spray room” means any room or structure used or intended to be used for the purpose of spraying vehicles or articles with flammable liquid and purposes incidental thereto;

“store” means any building or structure, other than a bulk store, which is used or intended to be used for the storage of flammable liquid in containers;

“tank” means a metal tank of adequate strength for the use intended, used or intended to be used for the storage of flammable liquid;

“transfer under seal” means the transfer of flammable liquid from or to a road tank wagon in such manner as to prevent the escape of flammable liquid or its

“ondergrondse opbergtenk” ’n tenk wat gebruik word of bedoel is om gebruik te word om vlambare vloeistof in op te berg en wat heeltemal in die grond ingelaat, en met grond of soliede rots omring is, of ’n tenk wat in ’n kelderverdieping onderkant die grondvlak geleë en omring is deur vloeistofdigte beton of steenwerk en geheel en al met ’n sandomhulling omring is;

“pakkamer” ’n gebou of bouwerk, uitgesonderd ’n grootmaatpakhuis, wat gebruik word of bedoel is om gebruik te word om vlambare vloeistof in houers in op te berg;

“persoon” ook enige individu, maatskappy of liggaam met regspersoonlikheid, of ’n vennootskap, of ’n ander vereniging van persone;

“pomp” enige pomp wat vir die voorsiening, lewering, voortdrywing of pomp van vlambare vloeistof of stowwe gebruik word, of wat vir sodanige gebruik bedoel is, en sluit alle apparate, pype en toestelle in wat daarvoor of in verband daarmee gebruik word, maar sluit nie pompe in grootmaatdepots in nie;

“Raad” die Stadsraad van Brits en omvat die bestuurskomitee van daardie Raad of enige beampete deur die Raad in diens geneem, handelende uit hoofde van enige bevoegdheid wat in verband met hierdie verordeninge aan die Raad verleen is en wat ingevolge artikel 58 van die Ordonnansie op Plaaslike Bestuur (Administrasie en Verkiesings), 1960 (Ordonnansie 40 van 1960), aan hom gedelegeer is;

“registrasiesertifikaat” ’n sertifikaat wat deur die Raad uitgereik is, waarby iemand gemagtig word om die persone wat daarin aangegee word vir die opbergting, gebruik of hantering van vlambare vloeistowwe of die opbergting van karbied, na gelang van die geval, te gebruik;

“spuithokkie” enige afsonderlike kompartement van metaal gebou en binne ’n bestaande lokaal ingerig of enige onderverdeling van ’n spuitlokaal indien so ’n kompartement of onderverdeling gebruik word of bedoel is om gebruik te word om voertuie of artikels met vlambare vloeistof te bespuit, en vir doeleinades wat daarmee gepaard gaan;

“spuitlokaal” ’n lokaal of bouwerk wat gebruik word of bedoel is om gebruik te word om voertuie of artikels met vlambare vloeistof te bespuit, en vir doeleinades wat daarmee gepaard gaan;

“spuitpermit” ’n permit wat die Raad uitreik en waarby iemand gemagtig word om enige artikel of ding in ’n gebou met vlambare vloeistowwe te bespuit;

“tenk” ’n metaaltenk, wat sterk genoeg is vir die bestemde doel, en wat gebruik word of bedoel is om gebruik te word om vlambare vloeistof in te berg;

“tenkvragmotor” ’n voertuig wat gebou en bedoel is om vlambare vloeistof, hoofsaaklik of uitsluitend in ’n tenk wat as deel van sodanige voertuig, en stewig daar-aan vasgebou is, vir verspreidingsdoeleinades te vervoer;

“verseelde oorbringing” die oorbring van vlambare vloeistof van of na ’n tenkvragmotor op so ’n wyse dat geen vlambare vloeistof of die dampe daarvan, by enige plek in die stelsel ontsnap nie, behalwe by sodanige plekke waar die dampe wat nooggedwonge afgedrywe word, deur ’n lugpypie ontsnap;

“vervoerpermit” ’n permit waarkragtens vlambare vloeistof per pad vervoer mag word;

“vlambare vloeistowwe” —

vapour at any point in the system, except at such points where the vapour necessarily expelled is discharged through a vent pipe;

"transport permit" means a permit authorizing the transportation by road of flammable liquid;

"underground storage tank" means a tank used or intended to be used for the storage of flammable liquid wholly sunk in and surrounded by earth or solid rock or any such tank situated in a basement below ground level and totally enclosed by a liquid-tight concrete or brick structure, and wholly surrounded by a sand filling;

"vent pipe" means a pipe constructed and installed to allow the escape of flammable liquid vapour into the atmosphere.

GENERAL.

Provisions of Other By-laws to Apply.

2. The provisions of these by-laws shall be in addition to, and not in substitution for, any other by-laws of the Council.

Application of these By-laws to Existing Premises.

3. The provisions of sections 34, 35, 37, 40, 41, 44, 56, 62, 65(a), 76, 81(2), 96(a), (b), (c), (e), (f) and (g), 99(a) and (c), and 103(a) and (d) shall not apply to any premises now in lawful use for the storage, use or handling of flammable liquid so as to require such premises to be reconstructed, altered or added to, to conform to the provisions thereof, but where any such premises or part thereof are reconstructed, altered or added to, such work shall be carried out in conformity with the provisions of these by-laws: Provided that on change of control or ownership of any premises in lawful use for the storage, use or handling of flammable liquid, no renewal of any certificate of registration issued in connection therewith shall be made, unless and until the provisions of sections hereinbefore mentioned have been complied with, and the provisions of such sections shall thereafter apply to such premises.

Application for the Approval of Plans.

4.(1) Every application for approval of plans shall be made in writing to the Council.

(2) Every such application shall be accompanied by a plan of the premises in respect of which a certificate is required, drawn to a scale of not less than 1:100, which shall specify —

(a) the premises including their elevation with regard to adjacent buildings or structures above or below the ground, the inside dimensions shown in figures of any room, building, structure or storage tank in which flammable liquid is to be stored, used or handled, as well as a description of the material to be used with which such room, building, structure or storage tank is or is proposed to be constructed; and

(b) full particulars including position of any pump, storage tank, store, mixing room, pipeline, dry-cleaning machinery, spray room, spray booth, or ventilating equipment.

'vlambare vloeistof Klas A' enige vlambare vloeistof waarvan die flitspunt 23°C en laer is;

'vlambare vloeistof Klas B' enige vlambare vloeistof met 'n flitspunt bo 23°C tot en met 55°C;

'vlambare vloeistof Klas C' enige vloeistof, olie of soortgelyke stof met 'n flitspunt wat hoër as 55°C maar laer is as 90°C.

Vir die toepassing van die woordomskrywing van "vlambare vloeistowwe", word flitspunt bepaal ooreenkomsdig die definisie daarvan vervat in die Gebruikskode vir die Petroleumnywerheid SABS 089; Deel I — 1966;

"vloeibare petroleum gas" 'n petroleum neweproduk wat, indien dit onder druk in silinders gestoor is, 'n vloeibare toestand aanneem totdat die druk verminder word.

ALGEMEEN.

Bepalings van Ander Verordeninge is van Toepassing.

2. Die bepalings van hierdie verordeninge is ter aanvulling van, en nie ter vervanging van enige ander verordeninge van die Raad nie.

Toepassing van hierdie Verordeninge op Bestaande Persele.

3. Die bepalings van artikels 34, 35, 37, 40, 41, 44, 56, 62, 65(a), 76, 81(2), 96(a), (b), (c), (e), (f) and (g), 99(a) en (c) en 103(a) en (d) is nie op enige perseel wat tans wettiglik vir die opbergung, gebruik of hantering van vlambare vloeistowwe gebruik word, op so 'n wyse van toepassing dat dit meebring dat sodanige perseel herbou, verbou of uitgebrei moet word ten einde aan die bepalings daarvan te voldoen nie, maar wanneer sodanige perseel of 'n gedeelte daarvan herbou, verbou of uitgebrei word, moet sodanige werk ooreenkomsdig die bepalings van hierdie verordeninge verrig word: Met dien verstande dat indien 'n perseel wat wettiglik vir die opbergung, gebruik of hantering van vlambare vloeistowwe gebruik word, van beheer of eienaar verwissel, geen registrasiesertifikaat wat in verband daarmee uitgereik is, hernieu word nie, tensy en Alvorens daar aan die bepalings van bogenoemde artikels voldoen is, en die bepalings van vermelde artikels is dan op sodanige persele van toepassing.

Aansoek om Goedkeuring van Planne.

4.(1) Elke aansoek om die goedkeuring van planne, moet skriftelik by die Raad gedoen word.

(2) Elke sodanige aansoek moet vergezel gaan van 'n plan van die perseel ten opsigte waarvan 'n sertifikaat vereis word, en moet volgens 'n skaal van minstens 1:100 geteken wees, en die volgende in besonderhede aandui —

(a) die perseel, insluitende die opstand daarvan met betrekking tot die aangrensende geboue of bouwerke bokant of onderkant die grond, die binneafmetings in syfers aangegee van enige vertrek, gebou, bouwerk of opbergtenk waarin vlambare vloeistof opgeberg, gebruik of gehanteer moet word, asook 'n beskrywing van die materiale waarmee sodanige vertrek, gebou, bouwerk of opbergtenk gebou is, of gebou gaan word; en

(b) volledige besonderhede, insluitende die terreinligging van enige pomp, onbergtent, pakkamer, menglokaal, pyleiding, droogskoonmaakmasjinerie, spuitlokaal, sputthokkie of ventilasietoerusting.

(3) Every such application shall also be accompanied by a block plan of such premises, drawn to a scale of not less than 1:500, which shall specify —

- (a) the premises and all open spaces with stand numbers thereof and the materials of which such premises are constructed or are to be constructed;
- (b) the stands with numbers thereof immediately adjoining;
- (c) the names of any streets on which the site abuts and the township in which it is situated; and
- (d) the north point.

(4) Where the plan relates to existing premises in respect of which a certificate of registration has been issued and wherein it is proposed to make alterations or additions to any apparatus lawfully used or intended to be used thereon for the storage or handling of flammable liquid, only a ground plan together with such application form and the prescribed charges shall be submitted. Such ground plan shall be drawn to a scale not less than 1:100 and shall show such additions or alterations in relation to such existing premises or apparatus.

(5) All plans shall be —

- (a) signed by the owner or his agent;
- (b) drawn in Indian ink on tracing linen or clear prints on cloth with white ground; and
- (c) coloured with fixed colours as follows:

(i) *Block Plan:*

Proposed premises: Red.

Other existing buildings: Grey or a neutral colour.

Open spaces: Uncoloured.

(ii) *Other Plans:*

Ventilation ducts, trunks or enclosures: Blue.

Storage tanks, pumps, pipelines, dry-cleaning machinery and spray booths: Red.

Buildings in which flammable liquid is to be stored, used or handled: Uncoloured.

Other existing buildings where required: Grey or a neutral colour.

(6) A charge of R3 for every application for approval of a plan or plans shall be paid on submission thereof, and on approval, such plan or plans shall become the property of the Council. On approval of such plans a written notice in accordance with these by-laws shall be issued with such conditions endorsed thereon as are deemed necessary by the Council.

(7) The approval of plans in respect of premises shall in no way imply the acceptance of any responsibility on the part of the Council in regard to such premises.

When Plans are Null and Void.

5. The approval by the Council in terms of section 4 of any plans shall lapse and be of no force and effect if the provisions of these by-laws shall not have been com-

(3) Elke sodanige aansoek moet ook vergesel gaan van 'n blokplan van sodanige perseel, wat volgens 'n skaal van minstens 1:500 geteken is, en waarop die volgende gespesifieer moet word:

- (a) Die persele en alle oop ruimtes en die standplaasnommers daarvan asook die materiaal waarvan sodanige persele gebou is of gebou gaan word;
- (b) die direk aangrensende standplase en hulle nommers;
- (c) die name van strate waaraan die terrein grens en die naam van die dorp waarin dit geleë is; en
- (d) die noordpunt.

(4) Indien die plan betrekking het op bestaande persele ten opsigte waarvan 'n registrasiesertifikaat uitgereik is, en ten opsigte waarvan dit die voorneme is om veranderings of toevoegings aan te bring aan 'n apparaat wat in verband met die opberging of hantering van vlambare vloeistowwe wettiglik daarop gebruik word of wat dit die voorneme is om daarop te gebruik, moet daar slegs 'n grondplan en die voorgeskrewe gelde saam met so 'n aansoekvorm ingedien word. So 'n grondplan moet volgens 'n skaal van minstens 1:100 geteken word, en moet sodanige toevoegings of veranderings met betrekking tot die bestaande perseel of apparaat aandui.

(5) Alle planne moet —

- (a) deur die eienaar of sy agent onderteken word;
- (b) met Indiese ink op natrekklinne geteken of duidelik op 'n wit doek afgedruk wees; en
- (c) soos volg met vaste kleure ingekleur wees;

(i) *Blokplan:*

Voorgestelde perseel: Rooi.

Ander bestaande geboue: Grys of 'n neutrale kleur.

Oop ruimtes: Ongekleurd.

(ii) *Ander Planne:*

Ventilasiepype, hoofleidings of insluitings: Blou.

Opbergtenks, pompe, pyleidings, droogskoonmaakmasjinerie en spuithokkies: Rooi.

Geboue waarin vlambare vloeistowwe opgeberg, gebruik of hanteer word: Ongekleurd.

Ander bestaande geboue waar vereis: Grys of 'n neutrale kleur.

(6) Daar moet 'n vordering van R3 ten opsigte van elke aansoek om goedkeuring van 'n plan of planne, betaal word wanneer dit ingedien word, en nadat dit goedgekeur is, behou die Raad sodanige plan of planne. Wanneer sodanige planne goedgekeur is, word 'n skriftelike kennisgewing uitgereik met sodanige voorwaardes as wat ooreenkomsdig hierdie verordeninge nodig geag word, deur die Raad daarop geëndosseer.

(7) Die goedkeuring van planne ten opsigte van persele beteken geensins dat die Raad enige aanspreeklikheid met betrekking tot sodanige perseel aanvaar nie.

Wanneer Planne van Nul en Gener Waarde is.

5. Die goedkeuring deur die Raad van enige plan kragtens artikel 4 verval en is van nul en gener waarde indien daar nie binne een jaar na die datum van sodanige

plied with within one year after the date of such approval.

Permits.

6.(1) No person shall carry out any spraying operations with flammable liquid in any building or part thereof unless such person is in possession of a spray permit in respect of the said building or part thereof issued in accordance with these by-laws, or store, use or handle flammable liquid on any premises in excess of the undermentioned quantities:

- (a) Class A flammable liquid — a total quantity of 50 l.
- (b) Class B flammable liquid — a total quantity of 400 l, unless such person is in possession of a certificate of registration in respect of such premises issued in terms of these by-laws.

(2) No certificate of registration or spray permit shall be issued in respect of any premises for the storage, use or handling of flammable liquid unless application is made in writing to the Council and accompanied by the prescribed charge as set out in Schedule 1 hereto, and until the provisions of these by-laws have been complied with in respect of such premises.

(3) Such certificate of registration or spray permit may be issued subject to such conditions as are deemed necessary by the Council, having regard to the circumstances pertaining to each application.

(4) Such certificate of registration shall state the maximum amount of each class of flammable liquid permitted to be stored, used or handled, the manner in which such liquid shall be stored, used or handled and the number of pumps, storage tanks and stores permitted on the premises.

(5) Every such certificate of registration shall only be valid for the period terminating on the next succeeding 31st day of December.

(6) No certificate of registration or spray permit, other than a renewal thereof, shall be issued in respect of any premises until the provisions of the by-laws have been complied with and the application therefor has been approved by the Council.

Supply of Flammable Liquid.

7. No person shall —

- (a) supply or deliver or cause or permit to be supplied or delivered flammable liquid in excess of the quantity specified in section 6(1) to any premises, the occupier of which is not in possession of a certificate of registration issued in terms of these by-laws in respect of the said premises; or
- (b) supply or deliver or cause or permit to be supplied or delivered to any premises flammable liquid in excess of the quantity or of a class other than that specified on the certificate of registration relating to such premises.

Exemptions and Requirements: General.

- 8.(1) Notwithstanding anything contained in these by-laws —

goedkeuring aan die bepalings van hierdie verordeninge voldoen is nie.

Permitte.

6.(1) Niemand mag in 'n gebou of 'n gedeelte daarvan met vlambare vloeistowwe spuitwerk verrig nie, tensy hy in besit is van 'n spuitpermit ten opsigte van genoemde gebou of 'n gedeelte daarvan wat ooreenkomsdig hierdie verordeninge uitgereik is of mag, tensy hy 'n registrasiesertifikaat ten opsigte van 'n perseel besit, meer vlambare vloeistof as die volgende hoeveelhede op sodanige perseel opberg, gebruik of hanter nie.

- (a) Vlambare vloeistof, Klas A — altesaam 50 l.
- (b) Vlambare vloeistof, Klas B — altesaam 400 l, tensy sodanige persoon ten opsigte van sodanige perseel in besit is van 'n registrasiesertifikaat vir die perseel kragtens hierdie verordeninge uitgereik.

(2) Daar word geen registrasiesertifikaat of spuitpermit ten opsigte van 'n perseel vir die opberg, gebruik of hantering van vlambare vloeistof uitgereik nie, tensy daar skriftelik by die Raad aansoek gedoen word en die voorgeskrewe gelde soos in Bylae 1 hierby uiteengesit, die aansoek vergesel en alvorens daar aan die bepalings van hierdie verordeninge met betrekking tot sodanige perseel voldoen is.

(3) Sodanige registrasiesertifikaat of spuitpermit kan uitgereik word onderworpe aan sodanige voorwaardes as wat die Raad, met inagneming van die omstandighede wat aan elke aansoek verbonde is, noodsaaklik ag.

(4) Sodanige registrasiesertifikaat moet die grootste hoeveelheid vlambare vloeistof van elke klas wat opgeberg, gebruik of gehanteer mag word, asook die wyse waarop sodanige vloeistof opgeberg, gebruik of gehanteer moet word, en die aantal pompe, opbergtenks en pakkamers wat op die perseel toegelaat word, aangee.

(5) Elke sodanige registrasiesertifikaat is slegs geldig vir die tydperk wat verstryk op die eerste daaropvolgende 31ste dag van Desember.

(6) Daar word geen registrasiesertifikaat of spuitpermit, uitgesonderd 'n hernuwing daarvan, ten opsigte van enige perseel uitgereik, alvorens daar aan die bepalings van hierdie verordeninge voldoen is en die aansoek daarvoor deur die Raad goedgekeur is.

Verskaffing van Vlambare Vloeistowwe.

7. Niemand mag —

- (a) meer vlambare vloeistof as die hoeveelheid wat in artikel 6(1) gespesifieer is, aan 'n perseel waarvan die okkupant nie in besit is van 'n registrasiesertifikaat wat ingevolge die bepalings van hierdie verordeninge ten opsigte van die genoemde perseel uitgereik is nie, verskaf of aflewer of toelaat dat dit verskaf of afgelewer word nie; of
- (b) meer vlambare vloeistof as die hoeveelheid, of vlambare vloeistof van 'n ander klas as dié wat in die registrasiesertifikaat wat betrekking op sodanige perseel het, gespesifieer is, aan 'n perseel verskaf of aflewer of toelaat dat dit verskaf of afgelewer word nie.

Vrystellings en Vereistes: Algemeen.

- 8.(1) Ondanks enigets in hierdie verordeninge vervat —

- (a) flammable liquid shall not be deemed to be stored or conveyed or transported when contained in the fuel tank of a motor vehicle or stationary engine in normal use as such;
- (b) any person may keep any flammable substance such as varnish, lacquer, paint, vulcanising cement or other similar preparations, hydraulic fluides and other similar preparations, liquids constituting or forming part of medicinal, cosmetic and other similar preparations and diesel and heavy furnace fuels on any premises where such substances is entirely contained in sealed metal containers and no container shall be opened on such premises except in the open air or in a store as defined in section 1: Provided that —
- (i) where 1 kl or more of such substances are kept in any room or building, such room or building shall be constructed of non-combustible material and fire appliances shall be installed to the satisfaction of the Chief Fire Officer and the substances shall be situated in such a position that they shall not impede the escape of any person or animal from the premises in case of fire;
 - (ii) where the total quantity of such substances is in excess of 5 kl such excess quantities shall be kept in a separate non-combustible room or building or store;
 - (iii) such room or building shall be constructed in such a manner and be surrounded by walls or bunds of such a character that the substances contained therein cannot escape therefrom, such walls or bunds to be of sufficient capacity to contain not less than 75 per cent of the maximum quantity capable of being stored therein;
 - (iv) the room or building shall be ventilated so as to adequately prevent the accumulation of flammable vapour within all portions of such room or building;
 - (v) the room or building shall be situated in such a position that it is not likely to endanger any other adjoining room, building or premises in case of fire;
 - (vi) the words "DANGER — NO SMOKING" in both official languages shall be prominently displayed in letters not less than 150 mm in height outside the entrance to every such room or building and shall at all times be maintained in such positions and in a legible condition.
 - (vii) no container shall be opened in such room or building;
 - (viii) fire appliances shall be installed to the satisfaction of the Chief Fire Officer;
 - (ix) the Chief Fire Officer may require other additional safety precautions to be complied with, having regard to the particular circumstances of any case.

Exemptions and Requirements: Class C Flammable Liquid.

(2)(a) The exemption referred to in subsection (1)(a) and (b) shall *mutatis mutandis* apply to Class C flammable liquid contained in drums and not exceeding 1 kl

- (a) word daar nie geag dat vlambare vloeistof opgeberg of vervoer word wanneer dit in die brandstoftenk van 'n motorvoertuig of 'n vasstaande masjien is, wat as sodanig in normale gebruik is nie;
- (b) kan enigiemand enige vlambare stof soos vernis, lakvernis, verf, vulkaniseergom of ander soortgelyke preparate, hidrouliese vloeistowwe en ander soortgelyke preparate, vloeistowwe wat of self of deel uitmaak van geneeskundige, skoonheids- en ander soortgelyke preparate, en diesel en grootoond stowwe aanhou op enige perseel waar sodanige stowwe geheel en al in verscölde metaalhouers gehou word en sodanige houer nie op die perseel oopgemaak word nie, behalwe in die buitelug of in 'n pakkamer soos omskryf in artikel 1: Met dien verstande dat —
- (i) indien 1 kl of meer van sodanige stowwe in 'n vertrek of gebou gehou word, so 'n vertrek of gebou van nie-brandbare materiaal gebou moet wees, brandblustoestelle tot voldoening van die Brandweerhoof aangebring moet word, en die stowwe sodanig gestoor moet word dat dit nie die ontvlugting van mense of diere in geval van 'n brand belemmer nie;
 - (ii) indien die totale hoeveelheid van sodanige stowwe meer as 5 kl is, sodanige addisionele hoeveelhede in 'n afsonderlike nie-brandbare vertrek of gebou of pakkamer gehou moet word;
 - (iii) so 'n vertrek of gebou op so 'n wyse opgerig en omring moet wees van mure of walle van sodanige aard dat die stowwe wat daarin vervat is, nie daaruit kan ontsnap nie en sodanige mure of walle se inhoudsvermoë moet voldoende wees om minstens 75 persent van die grootste hoeveelheid stowwe wat daarin opgeberg kan word, te hou;
 - (iv) die vertrek of gebou sodanig gevентileer moet word om die ophoping van vlambare damp in enige gedeelte van sodanige vertrek of gebou voldoende te voorkom;
 - (v) die vertrek of gebou sodanig geleë moet wees dat dit geen gevaar inhoud vir aangrensende vertrekkie, geboue of persele in geval van 'n brand nie;
 - (vi) opvallende kennisgewings met die woorde "GEVAAR — ROOK VERBODE" duidelik in albei amptelike tale daarop, in letters wat minstens 150 mm hoog is, buite alle ingange tot sodanige vertrek of gebou opgerig moet word, en te alle tye op dié plekke in 'n leesbare toestand in stand gehou moet word;
 - (vii) geen houer in sodanige vertrek of gebou oopgemaak mag word nie;
 - (viii) Brandblussers tot voldoening van die Brandweerhoof geïnstalleer moet word;
 - (ix) die Brandweerhoof ander addisionele veiligheidsmaatreëls kan vereis met inagneming van die besondere omstandighede van enige geval.

Uitsonderings en Vereistes: Klas C Vlambare Vloeistowwe.

(2)(a) Die uitsondering waarnaar in subartikel (1)(a) en (b) verwys word, is *mutatis mutandis* van toepassing op Klas C, vlambare vloeistowwe wat in drom-

on any premises. In the event of the quantity exceeding 1 kl the provisions of subsection (1)(b)(i) to (ix) inclusive shall *mutatis mutandis* apply.

(b) In the case of bulk storage of liquids, oils or other substances which are or are to be stored or used for heating or any other purpose, the procedure and provisions of sections 4, 5 and 33 to 46 inclusive shall be followed and shall *mutatis mutandis* apply, save and except that with reference to section 35(2) the Chief Fire Officer may in his discretion permit above ground storage tanks, subject to the following conditions:

- (i) The capacity of any tank containing liquids with a true flash-point of more than 55 °C but under 90 °C and not installed in a building shall not exceed 2,3 kl and such tank shall not be positioned within 6 m of any protected work or within 4,5 m of any public thoroughfare.
- (ii) The capacity of any tank containing liquids, oils or other substances with a true flash-point of over 90 °C and not installed in a building, and any part of which is placed within a distance of 6 m from any part of a building, shall not exceed 23 kl and if such tank is not so placed that the whole of it is below the surface of the adjoining ground, the following requirements shall be complied with:
 - (aa) If the tank is placed within a distance of 2 m from the building, unless the part of the wall of the building within 6 m from the tank is of fire-resisting construction and impervious, it shall be enclosed in a tank chamber.
 - (bb) If the tank is placed at a distance of more than 2 m but within a distance of 6 m from the building it shall be placed in a tank chamber unless either the part of the wall of the building within 6 m from the tank and any opening therein shall be of fire-resisting construction or a screen wall of fire-resisting construction shall have been erected between the tank and the building: Provided that such screen wall shall have been erected co-extensive with the tank so as to project laterally for a distance of not less than 1 m at each extremity of such tank and such screen wall shall have foundations of adequate strength, and throughout its length shall have been erected above the ground to a height of not less than 1 m above the uppermost part of the tank.
 - (iii) If the storage tank is placed so that the whole of it is below the surface of the adjoining ground it shall be covered by a roof of fire-resisting construction.

(c) All tanks shall be firmly placed in steel, concrete or brick saddles of adequate strength and stability or some other approved method. The Chief Fire Officer may require other additional safety precautions he may deems necessary to be complied with appertaining either to the tank or to apparatus or other equipment using fuel from such tank for any purpose whatsoever. Fire extinguishing appliances shall be installed to the satisfaction of the Chief Fire Officer.

me aangehou word en nie 1 kl op enige perseel oorskry nie. Waar die hoeveelheid 1 kl oorskry, is die bepalings van subartikel (1)(b)(i) tot en met (ix) *mutatis mutandis* van toepassing.

(b) In die geval van die massa opberging van vloeistowwe, olie of ander stowwe wat geberg of gebruik word of geberg of gebruik sal word vir verhitting of vir enige ander doel, moet die prosedure en bepalings van artikels 4, 5 en 33 tot en met 46 gevvolg word en is *mutatis mutandis* van toepassing, behalwe dat die Brandweerhoof met verwysing na artikel 35(2) na goeddunke bogondse opgaartenks kan toelaat onderworpe aan die volgende voorwaarde:

- (i) Die inhoudsvermoë van enige tenk wat vloeistowwe met 'n flitspunt van meer as 55°C maar minder as 90°C bevat, en nie in 'n gebou geïnstalleer is nie, mag nie 2,3 kl oorskry nie, en sodanige tenk mag nie nader as 6 m van enige beskermd gebou of 4,5 m van enige openbare deurgang geleë wees nie.
- (ii) Die inhoudsvermoë van enige tenk wat vloeistowwe, olie of ander stowwe met 'n flitspunt van meer as 90°C bevat en nie in 'n gebou geïnstalleer is nie, en waarvan enige deel nie meer as 6 m van enige deel van 'n gebou geleë is nie, mag nie 23 kl oorskry nie, en indien sodanige tenk so geplaas is dat dit nie heeltemal onder die omliggende grondhoogte geleë is nie, moet daar aan die volgende vereistes voldoen word:
 - (aa) Indien die tenk binne 2 m van 'n gebou geleë is, tensy die deel van die muur van die gebou wat binne 6 m van die tenk geleë is van brandbestande materiaal gebou en syferdig is, moet dit in 'n tenkkamer gehou word.
 - (bb) Indien die tenk meer as 2 m maar minder as 6 m van 'n gebou staan, moet dit in 'n tenkkamer geplaas word tensy dié gedeelte van die muur van die gebou binne 6 m van die tenk en enige opening daarin van brandbestande konstruksie is of 'n skeidsmuur van brandbestande materiaal tussen die tenk en die gebou opgerig word: Met dien verstande dat sodanige skeidsmuur gelykydig met die tenk opgerig moet word sodat dit minstens 1 m aan weerskante van die uiterste van die tenk verbysteek, en sodanige skeidsmuur fondamente van voldoende sterkte moet hê en vir die volle lengte van die muur bokant die grondoppervlakte uitgebou moet wees tot 'n hoogte van minstens 1 m bokant die hoogste punt van die tenk.
 - (iii) Indien die opgaartenk so geplaas is dat dit heeltemal onder die oppervlakte van die omliggende grond geleë is, moet dit bedek word met 'n dak van brandbestande materiaal.

(c) Alle tenks moet stewig geplaas word in staal, beton of steenstutte van voldoende sterkte en stabiliteit of enige ander goedgekeurde metode. Die Brandweerhoof kan ander bykomende veiligheidsmaatreëls wat hy nodig ag en waaraan voldoen moet word, ople met betrekking tot die tenk of apparaat, of ander toerusting wat brandstof uit sodanige tenk gebruik vir watter doel ook al. Brandblusapparaat moet tot voldoening van die Brandweerhoof geïnstalleer word.

Conditions of Certificate of Registration.

- 9.(1) No person shall store, use or handle or cause to be stored, used or handled on any premises —
- any quantity of flammable liquid in excess of the amount specified in the certificate of registration relating to such premises;
 - any flammable liquid other than the class or classes specified in the certificate of registration relating to such premises;
 - any flammable liquid in a manner other than the manner specified in the certificate of registration relating to such premises; or
 - a greater number of pumps, storage tanks or stores than specified in the certificate of registration relating to such premises.

(2) Any person in lawful possession of any certificate of registration may make written application to the Council for the amendment of the total quantity or the class of flammable liquid specified in such certificate. Such application shall be granted by the Council only when the proposed amendment is in conformity with the provisions of these by-laws. Where the Council has granted any such application, such person shall surrender the certificate of registration to the Council for amendment.

Display of Certificate of Registration.

10. Any person to whom a certificate of registration has been issued shall cause such certificate to be affixed and maintained in a conspicuous position on the registered premises. Such certificate shall be maintained at all times in such position and in a legible condition.

Renewal of Certificate of Registration or Spray Permit.

11. Application for the annual renewal of a certificate of registration or spray permit shall be made not later than the 15th day of November of the year prior to that for which such renewal is required, on a form to be provided by the Council and shall be accompanied by the prescribed charge as set out in Schedule 1 hereto. No plans of the premises in terms of section 4 shall be required in the case of a renewal of a certificate of registration or spray permit, unless called for at the discretion of the Council.

Transfer of Certificate of Registration or Spray Permit.

12.(1) A certificate of registration or spray permit may be transferred from one person to another.

(2) The person desiring such transfer shall apply in writing to the Council on a form to be provided by the Council for such purpose. Such application shall be accompanied by the prescribed charge as set out in Schedule 1 hereto, together with the certificate of registration or spray permit relating to the premises in respect of which such transfer is desired.

(3) No certificate of registration or spray permit shall be transferable from one premises to another.

Temporary Storage.

13.(1) The Council may in writing exempt from the provisions of section 6 for such period as it may deem necessary any person wishing to store more than 50 l of Class A flammable liquid or more than 400 l of

Voorwaardes van die Registrasiesertifikat.

- 9.(1) Niemand mag op enige perseel —
- meer vlambare vloeistof as die hoeveelheid wat op die registrasiesertifikaat wat op sodanige perseel betrekking het, aangegee word;
 - enige vlambare vloeistof, uitgesonderd die klas of klasse wat op die registrasiesertifikaat wat op sodanige perseel betrekking het, aangegee word;
 - enige vlambare vloeistof op 'n ander wyse as dié wat op die registrasiesertifikaat wat op sodanige perseel betrekking het, aangedui word; of
 - meer pompe, opbergtenks, of pakkamers as dié wat op die registrasiesertifikat wat op sodanige perseel betrekking het, aangegee word;
- opberg, gebruik of hanteer of laat opberg, gebruik of hanteer nie.
- (2) Enigiemand wat in wettige besit van 'n registrasiesertifikaat is, kan by die Raad skriftelik aansoek doen om die totale hoeveelheid of die klas vlambare vloeistof wat op so 'n sertifikaat aangegee word, te laat wysig. Die Raad staan so 'n aansoek slegs toe indien die voorgestelde wysiging voldoen aan die bepalings van hierdie verordeninge. Indien die Raad so 'n aansoek toegestaan het, moet so 'n persoon die registrasiesertifikaat by die Raad indien sodat dit gewysig kan word.

Vertoning van Registrasiesertifikaat.

10. Enigiemand aan wie 'n registrasiesertifikaat uitgereik is, moet die sertifikaat op 'n opvallende plek op die geregistreerde perseel laat aanbring en onderhou. Sodanige sertifikaat moet te alle tye in 'n leesbare toestand op dié plek in stand gehou word.

Hernuwing van Registrasiesertifikaat of Spuitpermit.

11. Daar moet uiterlik op die 15de dag van November van die jaar wat die jaar voorafgaan ten opsigte waarvan die hernuwing benodig word, aansoek om die hernuwing van die registrasiesertifikaat of spuitpermit gedoen word op 'n vorm wat deur die Raad verskaf word, en die voorgeskrewe geld, soos in Bylae 1 hierby uiteengesit is, moet die aansoek vergesel. Tensy die Raad na goeddunke dit verlang, word daar in die geval van 'n hernuwing van 'n registrasiesertifikaat of spuitpermit geen plan van die perseel kragtens artikel 4 vereis nie.

Oordrag van Registrasiesertifikaat of Spuitpermit.

12.(1) 'n Registrasiesertifikaat of spuitpermit mag deur een persoon aan 'n ander oorgedra word.

(2) Die persoon wat sodanige oordrag verlang, moet skriftelik by die Raad aansoek daarom doen op 'n vorm wat die Raad vir die doel verskaf. So 'n aansoek moet vergesel gaan van die voorgeskrewe geld, soos in Bylae 1 hierby uiteengesit is, asook van die registrasiesertifikaat of spuitpermit wat betrekking het op die perseel ten opsigte waarvan sodanige oordrag verlang word.

(3) Geen registrasiesertifikaat of spuitpermit is van een perseel na 'n ander oordraagbaar nie.

Tydelike Opbergung.

13.(1) Die Raad kan enigeen wat verlang om meer as 50 l vlambare vloeistof Klas A, of meer as 400 l vlambare vloeistof Klas B, wat vir of in verband met uitgrawingswerk, bouwerk, padaanleg of ander soortgelyke werk van 'n tydelike aard benodig word, op te berg,

Class B flammable liquid required for or in connection with any excavation, building, road making or other like operations of a temporary nature: Provided that —

- (a) application is submitted in writing to the Council on a form to be obtained from the Council;
- (b) suitable provision has been made to surround the containers of such flammable liquid by walls or bunds of such a character that such flammable liquid cannot escape from such walls or bunds either under the action of fire or otherwise; and
- (c) at least one efficient chemical fire extinguisher of the dry chemical type as set out in section 26 has been provided.

(2) Any person to whom an exemption has been granted in terms of subsection (1) shall ensure that at all times —

- (a) all reasonable precautions are taken to prevent any fire, flame or other agency likely to ignite flammable liquid or flammable liquid vapour being brought into contact with such flammable liquid or its vapour;
- (b) such flammable liquid is not placed within 4,5 m of any protected work or public thoroughfare; and
- (c) the provisions of subsection (1)(b) and (c) are observed.

Installation and Erection.

14.(1) Immediately the installation of any pump, storage tank, filling device, dry-cleaning room, store, mixing room, spray room or other premises intended for the storage, use, or handling of flammable liquid has been completed, the occupier of the premises shall notify the Council in writing on a form to be obtained from it of the date on which the work will be ready for inspection.

(2) No person shall use or cause or permit to be used such pump, storage tank, filling device, dry-cleaning room, store, mixing room, spray room or other premises for the storage, use or handling of flammable liquid until such person is in possession of a certificate of registration relating thereto.

Additions and Alterations to Registered Premises.

15.(1) No additions or alterations to any existing registered premises shall be made unless and until a plan of the existing premises, together with the proposed work, shall have been submitted to the Council and approved by it in writing.

(2) Such plan shall be in accordance with the provisions of section 4.

Removal and Dismantling.

16.(1) Any person who removes or causes or permits to be removed any pump, storage tank or filling device from any registered premises, other than a bulk depot, shall give notice of such removal in writing to the Council on a form to be obtained from it.

(2) The removal of any such pump, tank or filling device from any registered premises shall *ipso facto* cancel the certificate of registration insofar as it refers to such pump, tank or filling device, as the case may be,

skriftelik vir sodanige tydperk as wat hy dit nodig ag, van die bepalings van artikel 6, vrystel: Met dien verstande dat —

- (a) daar skriftelik op 'n vorm wat van die Raad verkrybaar is, by die Raad aansoek gedoen word;
- (b) daar behoorlik voorsorg getref is om die houers van sodanige vlambare vloeistof te omring met mure of walle van so 'n aard dat die vlambare vloeistof nie ten gevolge van brand of andersins, deur die mure of walle kan ontsnap nie; en
- (c) daar minstens een doeltreffende chemiese brandblustoestel van die droë chemiese tipe, soos in artikel 26 uiteengesit is, verskaf word.

(2) Enigiemand aan wie daar 'n vrystelling kragtens subartikel (1) verleen is, moet te alle tye sorg dat —

- (a) daar alle redelike voorsorg getref word om te voor-kom dat 'n brand, 'n vlam of 'n ander middel wat vlambare vloeistof of vloeistofdampe aan die brand kan laat slaan, in aanraking met sodanige vlambare vloeistof of die dampe daarvan gebring word;
- (b) sodanige vlambare vloeistof nie binne 4,5 m van 'n beskermd gebou of openbare verkeersweg geplaas word nie; en
- (c) die bepalings van subartikel (1)(b) en (c) nagekom word.

Installasie en Oprigting.

14.(1) Onmiddellik nadat 'n pomp, opbergtenk, vultoestel, droogskoonmaaklokaal, pakkamer, menglokaal, spuitlokaal of ander perseel wat vir die opberging, gebruik of hantering van vlambare vloeistof bedoel is, klaar opgerig is, moet die okkupant van die perseel die Raad skriftelik op 'n vorm wat by die Raad verkrybaar is, verwittig van die datum waarop die werk vir inspeksie gereed is.

(2) Niemand mag so 'n pomp, opbergtenk, vultoestel, droogskoonmaaklokaal, pakkamer, menglokaal, spuitlokaal of ander perseel vir die opberging, gebruik of hantering van vlambare vloeistof gebruik, laat gebruik, of toelaat dat dit daarvoor gebruik word nie, alvorens so iemand 'n registrasiesertifikaat wat daarop betrekking het, besit.

Aanbousels en Veranderings aan 'n Geregistreerde Perseel.

15.(1) Geen aanbousel of verandering mag aan enige bestaande geregistreerde perseel aangebring word nie, tensy en alvorens 'n plan van die bestaande perseel, asook van die voorgestelde werk, by die Raad ingedien en skriftelik deur hom goedgekeur is.

(2) Sodanige plan moet ooreenkomsdig die bepalings van artikel 4 wees.

Verwydering en Demontering.

16.(1) Enigiemand wat 'n pomp, opbergtenk of vultoestel van 'n geregistreerde perseel, uitgesonderd 'n grootmaatdepot, verwyder, laat verwyder, of toelaat dat dit verwyder word, moet die Raad skriftelik daarvan in kennis stel op 'n vorm wat by die Raad verkrybaar is.

(2) Indien so 'n pomp, tenk of vultoestel van 'n geregistreerde perseel verwyder word, verval die registrasiesertifikaat *ipso facto* vir sover dit, na gelang van die geval, betrekking het op so 'n pomp, tenk of vultoestel,

together with any other authority including any exemption granted in terms of these by-laws and no such pump, tank or filling device shall be re-erected on such premises unless and until a new certificate of registration has been obtained in the manner provided in terms of these by-laws: Provided that the provisions of this section shall not apply in respect of any such pump, storage tank or filling device which is temporarily removed for the purpose of effecting repairs thereto.

Storage, Use and Handling on Registered Premises Prohibited in Certain Circumstances.

17. Except as otherwise provided in these by-laws, no person shall store, use or handle, or permit or cause to be stored, used or handled any flammable liquid on any registered premises —

- (a) where such flammable liquid or its vapour comes or is likely to come into contact with any fire, flame, naked light or other agency likely to ignite such flammable liquid or its vapour;
- (b) unless such premises are so situated or constructed or so protected by surrounding walls as not to expose any adjoining premises, room, building, or other property to the risk of danger from fire;
- (c) so situated as to prevent or impede the escape of any person or animal in the case of fire or otherwise;
- (d) unless all equipment and apparatus used on such premises for the storage, use or handling of flammable liquid is maintained in good and proper order and free from leakage of flammable liquid; or
- (e) unless such person has taken all due precautions for the prevention of accidents by fire or explosion on such premises, and for the prevention of unauthorized persons obtaining access to the flammable liquid kept thereon.

Prohibition of Certain Acts.

18. No person who stores, uses or handles or causes or permits to be stored, used or handled any flammable liquid on any premises shall do or cause or permit to be done any act which tends or is likely to cause fire or explosion.

Notice to Discontinue Dangerous Method.

19.(1) Where on inspection of any premises it appears that any method of storage, use, transport or handling of flammable liquid is in conflict with the provisions of these by-laws and is calculated to endanger the safety of the public or of any person employed in or on such premises, any authorized officer of the Council may require the immediate discontinuance of such method or the removal of the flammable liquid to a place of safekeeping.

(2) Any person failing to comply with any instruction of any authorized officer of the Council, issued in terms of this section, shall be guilty of an offence under these by-laws.

Flammable Liquid Escaping into Drains.

20. No person shall cause or permit flammable liquid to enter any sewer or inlet or drain communicating with any sewer or any surface water drain.

asook enige ander magtiging, insluitende 'n vrystelling, wat kragtens hierdie verordeninge toegestaan is, en geen sodanige pomp, tenk of vultoestel mag weer op die terrein opgerig word nie, tensy en alvorens 'n nuwe registrasiesertifikaat verkry is op die wyse wat kragtens hierdie verordeninge bepaal word: Met dien verstande dat die bepalings van hierdie artikel nie van toepassing is in die geval van 'n pomp, opbergtenk of vultoestel wat tydelik verwyder word met die doel om herstelwerk daaraan te verrig nie.

Opbergung, Gebruik en Hantering op Geregistreerde Perseel word onder Sekere omstandighede Verbied.

17. Behoudens andersluidende bepalings in hierdie verordeninge vervat, mag niemand vlambare vloeistof op 'n geregistreerde perseel opberg, gebruik of hanteer, laat opberg, gebruik of hanteer nie —

- (a) indien sodanige vlambare vloeistof of die dampe daarvan met enige vuur, vlam, oop lig, of 'n ander middel wat sodanige vlambare vloeistof of die dampe daarvan aan die brand kan laat slaan, in aanraking kom, of moontlik daarmee in aanraking kan kom;
- (b) tensy sodanige perseel aldus geleë of gebou is, of so deur ringmure beskerm word, dat dit geen aangrensende perseel, vertrek, gebou of ander eiendom aan brand blootstel nie;
- (c) indien dit so geleë is dat dit die ontkoming van 'n persoon of dier in die geval van brand, of andersins, verhinder of belemmer;
- (d) tensy alle toerusting en apparate wat in sodanige perseel vir die opbergung, gebruik of hantering van vlambare vloeistof, gebruik word behoorlik en deeglik onderhou word, en daar gesorg word dat geen vlambare vloeistof daar uitlek nie; of
- (e) tensy sodanige persoon alle behoorlike voorsorg getref het om ongelukke weens brand of ontploffing op sodanige perseel te voorkom en te verhoed dat ongemagtigde persone toegang verkry tot die vlambare vloeistof wat daarop gehou word.

Sekere Dade word Verbied.

18. Niemand wat vlambare vloeistof op 'n perseel opberg, gebruik of hanteer, dit daar laat opberg, gebruik of hanteer, of toelaat dat dit geskied, mag 'n daad verrig, of toelaat dat dit verrig word, wat tot brand of 'n ontploffing kan lei, of wat dit moontlik kan veroorsaak nie.

Kennisgewing om 'n Gevaarlike Metode te Staak.

19.(1) Indien daar by ondersoek van 'n perseel blyk dat 'n metode waarvolgens vlambare vloeistof opgeberg, gebruik, vervoer of gehanteer word, in stryd met die bepalings van hierdie verordeninge is, en daar geag word dat dit die publiek of iemand wat in of op sodanige perseel werkzaam is, aan gevaar blootstel, kan enige gemagtigde beampete van die Raad eis dat sodanige metode onmiddellik gestaak word, of dat die vlambare vloeistof na 'n plek vir veilige bewaring verwyder word.

(2) Enigiemand wat in gebreke bly om aan 'n opdrag van 'n gemagtigde beampete van die Raad, wat kragtens die bepalings van hierdie artikel uitgereik is, te voldoen, is ingevolge hierdie verordeninge skuldig aan 'n misdryf.

Vlambare Vloeistof mag nie in Riole inloop nie.

20. Niemand mag toelaat dat vlambare vloeistof in 'n riool of 'n inloop- of afloopvoor wat na 'n riool of 'n watervoer lei, inloop nie.

Prohibition against Devices and Pumps in Basements.

21. No person shall use or cause or permit to be used in any basement any device for spraying flammable liquid or any pump or other device for the issue or transfer of flammable liquid to vehicles or containers.

Filling Operations.

22.(1) No person shall transfer, other than at a bulk depot, any flammable liquid from or to any road tank wagon unless such transfer is carried out under seal and in the case of such wagon the engine thereof is stopped.

(2) The refuelling of aircraft at an aerodrome or landing ground may be performed from a road tank wagon equipped with an approved power pump: Provided that the engine or engines of such aircraft is or are stopped.

Filling on or across Public Sidewalks.

23. No person shall —

- (a) take on or across any public sidewalk or cause or permit to be so taken the hose of a pump for the purpose of replenishing any vehicle or container with flammable liquid; or
- (b) so replenish or cause or permit to be so replenished any vehicle or container which is standing on any public sidewalk.

Replenished Fuel Tanks.

24.(1) No person shall —

- (a) upon any registered premises strike a match or smoke a pipe, cigar or cigarette or ignite a lighter or other similar contrivance or approach with any fire, flame, naked light or other agency likely to ignite flammable liquid or its vapour within a distance of 3 m of any fuel tank of any motor vehicle whilst such fuel tank is being replenished or is open; or
- (b) replenish or permit to be replenished any such fuel tank while the engine of such motor vehicle is in motion.

(2) All registered premises shall have prominent notice boards bearing the words "DANGER — NO SMOKING" in letters not less than 75 mm in height in both official languages erected and such notice boards shall be maintained in such position and in a legible condition.

Replenishing of Public Omnibuses.

25. No person shall replenish or cause or permit to be replenished the fuel tank of any motor omnibus or carry or cause or permit to be carried any flammable liquid in or on any motor omnibus except in the fuel tank thereof whilst any person, other than the driver or person responsible therefor, is within or upon such omnibus.

Fire Appliances.

26.(1) Except where otherwise provided in these by-laws, the person to whom the certificate of registration or permit has been issued in terms of these by-laws shall install or cause to be installed on all premises to which such certificate or permit refers in an easily accessible

Verbod op Toestelle en Pompe in Kelderverdiepings.

21. Niemand mag 'n toestel om vlambare vloeistof mee te spuit, of 'n pomp of 'n ander toestel om vlambare vloeistof aan voertuie of houers te lewer of daarheen oor te bring, in 'n kelderverdieping gebruik, laat gebruik of toelaat dat dit daar gebruik word nie.

Vulwerksaamhede.

22.(1) Niemand mag, elders as by 'n grootmaatdepot vlambare vloeistof van of na 'n tenkvragmotor oorplaas, tensy dit by wyse van verseëerde oorplasing geskied, en die enjin van so 'n tenkvragmotor afgeskakel is.

(2) Brandstof kan aan 'n vliegtuig op 'n lughawe of 'n landingsplek vanuit 'n tenkvragmotor wat met 'n gedgekeurde kragpomp toegerus is, voorsien word: Met dien verstande dat die enjin of enjins van sodanige vliegtuig afgeskakel is.

Vulwerksaamhede op of oor Openbare Sypaadjies.

23. Niemand mag —

- (a) die slang van 'n pomp op of oor 'n openbare sypaadjie gebruik, laat gebruik of toelaat dat dit aldus gebruik word, met die doel om 'n voertuig of houer met vlambare vloeistof vol te maak nie; of
- (b) 'n voertuig of houer wat op 'n openbare sypaadjie staan, aldus volmaak of laat volmaak of toelaat dat dit volgemaak word nie.

Brandstoffentanks wat Volgemaak Word.

24.(1) Niemand mag —

- (a) op 'n geregistreerde perseel, 'n vuurhoutjie trek, of 'n pyp, sigaar of sigaret rook, of 'n sigaretaansteker of 'n ander soortgelyke toestel aan die brand steek, of met enige vuur, vlam, oop lig of ander middel wat moontlik vlambare vloeistof of die dampe daarvan aan die brand kan laat slaan, binne 3 m van 'n motorvoertuig se brandstoffentank af kom, terwyl sodanige tenk volgemaak word of oopstaan nie; of
- (b) so 'n brandstoffentank volmaak of toelaat dat dit volgemaak word terwyl die enjin van so 'n motorvoertuig nog loop nie.

(2) Alle geregistreerde persele moet voorsien wees van opvallende kennisgewings met die woorde "GEVAAR — ROOK VERBODE" duidelik in albei amptelike tale daarop in letters wat minstens 75 mm hoog is en moet te alle tye op so 'n plek en in 'n leesbare toestand in stand gehou word.

Openbare Motorbusse wat van Brandstof voorsien Word.

25. Niemand mag, terwyl daar enige ander persoon, uitgesonderd die bestuurder of die persoon wat daarvoor verantwoordelik is, in of op 'n motorbus is, die brandstoffentank van sodanige motorbus volmaak, laat volmaak of toelaat dat dit volgemaak word, of toelaat dat vlambare vloeistof in of op sodanige motorbus vervoer, laat vervoer, of toelaat dat dit aldus vervoer word, uitgesonderd in die brandstoffentank daarvan nie.

Brandblustoestelle.

16.(1) Behoudens andersluidende bepalings in hierdie verordeninge vervat, moet die persoon aan wie die registrasiesertifikaat of permit kragtens hierdie verordeninge uitgereik is, op alle persele waarop sodanige sertifikaat of permit betrekking het, op 'n maklik toeganklike en sigbare plek aan 'n muur of op 'n ander geskikte

and visible position on a wall or other suitable position not less than 1 m above the level of the floor of the premises, fire extinguishers and fire buckets on the following minimum scale:

One such fire extinguisher of the dry chemical type and two such fires buckets shall be installed for each filling station or single pump or other filling device; each flammable liquid store, each dry-cleaning room, each mixing room or each spray room on the premises.

(2) Such fire extinguishers shall be efficient dry chemical fire extinguishers, each of a capacity of not less than 9 kg: Provided that where the Chief Fire Officer is of the opinion, having regard to the particular circumstances of any case, that dry chemical fire extinguishers are not adequate, such other fire extinguishers as he may consider to be required by the particular hazard, shall be installed.

(3) Every fire bucket shall be constructed of metal and shall be of a capacity of not less than 9 l and painted red with the word "FIRE" painted in white and legibly maintained thereon and filled with dry sand.

(4) Where, in terms of these by-laws, any chemical fire extinguisher is required to be installed, such extinguisher shall be a vessel or machine manufactured as a fire appliance and shall withstand internal hydraulic tests approved of by the Chief Fire Officer.

(5) The person to whom a certificate of registration, spray permit or transport permit has been issued in terms of these by-laws shall maintain at all times on the premises or vehicle to which such certificate or permit relates —

- (a) all fire extinguishers, buckets, appliances and alarms in accordance with the provisions of these by-laws; and
- (b) all such equipment in good order and ready for immediate use.

Examination of Fire Appliances.

27.(1) Where, in terms of these by-laws, any chemical fire extinguisher, fire fighting equipment, or fire alarm has been installed on any premises, the occupier of such premises shall cause such fire extinguisher, equipment or alarm to be examined once every 12 months by the manufacturers thereof or their authorized representative or other qualified person.

(2) Every such fire extinguisher, all such equipment and every such alarm shall bear a label on which such person examining is shall endorse his name, the date of examination and the condition, in his opinion, of the fire extinguisher, equipment or alarm at that date.

Reporting Accidents.

28. The occupier of any premises shall immediately report to the Council any fire or accident involving flammable liquid that has occurred in connection with any such premises where such fire or accident has resulted in damage to any property or injury to any person.

plek wat minstens 1 m bokant die oppervlak van die perseel se vloer is, brandblustoestelle en brandemmers, volgens die onderstaande minimum skaal aanbring of laat aanbring:

Een sodanige brandblustoestel van die droë chemiese tipe en twee sodanige brandemmers moet ten opsigte van elke vulstasie, of enkele pomp, ander vultoestel, vlambare vloeistof pakkamer, droogskoonmaaklokaal, menglokaal, of spuitlokaal op die perseel aangebring word.

(2) Sodanige brandblustoestelle moet doeltreffende droë chemiese brandblustoestelle wees wat elkeen 'n inhoudsvermoë van minstens 9 kg het: Met dien verstande dat waar die Brandweerhoof, met inagneming van die besondere omstandighede van 'n geval, van mening is dat die brandblustoestelle van die droë chemiese tipe nie voldoende is nie, moet sodanige ander brandblustoestelle wat hy vir die besondere gevaaar nodig ag, geïnstalleer word.

(3) Elke brandemmer moet van metaal vervaardig wees met 'n inhoudsvermoë van minstens 9 l, en rooi geverf met die woord "BRAND" in wit daarop geverf, en moet leesbaar in stand gehou word en met droë sand gevul wees.

(4) Waar, daar kragtens hierdie verordeninge 'n chemiese brandblustoestel aangebring moet word, moet so 'n brandblustoestel 'n houer of apparaat wees wat as 'n brandblustoestel vervaardig is, en moet dit interne hidrouliese toets wat deur die Brandweerhoof goedgekeur is, weerstaan.

(5) Die persoon aan wie daar 'n registrasiesertifikaat, 'n spuitpermit of 'n vervoerpermit kragtens hierdie verordeninge uitgereik is, moet te alle tye op die perseel of voertuig waarop sodanige sertifikaat of permit van toepassing is —

- (a) alle brandblustoestelle, brandemmers, apparate en alarms ooreenkomsdig die bepalings van hierdie verordeninge; en
- (b) al sodanige toerusting in 'n goeie toestand en gereed vir onmiddellike gebruik, in stand hou.

Ondersoek van Brandblustoestelle.

27.(1) Waar daar ingevolge hierdie verordeninge 'n chemiese brandblustoestel, brandweertoerusting of brandalarm op 'n perseel aangebring is, moet die okkupant van sodanige perseel so 'n brandblustoestel, toerusting of alarm een maal elke 12 maande deur die vervaardigers daarvan, of deur hulle gemagtigde verteenwoordigers of deur 'n ander gekwalifieerde persoon, laat ondersoek.

(2) Elke sodanige brandblustoestel, toerusting en alarm moet 'n etiket aanhê waarop die persoon wat dit ondersoek, sy naam asook die datum van die ondersoek en die besonderhede in verband met die toestand waarin die brandblustoestel, toerusting of alarm op daardie tydstip na sy mening verkeer, moet aanteken.

Ongelukke moet Aangemeld word.

28. Die okkupant van 'n perseel moet enige brand of ongeluk waarby vlambare vloeistof betrokke is en wat plaasgevind het in verband met enige sodanige perseel waar so 'n brand of ongeluk skade aan ciendom berokken of beserings aan personele veroorsaak het, onmiddellik by die Raad aanmeld.

Rules to be Observed on Premises not Required to be Registered in Terms of these By-laws.

29.(1) No person shall store, use or handle or cause or permit to be stored, used or handled any flammable liquid on any unregistered premises unless such flammable liquid is stored, used or handled in such a place or in such a manner that —

- (a) no flammable liquid or its vapour comes or is likely to come into contact with any fire, flame or naked light or other agency likely to ignite such flammable liquid or its vapour; or
- (b) in the case of fire the escape of persons or animals will not be prevented or impeded.

(2) No person shall use or handle or cause or permit to be used or handled any flammable liquid on unregistered premises except in a suitable place in the open air so that the fumes can escape easily or in a room provided with adequate ventilation to remove the fumes therefrom and effectively prevent the accumulation of fumes therein.

(3) On unregistered premises flammable liquid shall be stored only in a substantial container which shall be kept securely closed when not in immediate use.

Inspection of Premises.

30.(1) Any authorized officer of the Council, may, for any purpose connected with the carrying out of these by-laws in accordance with the provisions of section 72 of the Local Government Ordinance, 1939, enter upon any premises whatsoever, and make such examination and enquiry thereon as he may deem necessary.

(2) The owner or occupier, or failing their presence on the premises, any other person employed thereon shall upon demand disclose to such authorized officer the presence of any flammable liquid in or upon such premises and shall answer all enquiries relating either to the observance of these by-laws or to any condition in connection with the certificate of registration or permit.

Taking of Samples.

31. Upon inspection of any premises by an authorized officer of the Council, such officer may take samples for the purpose of analysis or examination of any flammable liquid or substance, or of any liquid or substance suspected of being flammable, which is found upon such premises: Provided that —

- (a) any sample so taken shall be taken in the presence of the owner, occupier or other person in charge, as the case may be;
- (b) the owner, occupier or other person in charge may require the officer taking the sample to divide it into two parts and to mark, seal and deliver to him one such part.

Reëls ten opsigte van Persele wat nie Ingevolge Hierdie Verordeninge Geregistreer hoeft te word nie.

29.(1) Niemand mag vlambare vloeistof op 'n ongeregistreerde perseel opberg, gebruik of hanteer, of dit daar laat opberg, gebruik of hanteer, of toelaat dat dit geskied nie, tensy die vlambare vloeistof op sodanige plek of op sodanige wyse opgeberg, gebruik of gehanteer word, dat —

- (a) geen vlambare vloeistof of dampe daarvan met enige vuur, vlam, of oop lig of 'n ander middel wat moontlik sodanige vlambare vloeistof of die dampe daarvan aan die brand kan laat slaan, in aanraking kom, of moontlik daarmee in aanraking kan kom nie; of
- (b) die ontkomming van persone of diere in die geval van brand, nie verhinder of belemmer word nie.

(2) Niemand mag vlambare vloeistof op 'n ongeregistreerde perseel gebruik of hanteer, of laat gebruik of hanteer, of toelaat dat dit daar gebruik of gehanteer word nie, behalwe op 'n geskikte plek in die buitelug sodat die dampe maklik kan ontsnap, of in 'n kamer wat behoorlik geventileer is sodat die dampe daaruit weggevoer word, en dit doeltreffend verhoed word dat dampe daarin versamel.

(3) Op ongeregistreerde persele mag vlambare vloeistof slegs in 'n sterk houer, wat dig toegehou moet word wanneer dit nie daadwerklik in gebruik is nie, opgeberg word.

Ondersoek van Persele.

30.(1) Enige gemagtigde beampete van die Raad kan vir enige doel in verband met die nakoming van hierdie verordeninge ooreenkomsdig die bepalings van artikel 72 van die Ordonnansie op Plaaslike Bestuur, 1939, enige perseel betree en sodanige navrae doen of ondersoek instel as wat hy nodig mag ag.

(2) Die eienaar of okkupant of, indien hulle nie op die perseel teenwoordig is nie, enige ander persoon wat daar in diens is, moet op versoek van sodanige gemagtigde beampete, hom op versoek verwittig van enige vlambare vloeistof wat in of op sodanige perseel aanwesig is, en moet alle navrae met betrekking tot die nakoming van die bepalings van hierdie verordeninge, of met betrekking tot die voorwaarde in verband met die registrasiesertifikaat of permit beantwoord.

Die neem van Monsters.

31. Wanneer 'n gemagtigde beampete van die Raad 'n perseel ondersoek, kan sodanige beampete monsters van enige vlambare vloeistof of 'n stof of enige vloeistof of stof in verband waarmee daar vermoed word dat dit vlamaar is, en wat op sodanige perseel aangetref word neem, met die doel om dit te ontleed of te ondersoek:

Met dien verstande dat —

- (a) enige monster wat aldus geneem word, in die teenwoordigheid van die eienaar, okkupant of ander verantwoordelike persoon, na gelang van die geval, geneem moet word;
- (b) die eienaar, okkupant of ander verantwoordelike persoon kan eis dat die beampete wat die monster neem, dit in twee dele moet verdeel en die een deel moet merk, verseël, en aan hom moet oorhandig.

Breach of Conditions.

32. Any person who commits any breach of any condition endorsed on the approval notice or certificate of registration or spray permit issued in terms of these by-laws shall be guilty of an offence in terms of these by-laws.

STORAGE TANKS, PUMPS, PIPELINES AND CONTAINERS.

Capacity of Underground Storage Tanks.

33. The capacity of any underground storage tank, if not situated within a bulk depot or an aerodrome or landing ground used by aircraft, shall not exceed 23 kl: Provided that a storage tank with a greater capacity than 23 kl may be installed on any premises where such tank is to be used for manufacturing purposes.

Construction of Tanks.

34.(1) Every storage tank shall be constructed of iron, steel or other suitable metal plates of adequate strength and properly riveted and caulked, welded, brazed or otherwise secured by some equally satisfactory process.

(2) The top and sides of such tank shall be supported and strengthened by such uprights, girders, angle-irons and ties, as having regard to the capacity, shape and situation of the tank, may be necessary to render it sufficiently strong for the purpose to which it is being put.

(3) Every opening in any underground storage tank, other than a vent pipe, shall be securely closed by an effective and properly secured cap, cover, tap or valve.

(4) All pipes, other than a ventilation pipe, connected to an underground storage tank shall be carried down to within 100 mm of the bottom of the tank.

(5) Every above ground storage tank shall have an adequate system of ventilation so as to prevent excessive internal pressure.

(6) Every storage tank shall be maintained at all times in accordance with the respective provisions of this section.

Installation of Storage Tanks.

35.(1) Every underground storage tank shall —

- (a) be so installed that the top of the tank is not less than 600 mm below the surrounding ground level, or covered with not less than a 100 mm reinforced concrete mat and not less than 150 mm of earth or sand;
- (b) be set in firm foundations and wholly surrounded with soft earth or sand or encased in concrete;
- (c) with the exception of any opening to the manhole, be covered with concrete adequately reinforced in all cases where vehicular traffic passes over such tank;
- (d) be situated within the boundary line of the premises; and
- (e) where such tank is situated in or within 1,5 m of any basement, be installed in a chamber of concrete

Verbreking van Voorwaardes.

32. Enigiemand wat 'n voorwaarde verbreek wat op die goedkeuringskennisgewing of registrasiesertifikaat of sputtpermit staan wat kragtens hierdie verordeninge uitgereik is, is ingevolge hierdie verordeninge skuldig aan 'n misdryf.

OPBERGTENKS, POMPE, PYPLEIDINGS EN HOUERS.

Inhoudsvermoë van Ondergrondse Opbergtenks.

33. Die inhoudsvermoë van 'n ondergrondse opbergtenk, indien dit nie in 'n grootmaatdepot of op 'n lughawe of landingsterrein wat deur vliegtuie gebruik word, geleë is nie, moet hoogstens 23 kl groot wees: Met dien verstande dat 'n opbergtenk met 'n groter inhoudsvermoë as 23 kl op 'n perseel geïnstalleer kan word indien sodanige tenk vir vervaardigingsdoeleindes gebruik word.

Bou van Tenks.

34.(1) Elke opbergtenk moet vervaardig wees van yster-, staal- of ander geskikte metaalplate wat sterk genoeg is, en wat behoorlik met naels vasgeklink en gekalfater, gesweis, hard gesoldeer of andersins deur middel van 'n ewe doeltreffende proses vasgeheg is.

(2) Die bopunt en kante van so 'n tenk moet ondersteun en versterk word deur middel van stutte, balke, hoekysters en ankers wat met inagneming van die inhoudsvermoë, die vorm en ligging van die tenk, nodig mag wees ten einde dit sterk genoeg te maak vir die doel waarvoor dit gebruik word.

(3) Elke opening uitgesonderd 'n lugpypie, in 'n ondergrondse opbergtenk moet behoorlik deur 'n doeltreffende dop, deksel, kraan of klep wat goed vas is, toegemaak word.

(4) Alle pype, uitgesonderd 'n ventilasiepyp, wat met 'n ondergrondse opbergtenk verbind is, moet tot binne 100 mm van die boom van die tenk af reik.

(5) Elke bogrondse opbergtenk moet 'n doeltreffende ventilasiestelsel hê ten einde te voorkom dat die druk daarbinne te hoog word.

(6) Elke opbergtenk moet ten alle tye ooreenkomsdig die betrokke bepalings van hierdie artikel, in stand gehou word.

Aanbring van Opbergtenks.

35.(1) Elke ondergrondse opbergtenk moet —

- (a) so aangebring word dat die bopunt van die tenk minstens 600 mm onder die oppervlakte van die omliggende grond is, of moet met 'n gewapende betonblad van minstens 100 mm dik, en met minstens 150 mm grond of sand bedek wees;
- (b) op 'n vaste fondament aangebring en heeltemal met sagte grond of sand omring word, of met beton omhul word;
- (c) met uitsondering van enige opening na die mangat, in alle gevalle waar voertuigverkeer oor sodanige tenk gaan, met beton wat behoorlik gewapen is, bedek wees;
- (d) binne die grenslyn van die perseel geleë wees; en
- (e) in die geval waar so 'n tenk wat in 'n kelderverdieping of binne 1,5 m daarvandaan is aangebring

not less than 150 mm thick of brick not less than 215 mm thick set in cement mortar with the space within the pit surrounding the tank completely filled with closely packed earth or sand: Provided that the provisions of this section shall not apply to any bulk depot.

(2) Above ground storage tanks shall only be installed within a bulk depot.

Ventilation of Underground Storage Tanks.

36. Every underground storage tank shall have a ventilation pipe of not more than 50 mm nor less than 25 mm internal diameter the top of which pipe shall —

- (a) extend at least 4 m into the open air;
- (b) be protected with a non-corrodible wire gauze with a mesh aperture not exceeding 600 micrometres. Such gauze shall be secured in such a manner that it may be removed for examination and cleaning.
- (c) terminate at least 6 m away from any fire, flame or naked light or other agency likely to ignite flammable liquid or its vapour.

Installation of Storage Tanks, Pumps or Filling Devices in Buildings.

37. No storage tank, pump or filling device shall be installed in or below any building which is more than one storey high, unless the ceiling above such tank, pump or filling device is constructed of reinforced concrete.

Abandoned Tanks.

38. In the event of any underground storage tank being abandoned, the owner of such tank shall cause it to be removed or filled with sand or liquid concrete.

Entering of Storage Tanks.

39. No person shall —

- (a) enter or cause or permit any person to enter any storage tank which has contained flammable liquid until such tank has been totally freed from any flammable liquid vapour, unless such person is wearing an efficient gas mask; or
- (b) enter any storage tank at any time unless he is bound to a life line which at surface level is under the control of a reliable person continuously responsible for the safety of the person in the storage tank.

Position of Pumps.

40.(1) All pumps, and all other filling devices used or capable of use for the issue or transfer of flammable liquid to any vehicle or container shall be situated on private property and not less than 4 m from the boundary between it and any public place: Provided that no such pump or filling device shall be erected in such a position that a hose can be used for the issue or transfer of flammable liquid onto or across any public place.

(2) Notwithstanding anything contained in section 3, subsection (1) shall not apply to pumps or filling devices already erected on registered premises at the time of the coming into operation of these by-laws when a change

word in 'n kamer met betonmure wat minstens 150 mm dik is of baksteenmure wat minstens 215 mm dik is en met sementmortel gemessel is, en die ruimte in die put om die tenk moet heeltemal gevul wees met grond of sand wat styf vasgestamp is: Met dien verstande dat die bepalings van hierdie artikel nie op 'n grootmaatdepot van toepassing is nie.

(2) Bogrondse opbergtenks moet slegs in grootmaatdepos aangebring word.

Ventilasie van Ondergrondse Opbergtenks.

36. Elke ondergrondse opbergtenk moet 'n ventilasiepyp met 'n binne-middellyn van hoogstens 50 mm en minstens 25 mm hê en die boonste punt van die pyp moet —

- (a) minstens 4 m in die buitelug uitsteek;
- (b) met gaasdraad wat teen invretting bestand is en wat 'n gaasopening van minstens 600 mikrometer het, op so 'n wyse bedek word dat die gaasdraad vir ondersoek- en reinigingsdoeleindes verwijder kan word;
- (c) minstens 6 m van enige vuur, vlam of oop lig of ander middel wat moontlik vlambare vloeistof of damp daarvan, aan die brand kan laat slaan af weg wees.

Die aanbring van Opbergtenks, Pompe of Vultoestelle in Geboue.

37. Geen opbergtenk, pomp of vultoestel mag in of onder 'n gebou wat hoër as een verdieping is, aangebring word nie, tensy die plafon bokant so 'n tenk, pomp of vultoestel van gewapende beton vervaardig is.

Tanks wat nie meer Gebruik word nie.

38. Ingeval 'n ondergrondse opbergtenk nie meer gebruik word nie, moet die eienaar van so 'n tenk dit laat verwijder of dit met sand of vloeibare beton laat opvul.

Toegang tot Opbergtenks.

39. Niemand mag —

- (a) 'n opbergtenk wat vlambare vloeistof bevat het, binnegaan of iemand anders dit laat binnegaan, of toelaat dat hy dit binnegaan, alvorens alle vlambare vloeistofdampe uit sodanige tenk verwijder is nie, tensy so iemand 'n doeltreffende gasmasker aan het; of
- (b) 'n opbergtenk te eniger tyd binnegaan nie tensy hy aan 'n reddingstou vas is, wat op die oppervlak onder beheer van 'n betroubare persoon is wat voordurend oor die veiligheid van die persoon in die opbergtenk waak.

Liggings van Pompe.

40.(1) Alle pompe, en alle ander vultoestelle wat gebruik word of gebruik kan word, om vlambare vloeistof na 'n voertuig of houer oor te plaas, of dit daaraan te lewer, moet op private eiendom en minstens 4 m vanaf die grens tussen die private eiendom en 'n openbare plek geleë wees: Met dien verstande dat geen sodanige pomp of vultoestel so opgerig mag wees nie dat 'n pyp vir die uitreiking of oorplasing van vlambare vloeistof op of oor enige openbare plek gebruik kan word nie.

(2) Ondanks enigets wat in artikel 3 vervat is, is subartikel (1) nie op pompe of vultoestelle wat ten tyde van die inwerkingtreding van hierdie verordeninge alreeds op 'n geregistreerde perseel opgerig is, van toepas-

of control or ownership of such premises occurs, unless the position of such existing pump or filling device constitutes or is likely to cause a danger or obstruction to the public or vehicular traffic.

Pumps on Ramps.

41. Pumps or other devices used or intended to be used for the issue of flammable liquid to motor vehicles or containers shall not be erected on any ramp or within 4 m of the beginning of the ramp.

Dipping Sticks.

42. Dipping sticks shall be made only of wood, brass or other non-ferrous metal or alloy.

Pump Hoses.

43. Delivery of flammable liquid from any pump to the fuel tank of any vehicle shall be made only through sound hose having an earthing wire in its construction efficiently attached to the metal of the pump and to the metal hose nozzle. Except at an aerodrome or landing ground used by aircraft no hose attached to any pump shall exceed 4,5 m in length measured from the pump to the tip of the nozzle.

Situation of Filling Pipes and Pumps.

44. Every filling pipe inlet and every pump shall be —

- (a) at surface level;
- (b) installed in such position that it will not impede the escape of any person or animal from the premises in the case of fire; and
- (c) so situated or protected by surrounding walls as not to expose adjoining property to the risk of danger from fire during any filling operations or otherwise.

Naked Lights and Electrical Apparatus.

45.(1) No person shall install or take or cause or permit to be installed or taken any fire, flame, naked light or other agency likely to ignite flammable liquid or its vapour, except an electric light, within 3 m of any flammable liquid pump.

(2) No person shall place or cause or permit to be placed any electric switch, fuse, motor or other such device within a distance of 3 m of any pump unless such switch, fuse, motor or device is of flame proof construction.

(3) The electrical wiring between the distribution board or junction box and the pump shall, where possible, be in one continuous length of wire: Provided that where this is not possible, flame proof junction boxes shall be used.

Maintenance of Tanks, Pipelines and Pumps.

46.(1) All tanks, pipelines, pumps, machinery, fittings and appurtenances for the storage, use or handling of flammable liquid shall be —

- (a) of sound and proper construction;

sing indien die beheer oor, of eienaarskap van sodanige perseel verwissel nie, tensy die ligging van sodanige bestaande pomp of vultoestel gevaelik is, of gevaelik kan word, of die openbare of voertuigverkeer belemmer.

Pompe of Opritte.

41. Pompe of ander toestelle wat gebruik word of bedoel is om gebruik te word om vlambare vloeistof aan motorvoertuie of houers te lever, mag nie op 'n oprit, of binne 4 m van die begin van die oprit af, opgerig word nie.

Maatstokke.

42. Maatstokke moet slegs van hout, geelkoper of ander nie-ysterhoudende metaal of allooi gemaak wees.

Pompslange.

43. Die lewering van vlambare vloeistof van 'n pomp af aan die brandstoffenk van 'n voertuig, mag slegs deur middel van 'n heel pompslang geskied, wat voorsien is van 'n aardleiding wat doeltreffend aan die metaal van die pomp, en aan die metaaltuit van die pompslang vasgeheg is. Behalwe in die geval van 'n lughawe of 'n landingsterrein wat deur vliegtuie gebruik word, mag geen pompslang wat aan so 'n pomp vas is, langer as 4,5 m van die pomp af tot by die punt van die tuit wees nie.

Liggings van Vulpype en Pompe.

44. Die inlaatopening van elke vulpyp en elke pomp moet —

- (a) gelyk met die grondvlak wees;
- (b) sodanig aangebring wees dat dit geen mens of dier in die geval van brand verhinder om van die perseel af weg te kom nie; en
- (c) sodanig geleë wees, of so deur middel van ringmure beskerm word dat dit nie die aangrensende eiendom tydens vul werkzaamhede of andersins, aan brand blootstel nie.

Oop Ligte en Elektriese Apparate.

45.(1) Niemand mag enige vuur, vlam, oop lig of 'n ander middel wat moontlik vlambare vloeistof of die dampe daarvan aan die brand kan laat slaan, uitgesonderd 'n elektriese gloeilamp, binne 3 m van 'n pomp vir vlambare vloeistof aanbring, daarheen neem, dit daar laat aanbring of daarheen laat neem, of toelaat dat dit geskied nie.

(2) Niemand mag 'n elektriese skakelaar, 'n sekering, 'n motor of 'n ander sodanige toestel, binne 'n afstand van 3 m van 'n pomp af plaas, laat plaas of toelaat dat dit daar geplaas word nie, tensy, sodanige skakelaar, sekering, motor of toestel vlamdig vervaardig is.

(3) Die elektriese draadleiding tussen die verdeelbord of die aansluitkas en die pomp moet, waar moontlik, een deurlopende stuk draad wees: Met dien verstande dat indien dit onmoontlik is, daar vlamdigte aansluitkaste gebruik moet word.

Onderhoud van Tenks, Pyleidings en Pompe.

46.(1) Alle tenks, pyleidings, pompe, masjinerie, toebehore en toestelle vir die opberging, gebruik of hantering van vlambare vloeistof moet —

- (a) stewig en sterk gemaak wees;

- (b) so installed and fixed as not to be liable to be damaged;
- (c) efficiently electrically earthed;
- (d) free from leakage of flammable liquids, and as far as is reasonably possible, free from leakage of flammable liquid vapour, except by means of a vent pipe; and
- (e) maintained in good and proper order and at all times in accordance with the provisions of this section.

(2) All pipelines shall be below ground level and at right angles to the building-line when crossing a public footpath.

(3) All electrical earth connections required in terms of this section shall be examined once every 12 months by a qualified person who shall enter in a suitable log book, supplied by the occupier of the premises and kept solely for that purpose, the efficiency and conditions of such earth connections, his name and address and the date of the examination. All such entries shall be signed by such qualified person and shall be readily available for inspection by any authorized officer of the Council.

Construction of Portable Containers.

47. No person shall store or convey or cause or permit to be stored or conveyed in any one container any Class A flammable liquid in a quantity exceeding 50 l unless such container is constructed of metal not less than 1,5 mm in thickness.

Filling of Containers.

48. No person shall carry on or cause or permit to be carried on the trade, business or occupation of filling container with Class A flammable liquid otherwise than in a fire-resisting building adequately ventilated: Provided that such filling may be conducted in the open air if, in the opinion of the Chief Fire Office, it is not carried out at such a place or in such circumstances that there is a danger either of the liquid or the vapour therefrom becoming ignited, or that, in the event of fire, any structure of building will be endangered or the escape of persons or animals from premises to a place of safety will be obstructed or impeded.

Quantity of Flammable Liquid in Containers.

49. No container shall be filled with flammable liquid to more than 95 per cent of its capacity.

Containers after Delivery.

50. No person taking delivery of any flammable liquid in containers in excess of the quantity stated in section 6 or under circumstances of temporary storage provided for in section 13, shall cause or permit such containers to remain unattended in any place other than a store or storage tank for a longer period than may be reasonably necessary which, in no circumstances, shall exceed a period of 12 hours.

- (b) sodanig aangebring en vasgeheg word dat dit nie moontlik beskadig kan raak nie;
- (c) doeltreffend elektrics geaard wees;
- (d) sodanig aangebring en vasgeheg word dat dit nie wat redelikerwys moontlik is, ook nie vlambare vloeistofpampe, uitgesonderd deur middel van 'n lugpypie, laat ontsnap nie; en
- (e) te alie tye in 'n behoorlike en goeie toestand, ooreenkomsdig die bepalings van hierdie artikel, in stand gehou word.

(2) Alle pyleidings moet onder die grondvlak wees, en moet reghoekig met die boulyn wees wanneer dit 'n openbare sypaadjie kruis.

(3) Alle elektriese aardsluitings wat kragtens hierdie artikel vereis word, moet een keer elke 12 maande deur 'n gekwalifiseerde persoon ondersoek word, wat in 'n geskikte logboek wat deur die okkupant van die perseel verskaf, en uitsluitend vir die doel aangehou moet word, aantekeninge in verband met die doeltreffendheid en toestand van sodanige aardsluitings, benewens sy naam en adres en die datum waarop die ondersoek ingestel is, moet inskrywe. Alle sodanige inskrywings moet deur so 'n gekwalifiseerde persoon, onderteken word en moet geredelik vir inspeksie deur 'n gemagtigde beampete van die Raad beskikbaar wees.

Bou van Draagbare Houers.

47. Niemand mag meer as 50 l Klas A vlambare vloeistof in een houer opberg of vervoer, laat opberg of vervoer, of toelaat dat dit daarin opgeberg of vervoer word nie, tensy sodanige houer van metaal wat minstens 1,5 mm dik is, vervaardig is.

Vul van Houers.

48. Niemand mag die bedryf, beroep of besigheid waar houers met Klas A vlambare vloeistof volgemaak word, uitoefen of dryf, laat uitoefen of dryf of toelaat dat dit geskied nie, uitgesonderd in 'n brandbestande gebou wat toereikend geventileer is: Met dien verstande dat sodanige vulwerk in die buitelug kan geskied indien die Brandweerhoof van mening is dat dit nie op 'n plek of onder omstandighede verrig word waar daar die gevvaar bestaan dat of die vloeistof, of die dampe daarvan, aan die brand kan slaan of dat, indien daar 'n brand uitbreek, enige bouwerk of gebou in gevvaar gestel word of dat persone of diere verhinder word om van die perseel af na 'n veilige plek te ontkom of dat hulle ontkomming belemmer word nie.

Hoeveelheid Vlambare Vloeistof in Houers.

49. Geen houer mag meer vlambare vloeistof as 95 persent van sy inhoudsvermoë bevat nie.

Houers na Aflewering.

50. Niemand wat meer vlambare vloeistof in houers as die hoeveelheid wat in artikel 6 aangegee word, of wat vlambare vloeistof vir tydelike opberging, soos bepaal in artikel 13 in ontvangs neem, mag sodanige houers langer as wat redelikerwys noodsaaklik is, op enige plek, uitgesonderd in 'n pakkamer of opbergtenk, onbewaak laat bly nie, of toelaat dat dit geskied nie, en onder geen omstandighede mag die tydperk 12 uur oorskry nie.

Storage of Empty Containers.

51.(1) No person shall place any empty container or cause or permit any empty container to be placed in any premises other than a store: Provided that —

- (a) such container may be stored in the open air in such a position that, in the opinion of the Chief Fire Officer, it is, in the event of fire, not likely to obstruct or impede the escape to safety from any premises of persons or animals or to endanger any room or building;
- (b) no person shall cause or allow any empty container to remain in or on any public place.

(2) Every empty container so stored shall at all times be securely closed with a bung or other suitable topper.

Repairing of Containers.

52. No person shall carry out or permit to be carried out any repairing operations to any container until all flammable liquid and flammable liquid vapours have been removed from such container.

Marking of Containers.

53. No person shall supply or deliver to any person any Class A flammable liquid in any container of less than 200 l capacity, unless such container bears in conspicuous letter the word "FLAMMABLE" in both official languages.

STORES.*Capacity of Stores.*

54. The certificate of registration issued in respect of any store shall state the class and maximum quantity of flammable liquid permitted to be kept in such store at any one time.

Danger Notice on Store.

55. No person shall use as such or cause or permit to be used as such any flammable liquid store, unless and until the words "DANGER — FLAMMABLE LIQUID — NO SMOKING" in letters not less than 75 mm in height is prominently displayed in a position where it will be visible from the outside whether the door be open or closed. Such notice shall at all times be maintained in such position and in a legible condition.

Construction and Situation of Store.

56.(1) Every store shall be constructed in accordance with the following requirements:

- (a) The walls shall be constructed of brick or concrete, the floor of concrete or other imprevious material, and the roof of reinforced concrete: Provided that the roof may be constructed of other non-combustible material, where such store is not likely to endanger any room, building or adjoining premises in case of fire.
- (b) The store shall be fitted with a hardwood door of a thickness of not less than 50 mm, completely covered with metal of not less than 0,9 mm in thickness carried on a metal door frame, or well fitted metal door of not less than 3 mm in thickness, carried on an angle-iron frame and having an all-round

Opberging van Leë Houers.

51.(1) Niemand mag 'n leë houer in 'n ander perseel as in 'n pakkamer plaas, laat plaas of toelaat dat dit daar geplaas word nie; Met dien verstande dat —

- (a) so 'n houer in die buitelug op sodanige plek opgeberg kan word waar dit, na die mening van die Brandweerhoof, in geval van 'n brand, waarskynlik nie persone of diere sal verhinder om van enige perseel of na 'n veilige plek te ontkom, of hulle ontkoming sal belemmer nie, of enige vertrek of gebou in gevær sal stel nie;
- (b) niemand enige leë houer in of op 'n openbare plek mag laat staan of toelaat dat dit daar staan nie.

(2) Elke leë houer wat aldus opgeberg word, moet te alle tye behoorlik met 'n spon of gesikte prop toe wees.

Herstel van Houers.

52. Niemand mag herstelwerk aan 'n houer verrig of toelaat dat dit verrig word, alvorens alle vlambare vloeistof en vlambare vloeistofdampe uit die houer verwyder is nie.

Houer moet Gemerkt wees.

53. Niemand mag aan enigiemand Klas A vlambare vloeistof in 'n houer met 'n kleiner inhoudsvermoë as 200 l versaf of aflewer nie, tensy die woord "VLAMBAAR" in opvallende letters in albei amptelike tale op sodanige houer staan.

PAKKAMERS.*Inhoudsvermoë van Pakkamers.*

54. Die registrasiesertifikaat wat ten opsigte van 'n pakkamer uitgereik word, moet die klas en die grootste hoeveelheid vlambare vloeistof wat te eniger tyd in sodanige pakkamer gehou mag word, aangee.

Gevaarkennisgewing aan Pakkamers.

55. Niemand mag 'n pakkamer vir vlambare vloeistof as sodanig gebruik, laat gebruik, of toelaat dat dit as sodanig gebruik mag word nie, tensy en alvorens die woorde "GEVAAR — VLAMBARE VLOEISTOF — MOENIE ROOK NIE" in letters wat minstens 75 mm hoog is, in 'n opvallende posisie vertoon word waar dit van die buitekant, of die deur oop of toe is, sigbaar is. Sodanige kennisgewing moet te alle tye op sodanige plek in 'n leesbare toestand in stand gehou word.

Bou en Ligging van Pakkamers.

56.(1) Elke pakkamer moet ooreenkomsdig die volgende vereistes gebou word:

- (a) Die mure moet van baksteen of beton, die vloer van beton of ander syferdigte materiaal, en die dak van gewapende beton gebou wees: Met dien verstande dat die dak van ander nie-brandbare materiaal gebou kan wees, indien sodanige pakkamer in die geval van brand nie moontlik 'n ander kamer, gebou of aangrensende perseel in gevær sal stel nie.
- (b) Die pakkamer moet voorsien wees van 'n hardhoutdeur wat minstens 50 mm dik is en wat geheel en al met metaal van minstens 0,9 mm dikte bedek is en aan 'n ysterkosyn bevestig is; of van 'n metaaldeur van minstens 3 mm dik, wat goed aan 'n hockysterkosyn bevestig is en wat 'n oorslag van

- overlap of not less than 50 mm. Such door shall open outwards, and be fitted with a substantial lock. The type of door fitted shall be at the discretion of the Chief Fire Officer.
- (c) All window frames shall be constructed of metal, glazed with wire woven glass and shall be of the non opening type. Each pane shall not exceed 450 mm x 450 mm.
- (d) Every store shall be constructed in such a manner or surrounded by walls or bunds of such a character that the flammable liquid contained therein cannot escape therefrom. The well formed by such walls or bunds shall be of sufficient capacity to contain the maximum liquid capacity of the store plus 10 per cent thereof.
- (e) the store shall be ventilated in such a manner as will adequately prevent the accumulation of flammable liquid vapour within all parts of such store and discharge the vapour into the open air at a point or points where the vapour is not likely to come into contact with any fire, flame, open light or other agency likely to ignite it. The ventilation may be created by either of the following two methods:
- (i) Terra-cotta air-bricks measuring 215 mm by 140 mm shall be built into the wall at distances of not more than 450 mm on all free walls: Provided that at least two such free walls shall be opposite each other and that the lower edge of such air-bricks shall be at bund level.
 - (ii) A mechanical system of exhaust ventilation shall be installed should the store be inside a building or where a well is of greater depth than 300 mm or, if in the opinion of the Chief Fire Officer, the store would be inadequately ventilated by means of method (i). Such exhaust apparatus installed shall be of flameproof construction and shall be capable of removing flammable vapour and changing the air through any cross-section of the store at least 30 times in very hour. The exhaust vents shall be constructed so as to conform to and comply with the provisions of section 103(1)(h). The exhaust system and lighting for the store shall be operated by means of a courtesy switch fitted to the door of such store.
- (f) All air-bricks shall be protected by non-corrodible wire gauze with a mesh aperture not exceeding 600 micrometres.
- (g) A store shall not be situated in such a position that it will impede the escape of any person or animal from the premises, or endanger any room, building, or premises in the case of fire.
- (h) Any store with a floor area in excess of 10 m² shall be provided with at least two doors, constructed as described in paragraph (b), situated at such distance from each other as to allow the free and unimpeded escape of persons within the store from either door in the case of fire or other danger.
- (2) Subject to the requirements of section 4 and notwithstanding anything to the contrary contained in these minstens 50 mm rondom het. Sodanige deur moet na buitekant toe oopgaan en 'n sterk slot aanhou. Die tipe deur wat gepas word, moet volgens die diskresie van die Brandweerhoof wees.
- (c) Alle vensterrame moet van metaal gemaak wees en draadglasruite in hê wat nie oopgemaak kan word nie. Elke ruit moet nie groter as 450 mm x 450 mm wees nie.
- (d) Elke pakkamer moet op so 'n wyse gebou wees of deur mure of walle van so 'n aard omring wees dat die vlambare vloeistof wat daarin is, nie daaruit kan ontsnap nie. Die put wat deur sodanige mure of walle gevorm word, moet groot genoeg wees om die grootste hoeveelheid vloeistof wat in die pakkamer opgeberg kan word, plus nog 10 persent daarvan, te hou.
- (e) Die pakkamer moet sodanig geventileer word dat dit die akkumulasie van vlambare vloeistofdampe op alle plekke in die pakkamer verhoed, en sodanige dampe in die buitelug laat ontsnap by 'n plek of by plekke waar sodanige dampe nie moontlik in aanraking met enige vuur, vlam, oop lig of 'n ander middel wat moontlik sodanige dampe aan die brand kan laat slaan, sal kom nie. Die ventilasie kan bewerkstellig word deur middel van enige van die volgende twee metodes:
- (i) Terra-cotta lugstene met afmetings van 215 mm by 140 mm moet nie verder as 450 mm uitmekaar in al die buitemure ingebou word: Met dien verstande dat minstens twee van die buitemure teenoor mekaar moet wees en die onderste rand van sodanige lugstene moet op walhoogte aangebring word.
 - (ii) 'n Meganiese ventilasiestelsel moet geïnstalleer word in die geval waar 'n pakkamer binne 'n gebou geleë is, of waar 'n put dieper as 300 mm is of, indien na die mening van die Brandweerhoof, onvoldoende ventilasie deur metode (i) verkry word. Sodanige ventilasiestelsel wat geïnstalleer is, moet van vlamdigte konstruksie wees en moet in staat wees om minstens 30 maal per uur deur enige dwarssnee van die pakkamer vlambare dampe doeltreffend uit die pakkamer te verwijder en die lug daarin te verander. Die ventilasieopeninge moet sodanig ontwerp wees dat dit aan die vereistes van artikel 103(1)(h) voldoen. Die ventilasiestelsel en ligte van die pakkamer moet beheer word vanaf 'n sekéringskakelaar wat aan die deur gemonter is.
- (f) Alle lugstene moet deur middel van gaasdraad met openings van nie meer as 600 mikrometer grootte en wat teen roes bestand is, beskerm word.
- (g) 'n Pakkamer mag nie so geleë wees dat dit, in die geval van brand, enige persoon of dier sal verskerf om van die perseel te ontsnap, of enige vertrek, gebou, of perseel in gevaar sal stel nie.
- (h) 'n Pakkamer met 'n groter vloeroppervlakte as 10 m² moet minstens twee deure in hê, wat gemaak is soos beskryf word in paragraaf (b), en wat op so 'n afstand van mekaar af is dat persone in die pakkamer, in die geval van brand of ander gevaar, vry en onbelemmerd deur enige van die deure kan ontsnap.
- (2) Onderworpe aan die bepalings van artikel 4 en ondanks andersluidende bepalings wat in hierdie ver-

by-laws, a store may be constructed of non-combustible material if —

- (a) such store has no building nearer to it than a minimum of 15 m; and
- (b) it is surrounded by the necessary wall or impervious bund as provided in subsection (1)(a).

(3) Every store shall be maintained at all times in accordance with the provisions of this section.

Lighting of Store.

57. All lights installed shall be enclosed in an outer flame-proof fitting and all wiring shall be armoured cable or enclosed in seamless metal tubes the junctions of which are screwed together. All switches, junction boxes, fuses and other electrical equipment shall be outside the store.

Use of Store.

58. No person shall —

- (a) use any store or cause or permit such store to be used for any purpose other than the storage, use or handling of flammable liquids and substances;
- (b) engage in or cause or permit any other person to be engaged in any store unless all the doors of the store are fully open and kept entirely unobstructed.

Unauthorized Persons Entering Store.

59. No person shall enter any store or cause or permit any store to be entered without the express permission of the occupier or other responsible person in charge of such store.

BULK DEPOTS.

Danger Notice at Entrance.

60. Prominent notice boards bearing the words "DANGER — FLAMMABLE LIQUID — NO SMOKING" in letters not less than 150 mm in height in both official languages shall be erected at all entrances to bulk depots and shall at all times be maintained in such position and in legible condition.

Storage.

61.(1) Flammable liquid shall be stored in bulk depots as follows:

- (a) Underground storage tanks.
- (b) Aboveground storage tanks.
- (c) Bulk stores.

(2)(a) Every such aboveground storage tank, or group of such tanks, with a total capacity of over 55 kl shall be surrounded by either an embankment (hereinafter called a retaining embankment) or a retaining wall of brick and cement or reinforced or plain concrete (hereinafter called a retaining wall), so designed and constructed as to form a reservoir capable of containing and retaining the quantity of liquid required to be retained in accordance with paragraph (e): Provided that the top of such retaining embankment or retaining wall shall be at least 75 mm

ordeninge vervat is, kan 'n pakkamer van nie-brandbare materiaal gebou word, indien —

- (a) daar geen gebou nader as 15 m van die pakkamer af staan nie; en
 - (b) dit omring is deur die vereiste muur of die syferdigte wal, soos in subartikel (1)(a) bepaal.
- (3) Elke pakkamer moet te alle tye ooreenkomsdig die bepalings van hierdie artikel onderhou word.

Beligting van Pakkamer.

57. Alle ligte wat aangebring word moet 'n vlamdigte buite omhulsel hê, en alle draadleidings moet gepantserde kabel wees, of moet in naatlose metaalbuise waarvan die lasse vaseskroef word, ingesluit wees. Alle skakelaars, aansluitkaste, sekeringen en ander elektriese toerusting moet buite die pakkamer geleë wees.

Gebruik van Pakkamer.

58. Niemand mag —

- (a) 'n pakkamer gebruik, laat gebruik, of toelaat dat dit gebruik word vir enige ander doel as om vlambare vloeistowwe en stowwe daarin op te berg, te gebruik of te hanteer nie.
- (b) iemand anders in 'n pakkamer in diens hê of veroorsaak of toelaat dat hy daar in diens is nie tensy al die deure van die pakkamer heeltemal oopstaan of geheel en al onversper gehou word.

Ongemagtigde Persone wat 'n Pakkamer Binnegaan.

59. Niemand mag 'n pakkamer binnegaan, iemand dit laat binnegaan of toelaat dat iemand dit binnegaan sonder die uitdruklike toestemming van die okkupant of 'n ander verantwoordelike persoon wat in beheer van sodanige pakkamer is nie.

GROOTMAATDEPOTS.

Gevaarkennisgewings by die Ingang.

60. Opvallende kennisgewings met die woorde "GEVAAR — VLAMBARE VLOEISTOF — MOENIE ROOK NIE" duidelik in albei amptelike tale daarop, in letters wat minstens 150 mm hoog is, moet by al die ingange na die grootmaatdepots opgerig word, en moet te alle tye op dié plekke in 'n leesbare toestand in stand gehou word.

Opbergting.

61.(1) Vlambare vloeistof moet soos volg in grootmaatdepots opgeberg word:

- (a) In ondergrondse opbergtenks.
- (b) In bogrondse opbergtenks.
- (c) In grootmaatpakhuise.

(2)(a) Elke sodanige bogrondse opbergtenk of groep sodanige tenks met 'n totale inhoudsvermoë van meer as 55 kl moet of deur 'n wal (hierna 'n steunwal genoem) of deur 'n steunmuur van baksteen en cement of van gewapende of ongewapende beton (hierna 'n steunmuur genoem) omring wees, wat sodanig ontwerp en gebou is dat dit 'n reservoir vorm wat in staat is om die hoeveelheid vloeistof wat ooreenkomsdig paragraaf (e), daarin gehou moet word, te bevat en te behou: Met dien verstande dat die kruin van sodanige steunwal of steunmuur minstens 75 mm hoër moet wees as wat nood-

higher than is necessary to contain and retain such quantity of liquid.

(b) The retaining embankment shall be at least 600 mm thick at the top with slopes on each side of 1.5 to 1. Such embankment shall be constructed with a central core of concrete not less than 200 mm thick at the top with a slope on each side of 1 in 24 to the level of the interior of the area enclosed. The core, of the same thickness as at this level, shall be taken down to such a depth, depending on the nature of the soil, as will effectually prevent any leakage of liquid. The earthwork around the core shall be composed of materials well watered and consolidated.

(c) The retaining wall shall be constructed in accordance with the following requirements:

- (i) It shall be capable of resisting the full overturning movement of the liquid in the enclosed reservoir when filled to within 75 mm of the top with a liquid of the same specific gravity as water.
- (ii) If such wall constitutes a partition between two reservoirs, it shall be capable of withstanding thrust from either side.
- (iii) Every retaining wall shall be taken down to such depth and be provided with such foundations, depending on the nature of the soil, as will ensure stability in all respects and effectually prevent any leakage of liquid.
- (iv) Every retaining wall of reinforced concrete shall not be less than 150 mm in thickness at the top and the tensile portion of the stresses shall be wholly taken up by steel rods placed not nearer the surface thereof than 50 mm.
- (v) The concrete stress shall not exceed 4,8 MPa and the stress in the steel 110 MPa under fully loaded conditions.

(d) Adequate provision shall be made to dispose of any water which may be retained by any such retaining embankment or wall. Any drain pipe through such embankment or wall shall be fitted with a cast iron valve on the outside which, except when in use, shall be kept closed and adequately locked.

(e) The retaining capacity of such enclosed reservoir surrounding any tank or groups of tanks shall be as follows:

- (i) Not less than 90 per cent of the total capacity of such tank where there is not more than one tank within such enclosed reservoir.
- (ii) Not less than 80 per cent of the total capacity of such tanks where there are two tanks within the same enclosed reservoir.
- (iii) Not less than 75 per cent of the total capacity of all such tanks where there are more than two tanks within the same enclosed reservoir.

Provided that the retaining capacity of the enclosed reservoir surrounding any tank or group of tanks need not be greater than at least 50 per cent of the total capacity of the tank or tanks, as the case may be, if such tank or group of tanks are constructed with a floating roof or provided with any other type of roof which effectively eliminates any space above the level of the liquid in such tank or group of tanks and is approved by the Council.

saaklik is om sodanige hoeveelheid vloeistof te bevatten te behou.

(b) Die steunwal moet bo minstens 600 mm dik wees, met 'n helling aan elke kant van 1,5 op 1. Sodanige walle moet gebou word met 'n betonkern wat bo minstens 200 mm dik is, en met 'n helling aan elke kant van 1 op 24 tot op die vlak van die binnekant van die ingeslotte ruimte. Die kern moet met dieselfde dikte as wat dit op hierdie vlak het, na gelang van die soort grond, so diep aangevoer word dat dit doeltreffend sal voorkom dat enige vloeistof uitlek. Die grondwal om die kern moet van materiaal wees wat deeglik natgemaak en vastgestamp is.

(c) Die steunmuur moet ooreenkomsdig die volgende vereistes gebou word:

- (i) Dit moet in staat wees om die hele kantelingsmoment van die vloeistof wat in die ingeslotte reservoir is wanneer dit tot 75 mm van bo af volgemaak is met vloeistof met dieselfde soortlike gewig as water, te kan weerstaan.
- (ii) Indien sodanige muur 'n afskorting tussen twee reservoirs vorm, moet dit in staat wees om die drukking van beide kante af te kan weerstaan.
- (iii) Elke steunmuur moet, na gelang van die soort grond, so diep aangevoer word en sodanige fondamente hê, dat dit in alle opsigte stewig is en doeltreffend sal voorkom dat vloeistof uitlek.
- (iv) Elke steunmuur van gewapende beton moet bo minstens 150 mm dik wees, en die trekspanning moet heeltemal deur staalstawe, wat hoogstens 50 mm van die oppervlak daarvan af aangebring is, opgeneem word.
- (v) Die betrekspanning moet nie 4,8 MPa en die spanning in die staal 110 MPa onder belasting, oorskry nie.

(d) Daar moet voldoende voorsorg getref word om water wat deur sodanige steunwalle of -mure opgedam mag word, af te voer. Enige afvoerpyp deur so 'n wal of muur moet met 'n gietyster klep aan die buitekant voorsien wees wat, behalwe wanneer dit gebruik word, toe en behoorlik gesluit gehou moet word.

(e) Die stukapasiteit van sodanige ingeslotte reservoir wat enige tenk of groep tenks omring, moet soos volg wees:

- (i) Minstens 90 persent van die totale inhoudsvermoë van sodanige tenk indien daar hoogstens een tenk binne sodanige ingeslotte reservoir is.
- (ii) Minstens 80 persent van die totale inhoudsvermoë van sodanige tenks indien daar twee tenks binne dieselfde ingeslotte reservoir is.
- (iii) Minstens 75 persent van die totale inhoudsvermoë van al sodanige tenks indien daar meer as twee tenks binne dieselfde ingeslotte reservoir is:

Met dien verstande dat die stukapasiteit van die ingeslotte reservoir, wat enige tenk of groep tenks omring, nie meer as minstens 50 persent van die totale inhoudsvermoë van die tenk of tenks, na gelang van die geval, hoef te beslaan nie indien die tenk of tenks met 'n drywende of 'n ander soort dak gebou is wat enige ruimte bokant die vlak van die vloeistof in die tenk of tenks op doeltreffende wyse elimineer en wat deur die Raad goedgekeur is.

(f) The area enclosed by such retaining embankment or wall not occupied by any storage tank shall except for the purpose of carrying out repairs, alterations or additions to such tanks, be kept entirely free and unoccupied.

(f) The provisions in terms of paragraphs (b) and (c) shall not apply to any existing reservoir in use at the date of publication of these by-laws.

(3) Every bulk store shall be constructed so as to conform with the provisions of section 56, except paragraph (d). The well formed by walls or bunds shall in this instance be of sufficient capacity to contain 50 per cent of the total quantity of liquid contained therein.

Tank Distances.

62. All storage tanks shall in regard to the sizes set out in the first column hereunder be separated from the boundary of the bulk depot and from each other by the distances set out in the second and third columns hereunder respectively:

	Capacity of Tank kl	Distance from Boundary m	Distance between Tanks m
Up to	60	6	1
Up to	100	8	1
Up to	150	9	1,5
Up to	200	11	3
Up to	300	12	4,5
Up to	400	14	5,5
Up to	500	15	6
Up to	1 000	15	8
Up to	2 500	15	9
Up to	5 000	15	12
Over	5 000	15	15

Provided that —

- (a) where tanks of varying capacities are to be grouped the distances from the boundaries shall be observed but the distances between individual tanks shall be not less than the sum of the specified distances for each size of tank divided by 2;
- (b) no building or structure shall be erected for the filling of containers with flammable liquids within 15 m of any storage tank or within 7,5 m of the boundary of any bulk depot; and
- (c) where bulk depots belonging to different persons are situated on adjoining sites, the distance between any tank and their common boundary shall be half that prescribed for such tank in the second column above.

Electric Motors.

63. No person shall place or cause or permit to be placed any electric motor in any position where it is likely to come into contact with any flammable liquid or its vapour unless such motor is of flame-proof construction.

(f) Die ruimte wat deur sodanige steunwal of -muur omring word, en wat nie deur 'n opbergtenk in beslag geneem word nie, moet uitgesondert met die doel om herstelwerk te verrig of veranderings of toevoegings aan sodanige tenks aan te bring, heeltemal vry en onbeset gehou word.

(g) Die bepalings ingevolge paragrawe (b) en (c), is nie van toepassing op enige bestaande reservoir wat op die datum van afkondiging van hierdie verordeninge, in gebruik is nie.

(3) Elke grootmaatpakhuis moet sodanig ontwerp word dat dit aan die bepalings van artikel 56, uitgesondert paragraaf (d), voldoen. Die putte wat deur mure of walle gevorm word, moet in hierdie geval van voldoende kapasiteit wees om 50 persent van die totale hoeveelheid vloeistof wat daarin is, te behou.

Afstande van Tenks.

62. Alle opbergtenks moet, met betrekking tot die groottes wat in die eerste kolom hieronder aangegee word, onderskeidelik die afstande wat in die tweede en derde kolomme hieronder aangegee word van die grens van die grootmaatdepot en van mekaar af verwyder wees:

	Inhoudsvermoë van Tenk kl	Afstand van die Grens m	Afstand tussen die Tenks m
Tot	60	6	1
Tot	100	8	1
Tot	150	9	1,5
Tot	200	11	3
Tot	300	12	4,5
Tot	400	14	5,5
Tot	500	15	6
Tot	1 000	15	8
Tot	2 500	15	9
Tot	5 000	15	12
Bo	5 000	15	15

Met dien verstande dat —

- (a) indien tenks van verskillende inhoudsvermoë saam gegroepeer moet word, die afstande van die grense af gehandhaaf moet word, maar die afstand tussen afsonderlike tenks minstens gelyk moet wees aan die totaal van die gespesifiseerde afstande ten opsigte van elke grootte tenk, gedeel deur 2;
- (b) geen gebou of bouwerk, wat bedoel is om houers met vlambare vloeistof in vol te maak, binne 15 m van 'n opbergtenk af, of binne 7,5 m van die grens van 'n grootmaatdepot af, opgerig mag word nie; en
- (c) waar grootmaatdepots aan verskillende persone op aangrensende persele behoort, moet die afstand tussen enige tenk en hul gemeenskaplike grens die helfte van die afstand wees soos voorgeskryf vir sodanige tenk in kolom twee hierbo.

Elektriese Motore.

63. Niemand mag 'n elektriese motor op 'n plek waar dit moontlik in aanraking met vlambare vloeistof of dampie daarvan kan kom, plaas, laat plaas, of toelaat dat dit daar geplas word nie, tensy sodanige motor vanvlamdigte konstruksie is.

Fire Appliances.

64.(1) Every bulk depot shall be connected to the municipal water supply by means of a lead with a diameter of not less than a 100 mm.

(2) A fire pump connection for each fire service shall be installed in a position approved by the Council and within easy access of a street hydrant.

(3) A reflux valve to shut off the supply from the street mains when the pump connection is being used shall be fitted between the stand boundary and the pump connection.

(4) Standard pattern wheel valve hydrants fitted with instantaneous couplings with a diameter of 63,5 mm shall be located in positions approved by the Council and adjacent to buildings and tanks used for flammable liquid storage, at the rate of one for every 500 m² of floor area and one within 90 m of each bulk storage tank.

(5) 63,5 mm canvas fire hose and branch pipes with 19 mm nozzles of sufficient length for the adjacent area which is served by such hydrants shall be provided.

(6) Wheeled dry chemical type extinguishers of not less than 45 kg capacity, or other similar types of extinguishers, shall be installed where deemed necessary by the Council. Every building used for the storage of flammable liquid or flammable substances shall be provided with one dry chemical type fire extinguisher with a capacity of not less than 9 kg at the rate of one for every 500 m² of floor area.

(7) an adequate system of alarm in case of fire (such as bells, whistles or sirens) shall be installed.

(8) All persons employed at or in the bulk depot shall be periodically instructed in the use of all fire appliances.

Filling of Road Tank Wagons.

65. The filling of a road tank wagon with flammable liquid shall not be commenced or carried out at a bulk depot by any person —

- (a) at a lesser distance than 7,5 m from any storage tank or building above ground or boundary of such depot;
- (b) unless and until all pipes have been efficiently earthed; or
- (c) unless good and sufficient metallic contact has been made and is maintained between such road tank wagon and the metal pipeline to prevent the building up of a static charge of electricity on such wagon.

Starting of Engine at Filling Point.

66. No person shall at a bulk depot start, or cause or permit to be started the engine of a road tank wagon or any mechanically propelled vehicle if such road tank wagon or vehicle is within 6 m of any place where filling operations are taking place not under seal or in any

Brandblustoestelle.

64.(1) Elke grootmaatdepot moet deur middel van 'n waterleiding van minstens 100 mm deursnit met die watertoever van die munisipaliteit verbind wees.

(2) 'n Brandspuitverbinding moet ten opsigte van elke brandbestrydingsleiding aangebring word op 'n plek wat deur die Raad goedgekeur is, en wat binne maklike bereik van 'n straatbrandkraan af is.

(3) 'n Terugslagklep om die toevoer van die straathoofleidings af te sluit wanneer die brandspuitverbinding gebruik word, moet tussen die grens van die standplaas en die brandspuitverbinding aangebring word.

(4) Standaard-wielklepbrandkrane wat voorsien is van blitsaankoppeling met 'n middellyn van 63,5 mm, moet op plekke wat deur die Raad goedgekeur is, langs geboue en tenks, wat vir die opberging van vlambare vloeistof gebruik word, aangebring word, teen een per elke 500 m² vloeroppervlakte, en een binne 90 m van elke grootmaatopbergtenk af.

(5) 'n 63,5 mm seilbrandslang en vertakkingspype met 19 mm tuite en wat lank genoeg is om die aangrensende gebied te bereik, wat deur sodanige brandkraan bedien word, moet verskaf word.

(6) Brandblustoestelle van die chemiese tipe met wiele wat 'n inhoudsvermoë van minstens 45 kg het, of ander soortgelyke tipe brandblustoestelle, moet aangebring word waar dit deur die Raad nodig geag word. Elke gebou wat vir die opberging van vlambare vloeistof of vlambare stowwe gebruik word, moet met een droë chemiese brandblustoestel met 'n inhoudsvermoë van minstens 9 kg teen een ten opsigte van elke 500 m² vloeroppervlakte, voorsien word.

(7) 'n Doeltreffende alarmstelsel (soos byvoorbeeld klokke, fluite of sirenes) moet vir gebruik in geval van brand aangebring word.

(8) Almal wat by, of in die grootmaatdepot in diens is, moet van tyd tot tyd in die gebruik van alle brandblustoestelle onderrig word.

Vul van Tenkvragmotors.

65. Niemand mag 'n tenkvragmotor by 'n grootmaatdepot met vlambare vloeistof volmaak of begin volmaak nie —

- (a) op 'n kleiner afstand as 7,5 m van 'n opbergtenk of gebou bokant die grond, of van die grens van sodanige depot af nie;
- (b) tensy en alvorens alle pype doeltreffend geaard is nie; of
- (c) tensy 'n behoorlike en doeltreffende metaalaansluiting tussen sodanige tenkvragmotor en die metaal-pypeleiding bewerkstellig en onderhou word, ten einde te voorkom dat 'n lading statiese elektrisiteit in sodanige vragmotor opgebou word.

Aanskakel van Enjin by Volmaakplek.

66. Niemand mag die enjin van 'n tenkvragmotor of enige voertuig wat meganies aangedryf word, by 'n grootmaatdepot aan die gang sit, dit aan die gang laat sit, of toelaat dat dit aan die gang gesit word, indien sodanige tenkvragmotor of voertuig binne 6 m van 'n plek af is waar die vulwerksaamhede nie by wyse van verseêerde oorplasing geskied nie, of 'n plek waar sodanige

place in which such wagon or vehicle comes or is likely to come into contact with flammable liquid or its vapour.

Steam Engines.

67. Where it is necessary for steam locomotives to enter a bulk depot, the occupier shall erect a notice board bearing the words "LOCOMOTIVES MUST NOT PASS THIS POINT" in letters not less than 150 mm in height in both official languages. The board shall be placed in a conspicuous position at a distance of not less than 15 m from any operation dealing with flammable liquids or storage thereof. No flammable liquid or open container containing flammable vapour shall be placed or stored at a distance of less than 15 m from any portion of the track which may be traversed by a steam locomotive.

Admission to Depots.

68. No person shall —

- (a) enter any bulk depot without the express permission of the occupier or the person authorized by the occupier to be in charge of such depot;
- (b) enter any bulk depot in possession of any matches, cigarette lighter or similar contrivance; or
- (c) commit any act which is liable or calculated to cause fire or explosion or to endanger the depot or its contents.

Supervision of Depots.

69. The occupier of a bulk depot shall ensure that a responsible person duly authorized thereto, shall at all times during working hours be on constant duty at such depot to ensure against fire hazards or other contingencies which may be a danger to life or property, and that a reliable watchman is always on duty at the depot after normal working hours.

TRANSPORT OF FLAMMABLE LIQUID.

Transport Permit.

70. Save as provided in section 80, no person shall use or cause or permit to be used in or on any public place any vehicle for the conveyance of flammable liquid within the municipality unless and until he is in possession of a transport permit issued to him by the Council in respect of such vehicle, or a permit issued to him by any other local authority.

Issue of Transport Permit.

71.(1) No transport permit shall be granted in respect of any vehicle unless and until such vehicle —

- (a) has been exhibited for examination at such place as the Council may direct, and the examination charge, as prescribed in Schedule 2 hereto has been paid;
- (b) complies with the conditions of fitness relating to such vehicle in terms of the Road Traffic Ordinance, 1966, and any regulations promulgated thereunder; and

vragmotor of voertuig in aanraking met vlambare vloeistof of damppe daarvan kom of moontlik kan kom nie.

Stoomlokomotiewe.

67. Waar dit vir 'n stoomlokomotief nodig is om 'n grootmaatdepot binne te gaan, moet die okkupant 'n kennisgewing met die woorde daarop "LOKOMOTIEWE MAG NIE BY HIERDIE PUNT VERBYGAAN NIE" in letters wat minstens 150 mm hoog is, in albei amptelike tale aanbring. Die kennisgewing moet op 'n opvallende plek minstens 15 m van die plek waar daar met vlambare vloeistof gewerk of waar dit opgeberg word opgerig word. Geen vlambare vloeistof of oop houer wat vlambare damppe bevat, mag nader as 15 m van enige gedeelte van die pad waaroor 'n stoomlokomotief loop, geplaas op opgeberg word nie.

Toegang tot Depots.

68. Niemand mag —

- (a) 'n grootmaatdepot sonder die uitdruklike toestemming van die okkupant of van die persoon wat deur die okkupant gemagtig is om oor sodanige depot toesig te hou, binnegaan nie;
- (b) 'n grootmaatdepot binnegaan terwyl hy in besit van vuurhoutjies, sigarettopsteker of soortgelyke toestelle is nie; of
- (c) 'n daad verrig wat moontlik brand of 'n ontploffing kan veroorsaak, of wat die depot of sy inhoud in gevaar kan stel, of wat bereken is om dit te doen nie.

Toesig oor Depots.

69. Die okkupant van 'n grootmaatdepot moet sorg dat 'n verantwoordelike persoon wat behoorlik daartoe gemagtig is, ononderbroke gedurende werksure by so 'n depot aan diens aanwesig is ten einde voorsorg teen brand of ander gebeurlikhede wat lewe of eiendom in gevaar kan stel, te tref, en moet sorg dat 'n betroubare oppasser altyd na gewone werksure by die depot waghou.

VERVOER VAN VLAMBARE VLOEISTOF.

Vervoerpermit.

70. Behoudens die bepalings van artikel 80, mag niemand 'n voertuig vir die vervoer van vlambare vloeistof op 'n openbare plek binne die munisipaliteit gebruik, laat gebruik of toelaat dat dit gebruik word nie, tensy en alvorens hy in besit van 'n vervoerpermit is, wat die Raad ten opsigte van sodanige voertuig aan hom uitgereik het, of 'n permit wat deur enige ander plaaslike bestuur aan hom uitgereik is.

Uitreiking van Vervoerpermit.

71.(1) Geen vervoerpermit ten opsigte van 'n voertuig word uitgereik nie, tensy en alvorens sodanige voertuig —

- (a) na sodanige plek as wat die Raad mag aanwys, gebring is om ondersoek te word en die ondersoeksgeld soos voorgeskryf in Bylae 2 hierby, betaal is;
- (b) aan die voorwaardes ten opsigte van geskiktheid wat op sodanige voertuig betrekking het, ingevolge die Ordonnansie op Padverkeer, 1966, en enige regulasies wat ingevolge daarvan afgekondig is, voldoen; en

- (c) complies with the requirements of section 72.
- (2) Such transport permit shall —
 - (a) Continue in force for a period of six months or such lesser period as may be stated in such permit;
 - (b) specify the maximum quantity and class of flammable liquid which such vehicle shall be permitted to carry;
 - (c) be affixed to the vehicle in respect of which such transport permit was issued and to no other vehicle; and
 - (b) be maintained on such vehicle in a good and legible condition by the owner or person in control of such vehicle in a position so as to be plainly visible.

Construction and Capacity of Vehicles.

72.(1) Every vehicle used for the purpose of transporting flammable liquids by road, in these by-laws referred to as road tank wagon, shall comply with the following requirements and the word "tank" in these by-laws means a tank carried on such a vehicle for the aforesaid purpose:

- (a) The vehicle shall be strongly constructed and as far as is reasonably possible shall be constructed of non-combustible material.
- (b) Where electric lighting or other electric devices are employed, the electrical circuit shall be heavily insulated and the wiring so fixed and protected as to reduce as far as reasonably possible any risk of damage. The generator, battery, fuses or switches shall not be situated in any position whereby they are likely to come into contact with any flammable liquid or its vapour.
- (c) The tank shall be constructed of iron, steel or other suitable metal and riveted, welded, brazed or otherwise made liquid-tight. Where aluminium alloys are used, the tank shall be constructed in accordance with the specifications detailed in section 385 of Volume 1 of the National Fire Codes issued by the National Fire Protection Association.
- (d) Means of cutting off the electrical current close to the battery by a double pole switch or other suitable method shall be provided.
- (e) Any tank having a capacity exceeding 6 kl shall be divided into liquid-tight compartments, each compartment to be of a capacity of not more than 6 kl: Provided that the aforesaid maximum capacity of 6 kl may be exceeded by not more than five per cent if the exigencies of construction make such excess necessary: Provided further that the liquid contents of any such compartment shall at no time exceed 98 per cent of the total capacity of the compartment.
- (f) The tank shall be securely attached to and in metal contact with the vehicle.
- (g) The draw-off pipes of the tank shall be fitted with two independent valves situated at remote points from one another.

- (c) aan die vereistes van artikel 72 voldoen.
- (2) Sodanige vervoerpermit —
 - (a) is van krag vir 'n tydperk van ses maande of sodanige korter tydperk as wat op die permit vermeld word;
 - (b) moet die grootste hoeveelheid asook die klas vlambare vloeistof wat so 'n voertuig toegelaat word om te vervoer, vermeld;
 - (c) moet aan die voertuig ten opsigte waarvan dit uitgereik is, en aan geen ander voertuig nie, vasgeheg word; en
 - (d) moet deur die eienaar of die persoon wat die voertuig onder sy sorg het in 'n goeie en leesbare toestand onderhou word op 'n plek op so 'n voertuig waar dit duidelik sigbaar is.

Bou en Inhoudsvermoë van Voertuie.

72.(1) Elke voertuig wat gebruik word vir die doel om vlambare vloeistowwe per pad te vervoer, in hierdie verordeninge 'n tenkvrugmotor genoem, moet aan die volgende vereistes voldoen, en die woord "tenk" beteken in hierdie verordeninge die tenk wat op sodanige voertuig vir voormelde doeleinde gedra word:

- (a) Die voertuig moet sterk gebou wees, en so ver as redelikerwyse moontlik, van nie-brandbare materiaal vervaardig wees.
- (b) Indien daar van elektriese verligting of ander elektriese toestelle gebruik gemaak word, moet die elektriese stroomleiding dig geïsoleer wees, en die bedrading op sodanige wyse aangebring en beskerm word, dat dit sover moontlik die gevær van beskadiging uitskakel. Die ontwikkelaar, battery, smeltdrade of skakelaars moet nie op 'n plek aangebring word waar hulle moontlik in aanraking met vlambare vloeistof of damp daarvan kan kom nie.
- (c) Die tenk moet van yster, staal of 'n ander geskikte metaal vervaardig wees en moet met naels vasgeklink, gesweis, hardgesoldeer of andersins vloeistofdig gemaak word. Waar daar van aluminium allooie gebruik gemaak word, moet die tenk gebou word volgens die spesifikasies, soos omskryf in artikel 385, Volume 1 van die "National Fire Codes" uitgereik deur die "National Fire Protection Association".
- (d) Daar moet gesorg word dat die elektriese stroom deur middel van 'n tweepolige skakelaar of 'n ander geskikte metode naby die battery afgeskakel kan word.
- (e) 'n Tenk wat 'n inhoudsvermoë van meer as 6 kl het, moet afgeskort word in vakke wat vloeistofdig is, en geen vak mag 'n groter inhoudsvermoë as 6 kl bevat nie: Met dien verstande dat voorgaande maksimum inhoudsvermoë van 6 kl hoogstens vyf persent oorskry kan word indien sodanige oorskryding deur die konstruksievereistes genoedsaak word: Voorts met dien verstande dat die vloeistofinhoud van enige sodanige vak te gener tyd meer as 98 persent van die totale inhoudsvermoë van die vak mag oorskry nie.
- (f) Die tenk moet stewig aan die voertuig vasgesit word, en in regstreekse aanraking met die metaal daarvan wees.
- (g) Die afvoerpype van die tenk moet voorsien wees van twee afsonderlike kleppe wat ver van mekaar af sit.

- (h) Efficient ventilating openings shall be fitted to each tank compartment and all such openings shall be covered with fine wire gauze with a mesh aperture not exceeding 600 micrometres and provided with a cock or valve: Provided that the Chief Fire Officer may permit the installation of other types of ventilating openings where these are shown to be equally efficient.
 - (i) Adequate provision shall be made to earth such vehicle efficiently so as to prevent the accumulation of a dangerous static charge of electricity in any part thereof, and, in addition, each pipe connection to the tank shall be so fitted as to ensure complete electrical connection between the tank and any receptacle being supplied with liquid therefrom.
 - (j) All electrical earth connections required in terms of this section shall be examined and entered in a log-book as required in terms of section 46(3), and the provisions of section 46(3) shall *mutatis mutandis* apply.
 - (k) The total quantity of flammable liquid conveyed by any road tank wagon or any number of such wagons constituting one haul shall, subject to the provisions of section 71, not exceed 30 kl.
- (2) Every vehicle other than a road tank wagon shall be—
- (a) of adequate capacity and construction to convey safely the quantity of flammable liquid which it is desired to convey on such vehicle;
 - (b) equipped with at least four wheels: Provided that a trailer forming part of an articulated vehicle shall for the purpose hereof be deemed to be equipped with four wheels; and
 - (c) so constructed and equipped as not to be likely to ignite any flammable liquid which may be conveyed in or on such vehicle.

Maintenance of Vehicles.

73. No person shall use or cause or allow to be used in or on any public place any vehicle for the transport of flammable liquid, unless such vehicle is maintained in good condition and in proper working order.

Opening to Tank.

74. All openings to the tank of any vehicle used for the transport of flammable liquid shall be kept securely and effectively closed at all times when not in use.

Supervision of Road Tank Wagon by Responsible Person.

75.(1) Every road tank wagon shall be under the constant supervision of a responsible person during the period such wagon is in use as such anywhere other than at a bulk depot.

(2) No road tank wagon which is not self-propelled and no other non-self-propelled vehicle so long as it is loaded with any flammable liquid shall be taken to or allowed to remain on any premises unless there is on the same premises at the same time a vehicle capable of and properly equipped for immediately towing it away from the premises.

- (h) Daar moet doeltreffende ventileeropeninge in elke tenkvak aangebring word, en elke sodanige opening moet bedek word met fyn gaasdraad met 'n maasopening van minstens 600 mikrometer en moet van 'n kraan of klep voorsien wees: Met dien verstande dat die Brandweerhoof kan toelaat dat ander soorte ventileeropeninge aangebring word, indien daar bewys is dat hulle ewe doeltreffend is.
 - (i) Sodanige voertuig moet van 'n doeltreffende aardleiding voorsien word ten einde te voorkom dat daar 'n gevaelike lading statiese elektrisiteit in enige gedeelte daarvan opgebou word en boonop moet elke pypverbinding met die tenk op so 'n wyse aangebring word dat daar volkome elektriese verbinding tussen die tenk en enige houer wat daaruit met vloeistof gevul word, bewerkstellig word.
 - (j) Alle elektriese aardleidings wat kragtens hierdie artikel vereis word, moet ondersoek en aangeteken word in 'n logboek, soos bepaal in artikel 46(3), en die bepalings van artikel 46(3) is *mutatis mutandis* van toepassing.
 - (k) Behoudens die bepalings van artikel 71, mag die totale hoeveelheid vlambare vloeistof, wat enige tenkvragmotor, of wat enige aantal sodanige vragmotors wat een trek uitmaak, vervoer, nie 30 kl oorskry nie.
- (2) Elke voertuig, uitgesonderd 'n tenkvragmotor moet—
- (a) groot genoeg wees en sterk genoeg gebou wees om die hoeveelheid vlambare vloeistof wat dit die voorname is om op sodanige voertuig te vervoer, veilig te vervoer;
 - (b) minstens vier wiele hê: Met dien verstande dat daar beskou word dat 'n sleepwa wat 'n deel van 'n gelede voertuig uitmaak, vir die toepassing hiervan, van vier wiele voorsien is; en
 - (c) sodanig gebou en toegerus wees dat dit nie waarskynlik vlambare vloeistof wat in of op sodanige voertuig vervoer word, sal laat ontbrand nie.

Onderhoud van Voertuie.

73. Niemand mag 'n voertuig vir die vervoer van vlambare vloeistof op 'n openbare plek gebruik; laat gebruik of toelaat dat dit daar gebruik word nie, tensy so 'n voertuig in 'n goeie en 'n behoorlike werkende toestand in stand gehou word.

Tenkopeninge.

74. Alle openinge in die tenk van 'n voertuig wat vir die vervoer van vlambare vloeistof gebruik word, moet te alle tye wanneer dit nie gebruik word nie deeglik en doeltreffend toegehou word.

'n Verantwoordelike Persoon moet Toesig oor die Tenkvragmotor Hou.

75.(1) Elke tenkvragmotor moet, terwyl dit as sodanig op enige ander plek as by 'n grootmaatdepot gebruik word, gedurig onder toesig van 'n verantwoordelike persoon wees.

(2) Geen tenkvragmotor wat nie selfaangedrewe is of enige ander voertuig wat nie selfaangedrewe is nie en wat met vlambare vloeistof gevul is, mag na enige perseel geneem word of op enige perseel gelaat word nie tensy daar terselfdertyd op dieselfde perseel 'n voertuig is wat in staat is en behoorlik toegerus is om sodanige voertuig onmiddellik van die perseel af weg te sleep.

(3) No road tank wagon or vehicle which is not self-propelled shall be allowed to remain in or on any street or other public place except for the minimum period necessary for unloading it and unless it is properly, firmly and directly connected to a vehicle capable of and properly equipped for immediately towing it away.

Position of Road Tank Wagon during Delivery Operations.

76.(1) No person shall —

- (a) cause or permit a road tank wagon to stand on or across any public footpath during delivery operations;
- (b) place the hose or cause or permit the hose to be placed across such footpath during such operations; or
- (c) cause or permit a road tank wagon to reverse onto or off any premises before or after delivery operations to such premises.

(2) Should it not be possible to comply with the provisions of subsection (1)(a), (b) and (c), the Council may permit the installation of an underground kerbside filling point, which shall be installed and maintained to the satisfaction of the Council.

Fire Extinguishers.

77.(1) No person shall use or cause or permit to be used any vehicle for the conveyance of flammable liquid, unless such vehicle is provided with at least one efficient fire extinguisher which shall be of the dry-chemical type and have a capacity of not less than 9 kg: Provided that where the Chief Fire Officer is of the opinion, having regard to the fire hazards of the particular case, that dry-chemical fire extinguishers are not adequate, such other fire extinguishers shall be installed as he may consider to be required by the said hazards.

(2) Such extinguishers shall be carried on the road tank wagon in such a position and shall be attached to the road tank wagon in such a manner as to be readily and easily accessible in the case of fire.

Agencies Likely to Ignite Flammable Liquids.

78. No person shall —

- (a) bring or cause or permit to be brought any fire, flame or other agency likely to ignite flammable liquid or its vapour within 3 m of any vehicle on or in which flammable liquid is transported;
- (b) carry or permit to be carried any matches, cigarette lighters or similar contrivances on any vehicle used for the transport of flammable liquid; or
- (c) while in attendance on such vehicle smoke or permit any other person thereon to smoke during the transport of flammable liquid or the filling of such vehicle with flammable liquid or the discharge of such liquid therefrom; or
- (d) smoke within 3 m of such vehicle during the filling of such vehicle with flammable liquid or the discharge of such liquid therefrom or while in at-

(3) Geen tenkvragmotor of voertuig wat nie selfaangedrewe is nie, mag in of op enige straat of ander publieke plek gelaat word behalwe vir die minimum tydperk wat nodig is om dit af te laat nie en tensy dit behoorlik, stewig en direk verbind is met 'n voertuig wat in staat is en behoorlik toegerus is om dit onmiddellik weg te sleep.

Posisie van 'n Tenkvragmotor Gedurende Afleweringbedrywighede.

76.(1) Niemand mag —

- (a) 'n tenkvragmotor op of oor 'n openbare sypaadjie laat staan of toelaat dat dit daar staan terwyl aflewering plaasvind nie;
- (b) die pompslang gedurende sodanige bedrywighede oor so 'n paadjie plaas, laat plaas of toelaat dat dit daar geplaas word nie; of
- (c) veroorsaak of toelaat dat enige tenkvragmotor op of van enige perseel agteruit beweeg voor of na aflewering op sodanige perseel.

(2) Indien nie aan die bepalings van subartikel 1(a), (b) en (c) voldoen kan word nie, kan die Raad die installasie van 'n ondergrondse sypaadjievulpunt toelaat wat tot voldoening van die Raad geinstalleer en in stand gehou moet word.

Brandblustoestelle.

77.(1) Niemand mag enige voertuig gebruik, laat gebruik of toelaat dat dit gebruik word vir die vervoer van vlambare vloeistof nie, tensy so 'n voertuig van minstens een doeltreffende droë chemiese tipe brandblustoestel met 'n inhoudsvermoë van minstens 9 kg voorsien is: Met dien verstande dat waar die Brandweerhoof, met inagneming van die brandgevare in 'n bepaalde geval, van mening is dat die droë chemiese tipe brandblustoestelle nie toereikend is nie, daar ander brandblustoestelle wat syns insiens deur genoemde brandgevare noodsaaklik gemaak word, aangebring moet word.

(2) Sodanige brandblustoestelle moet op so 'n plek op die tenkvragmotor vervoer word en op so 'n wyse daaraan vas wees dat dit, in die geval van brand, gou en maklik bereik kan word.

Middele wat Vlambare Vloeistof Moontlik aan die Brand Kan Laat Slaan.

78. Niemand mag —

- (a) enige vuur, vlam of ander middel wat moontlik vlambare vloeistof of die dampe daarvan aan die brand kan laat slaan, binne 3 m van 'n voertuig waarop of waarin vlambare vloeistof vervoer word, bring, laat bring, of toelaat dat dit daar gebring word nie;
- (b) vuurhoutjies, sigarettopstekers of soortgelyke toestelle op 'n voertuig wat vir die vervoer van vlambare vloeistof gebruik word, saamdra of toelaat dat dit saamgedra word nie;
- (c) terwyl hy sodanige voertuig onder sy sorg het, rook of toelaat dat iemand anders daarop rook terwyl vlambare vloeistof vervoer word of terwyl so 'n voertuig met vlambare vloeistof volgemaak word of sodanige vloeistof daaruit getap word; of
- (d) binne 3 m van sodanige voertuig af rook terwyl sodanige voertuig met vlambare vloeistof volgemaak word of terwyl vlambare vloeistof daaruit getap

tendance thereon permit any other person so to smoke.

Precautions.

79. Every person responsible for or concerned in the conveyance of flammable liquid shall take all reasonable precautions for the prevention of accident by fire or explosion and for the prevention of access by any unauthorized person to any container whilst in transit.

Restriction of Scope of Certain Sections.

80.(1) The provisions of section 70 to 77 inclusive shall not apply to the conveyance of flammable liquid on a vehicle, not being a road tank wagon —

- (a) of a quantity not exceeding 200 l of Class A flammable liquid or 400 l of Class B flammable liquid, in securely closed metal containers of a capacity not exceeding 50 l each; or
- (b) of a quantity not exceeding 600 l of Class A flammable liquid or 1 kl of Class B flammable liquid contained in securely closed metal containers of a capacity not less than 200 l each.

(2) Such containers shall be substantially constructed and packed in such a manner as to prevent leakage and obviate their becoming broken, defective or insecure in the course of conveyance.

(3) No flammable liquid shall be conveyed in or on any steam-driven vehicle or in or on any trailer or other vehicle drawn by a vehicle so driven.

DRY-CLEANING ROOMS: GENERAL.

Certificate for Dry-Cleaning Room.

81.(1) No person shall use or cause or permit to be used any room as a dry-cleaning room unless and until such room has been duly registered as such in terms of these by-laws.

(2) No certificate shall be issued in respect of any premises for use as dry-cleaning room unless and until such premises comply with the requirements of these by-laws.

(3) The provisions of sections 5 to 12 inclusive and 15 shall apply *mutatis mutandis* to a certificate in terms of this section.

Use of Dry-Cleaning Rooms.

82. No dry-cleaning room shall be used for any purpose other than that of dry-cleaning and purposes reasonably incidental thereto.

Installation of Machinery.

83.(1) No person shall install or cause or permit to be installed any dry-cleaning machinery such as washing machines, clarifiers, stills or settling tanks elsewhere than in the dry-cleaning room.

(2) All machinery shall be efficiently electrically earthed.

(3) All such electrical earth connections shall be examined and entered in a log-book as required in terms of section 46(3).

word, of terwyl hy dit onder sy sorg het, iemand anders toelaat om aldus te rook nie.

Voorsorgmaatreëls.

79. Elkeen wat vir die vervoer van vlambare vloeistof verantwoordelik is of daarby betrokke is, moet alle redelike voorsorgmaatreëls tref ten einde ongelukke deur brand of ontploffing te voorkom, en te verhoed dat 'n ongemagtigde persoon toegang tot enige houer verkry terwyl dit onderweg is.

Beperking van die Toepassing van Sekere Artikels.

80.(1) Die bepalings van artikels 70 tot en met 77 is nie van toepassing op die vervoer van vlambare vloeistof op 'n ander voertuig as 'n tenkvragmotor nie, indien daar —

- (a) 'n hoeveelheid van hoogstens 200 l vlambare vloeistof Klas A, of 400 l vlambare vloeistof Klas B in metaalhouers elk met 'n inhoudsvermoë van hoogstens 50 l en wat deeglik toe is, vervoer word; of
- (b) 'n hoeveelheid van hoogstens 600 l vlambare vloeistof Klas A of 1 kl vlambare vloeistof, Klas B, in metaalhouers wat deeglik toe is, met 'n inhoudsvermoë van minstens 200 l elk, vervoer word.

(2) Sodanige houers moet sterk gemaak wees en op so 'n wyse gepak word dat hulle nie sal lek, stukkend raak, defek of los raak terwyl hulle vervoer word nie.

(3) Geen vlambare vloeistof mag in of op 'n stoom-aangedrewe voertuig of in of op 'n sleepwa of ander voertuig wat deur 'n voertuig, wat aldus aangedryf word, getrek word of vervoer word nie.

DROOGSKOONMAAKLOKALE: ALGEMEEN.

Sertifikaat ten Opsigte van 'n Droogskoonmaaklokaal.

81.(1) Niemand mag 'n vertrek as 'n droogskoonmaaklokaal gebruik, laat gebruik, of toelaat dat dit as sodanig gebruik word nie, tensy en alvorens so 'n vertrek behoorlik kragtens hierdie verordeninge as sodanig geregistreer is.

(2) Daar word geen sertifikaat vir die gebruik van 'n perseel as 'n droogskoonmaaklokaal uitgereik nie tensy en alvorens sodanige perseel aan die vereistes van hierdie verordeninge voldoen.

(3) Die bepalings van artikels 5 tot en met 12 en 15 is *mutatis mutandis* van toepassing op 'n sertifikaat wat kragtens hierdie artikel uitgereik word.

Gebruik van Droogskoonmaaklokale.

82. Geen droogskoonmaaklokaal mag vir enige ander doel as vir droogskoonmaakwerk en vir doeleindes wat redelikerwys daarmee in verband staan, gebruik word nie.

Installasie van Masjinerie.

83.(1) Niemand mag enige droogskoonmaakmasjinerie soos byvoorbeeld wasmasjiene, suiweringsstoestelle, distilleerketels of neerslagtenks elders as in 'n droogskoonmaaklokaal installeer, laat installeer of toelaat dat dit daar geïnstalleer word nie.

(2) Alle masjinerie moet elektries doeltreffend met die aarde verbind wees.

(3) Alle sodanige elektriese aardleidings moet ondersoek word en in 'n logboek, soos in artikel 46(3) vereis, aangeteken word.

Boilers.

84. No boiler shall be installed in such proximity or in such a position or manner in relation to a dry-cleaning room that it is likely, in the opinion of the Chief Fire Officer, to ignite any flammable liquid in or vapour escaping from the room.

85. Notwithstanding the provisions of section 83(1), the installation of cleaning machines of the tumbler type shall be permitted elsewhere than in a dry-cleaning room: Provided that the machine so installed is equipped with an effective system of ventilation by the exhaust method.

Electrical Equipment.

86.(1) Subject to the provisions of subsection (2), no person shall install or cause or permit to be installed in any dry-cleaning room where flammable liquids of Class A or Class B are used, any electrical machinery or other electrical apparatus other than —

- (a) an electric light enclosed in an outer flame-proof fitting;
- (b) electric wires, protected throughout by seamless metal tubes the junctions of which are screwed together or cable approved by the Council by reference to current electrical practice;
- (c) one electric push-button switch of construction known as flameproof which shall be situated not less than 1 m above the level of the floor and constructed and connected for stopping machinery in case of emergency.

(2) Any electric motor installed in a dry-cleaning room where flammable liquids of Class A are used shall be of flame-proof construction, and any such motor installed in any such room where flammable liquids of Class B are used shall be of flame-proof or totally enclosed construction.

Handling of Flammable Liquid.

87. The storage tank shall be connected to the dry-cleaning machinery and no flammable liquid shall be handled during and cleaning process: Provided that a total quantity not exceeding 20 l at any one time may be handled in one or more containers for the purpose of handwashing or spotting.

Danger Notice at Entrance.

88. The words "DANGER — NO SMOKING" in both official languages shall be prominently displayed in letters not less than 150 mm high outside every entrance to every dry-cleaning room and shall at all times be maintained in such position and in a legible condition.

Removal of Foreign Matter and Metallic Substances from Garments.

89. No person shall dry-clean or cause or permit to be dry-cleaned any article of clothing or other textile unless and until such article has been thoroughly examined and all objects such as matches, metallic substances, metal buttons or other objects which are liable to cause sparks have been removed therefrom.

Stoomketels.

84. Geen stoomketel mag so na aan, of in so 'n posisie of op so 'n wyse in verhouding tot, 'n droogskoonmaaklokaal aangebring word dat dit, volgens die mening van die Brandweerhoof, waarskynlik vlambare vloeistof in, of die dampe wat ontsnap uit, die lokaal aan die brand kan laat slaan nie.

85. Ondanks die bepalings van artikels 83(1), kan wasmasjiene van die tuimelaartipe elders as in 'n droogskoonmaaklokaal geïnstalleer word: Met dien verstande dat die masjiene wat aldus geïnstalleer word, toegerus is met 'n doeltreffende ventilasiestelsel van die uitlaat-tipe.

Elektriese Toerusting.

86.(1) Behoudens die bepalings van subartikel (2), mag niemand elektriese masjienerie of ander elektriese apparaat in 'n droogskoonmaaklokaal waar vlambare vloeistowwe Klas A of Klas B gebruik word, installeer, laat installeer of toelaat dat dit daar geïnstalleer word nie, uitgesonderd —

- (a) 'n elektriese gloeilamp wat 'n vlamdigte omhulsel buite-on het;
- (b) elektriese draadleidings wat heeltemal deur naatlose metaalbuise waarvan die lasse vasgeskroef word, beskerm word of kabels wat die Raad ooreenkomsig die gangbare elektrotegniese praktyk goedgekeur het;
- (c) een elektriese drukknopskakelaar van die konstruksie wat as vlamdig bekendstaan, wat minstens 1 m bokant die vloervlak aangebring is, en wat op so 'n wyse gemaak en verbind moet wees dat dit in noodgevalle gebruik kan word om die masjienerie mee af te skakel.

(2) Enige elektriese motor wat in 'n droogskoonmaaklokaal waarin daar vlambare vloeistowwe Klas A gebruik word, geïnstalleer is, moet vlamdig gemaak wees en enige sodanige motor wat in sodanige lokaal waar daar vlambare vloeistowwe Klas B gebruik word, geïnstalleer is, moet vlamdig gemaak of geheel en al deur 'n omhulsel bedek wees.

Die Hantering van Vlambare Vloeistof.

87. Die opbergtenk moet met die droogskoonmaakmasjienerie verbind wees, en geen vlambare vloeistof mag tydens die droogskoonmaakbedrywighede gehanteer word nie: Met dien verstande dat hoogstens 20 l te enige enkele tyd in een of meer houers gehanteer kan word met die doel om hand-waswerk te verrig of om kolle te verwyder.

Gevaarkennisgewing by die Ingang.

88. Die woorde "GEVAAR — MOENIE ROOK Nie" moet opvallend in albei amptelike tale en in letters wat minstens 150 mm hoog is aan die buitekant van elke toegang tot elke droogskoonmaaklokaal aangebring word, en moet te alle tye op dié plek in 'n leesbare toestand in stand gehou word.

Verwydering van Vreemde Voorwerpe en Metaalbestande dele uit Kledingstukke.

89. Niemand mag 'n kledingstuk of 'n ander weefstof droogskoonmaak, laat droogskoonmaak of toelaat dat dit droogskoongemaak word nie, tensy en alvorens so 'n artikel deeglik ondersoek is en alle voorwerpe soos vuurhoutjies, metaalbestanddele, metaalknope of ander voorwerpe wat moontlik vonke kan veroorsaak, daaruit verwijder is.

Instructions to Employees.

90. The occupier shall cause all persons employed in the dry-cleaning room to be thoroughly instructed as to the hazards involved in the use of flammable liquids and in the handling and method of usage of all fire appliances required in terms of these by-laws to be on the premises, and shall repeat such instructions quarterly.

Unauthorized Persons or Acts.

91.(1) No person, other than a person lawfully employed on the premises, shall enter any dry-cleaning room without the express permission of the occupier or person in charge.

(2) No person shall commit any act which is liable to cause fire, explosion or other damage to a dry-cleaning room or its contents.

Position of Machinery.

92. All dry-cleaning machinery such as washing machines, clarifiers, stills and settling tanks shall be situated as near as reasonably possible to the exhaust ducts as required in terms of section 98.

Shafting.

93. Where any machinery is driven by means of shafts from motive power outside the dry-cleaning room, the driving shaft shall pass through a gas-proof wall box which shall be installed at the point where such shafting enters such dry-cleaning room.

Scouring or Brushing Table.

94. Every table used for washing or brushing any material with flammable liquid shall comply with the following requirements:

- (a) Such table shall be provided with a liquid-tight top with a curb on all sides not less than 25 mm high.
- (b) The top of such table shall be so pitched as to ensure thorough draining by a pipe of not less than 25 mm diameter directly connected to an underground tank through a trap which shall prevent the return of vapour.
- (c) Metal tops shall be effectively electrically earthed.
- (d) Such table shall be so secured to the floor or wall so as not to disturb the electrical earth and drain connections.

Portable Lamp.

95. No person shall take or cause or permit to be taken any flash lamp or any other light or lamp into any dry-cleaning room except an electrical light or safety lamp which has been fitted with an outer flame-proof fitting.

SPECIAL PROVISIONS WHERE CLASS A FLAMMABLE LIQUIDS ARE USED FOR DRY-CLEANING.*Construction of Dry-Cleaning Rooms.*

96. Every dry-cleaning room shall be constructed in accordance with the following requirements:

Opdragte aan Werknemers.

90. Die okkupant moet almal wat in die droogskoonmaaklokaal in diens is, behoorlik inlig omtrent die gevare verbonde aan die gebruik van vlambare vloeistof, asook ten opsigte van die hantering en die aanwendingsmetode van alle brandblustoestelle wat ingevolge hierdie verordeninge op die perseel gehou moet word, en sodanige voorligting moet elke kwartaal herhaal word.

Ongemagtigde Persone of Dade.

91.(1) Niemand, uitgesonderd 'n persoon wat wettiglik op die perseel in diens is, mag 'n droogskoonmaaklokaal sonder die uitdruklike toestemming van die okkupant of die persoon wat daar in beheer is, binnegaan nie.

(2) Niemand mag 'n daad verrig wat moontlik 'n brand of 'n ontploffing kan veroorsaak of ander skade aan die droogskoonmaaklokaal of die inhoud daarvan kan berokken nie.

Plasing van Masjinerie.

92. Alle droogskoonmaakmasjinerie soos wasmasjiene, suiweringsstoestelle, distilleerketels en neerslagtenks moet so na as redelikerwyse moontlik is, aan die uitleatopeninge soos by artikel 98 vereis, geplaas wees.

Asleidings.

93. Waar masjinerie aangedryf word deur middel van asse wat deur dryfkrag buite die droogskoonmaaklokaal aangedryf word, moet die dryfas deur 'n gasdigte muurkas gaan, wat op die plek waar sodanige as die droogskoonmaaklokaal binnekom, aangebring moet word.

Was- of Borseltafels.

94. Elke tafel wat gebruik word om materiaal met vlambare vloeistof te was of op af te borsel, moet aan die volgende vereistes voldoen.

- (a) So 'n tafel moet voorsien wees van 'n vloeistofdigte blad wat rondom 'n rand van minstens 25 mm hoog, aan het.
- (b) Die blad van so 'n tafel moet skuins wees, sodat alle vloeistof behoorlik kan wegloop deur middel van 'n pyp met 'n deursnee van minstens 25 mm wat regstreeks met 'n ondergrondse tenk verbind is en wat 'n afsluiter aan het wat voorkom dat dampe terugkeer.
- (c) Metaalblaaike moet elektries behoorlik met die aarde verbind wees.
- (d) So 'n tafel moet op so 'n wyse aan die vloer of muur vasgesit word dat die elektriese aardleiding en afvoerpyp nie versteur kan word nie.

Draagbare Lampe.

95. Niemand mag 'n flitslamp of 'n ander lig of lamp, uitgesonderd 'n elektriese gloeilamp of 'n veiligheidslamp, wat 'n vlamdigte omhulsel buitenom het, in 'n droogskoonmaaklokaal inneem, laat inneem of toelaat dat dit daar ingeneem word nie.

SPESIALE BEPALINGS IN GEVALLE WAAR VLAMBARE VLOEISTOF KLAS A VIR DROOGSKOONMAAKDOELEINDES GEBRUIK WORD.*Die Bou van Droogskoonmaaklokale.*

96. Elke droogskoonmaaklokaal moet ooreenkomsdig die volgende vereistes gebou word:

- (a) The walls shall be constructed of brick or concrete or similar suitable material, the floor of concrete or other impervious material and the roof of fire-resistant material.
- (b) All window frames shall be constructed of metal, glazed with wire woven glass and shall be of the opening type. Each single pane shall not exceed 450 mm x 450 mm.
- (c) All door frames shall be of metal and any internal door shall be made of hardwood of a thickness of not less than 50 mm and completely covered with metal of not less than 0,9 mm in thickness. Doors to the open air shall be constructed as above or shall be close-fitting metal on an angle-iron frame and having an all round overlap of 50 mm. The type of door fitted shall be at the discretion of the Chief Fire Officer.
- (d) A sill of concrete at least 150 mm in height shall be erected across all door openings at surface level or the floor of the room shall be 150 mm below the adjacent surface level.
- (e) The dry-cleaning room shall be situated not closer than 1,5 m to any public thoroughfare or building unless the wall or walls which are exposed to such thoroughfare or building are constructed without openings: Provided that not more than two sides of any dry-cleaning room shall be without openings.
- (f) There shall be provided at least two doors opening outwards, one directly into the open air. Such doors shall be so situated and at such a distance from each other as to allow the free and unimpeded escape of persons within the dry-cleaning room through either door in the case of fire or other danger.
- (g) No dry-cleaning room shall have any opening into any other room or building: Provided that subject to compliance with the conditions hereunder set out any room used or intended to be used solely for the purpose of drying materials which have been cleaned or treated with flammable liquid may be constructed under the same roof as the dry-cleaning room:
- (i) Such drying room shall be separated from the dry-cleaning room by a wall constructed of non-combustible material; and
 - (ii) the entrance to such drying room shall be provided with a metal door and frame.
- (h) No dry-cleaning room shall be situated below or above any other room or building.
- (i) Every dry-cleaning room shall be maintained at all times in accordance with the provisions of this section.

Steam Pipes.

97.(1) Every dry-cleaning room shall be fitted with at least one steam pipe not less than 25 mm in diameter. Every such pipe shall be provided with —

- (a) perforations or jets of at least 6 mm in diameter and so spaced as to give as near as practicable an equal distribution of steam in such a manner that such room can be immediately flooded with steam in the case of fire; and

- (a) Die mure moet van baksteen of beton of van soortgelyke geskikte materiaal, die vloer van beton of ander syferdigte materiaal en die dak van brandbestande materiaal gebou word.
- (b) Alle vensterrame moet van metaal gemaak wees en moet ruite van splintervrye draadglas in hê, en moet van die tipe wees wat oopgemaak kan word. Elke afsonderlike ruit mag nie groter as 450 mm x 450 mm wees nie.
- (c) Alle deurkosyne moet van metaal gemaak wees en enige binnedeur moet van hardehout met 'n dikte van minstens 50 mm wees en moet geheel en al met metaal van minstens 0,9 mm dik bedek wees. Buite-deure moet, soos hierbo genoem, vervaardig wees, of moet styfpassende metaaldeure van minstens 3 mm dik wees en moet aan hoekysterkosyne gemonteer word en rondom 'n oorslag van 50 mm hê. Die tipe deur wat ingesit word is volgens die diskresie van die Brandweerhoof.
- (d) 'n Drumpel van beton, minstens 150 mm hoog, moet op die grondhoogte dwarsoor alle deuropeninge aangebring word, of die vloer van die vertrek met 150 mm laer as die aangrensende grondhoogte wees.
- (e) Die droogscoonmaaklokaal moet nie nader as 1,5 m van 'n openbare deurgang of gebou af wees nie, tensy die muur of mure wat aan sodanige weg of gebou front, geen openinge in het nie: Met dien verstande dat hoogstens twee kante van 'n droogscoonmaaklokaal sonder openinge mag wees.
- (f) Daar moet minstens twee deure wat na buite oopmaak, verskaf word, en een daarvan moet regstreeks in die buitelug oopgaan. Sodanige deure moet so geleë wees en so ver van mekaar af wees, dat persone binne die droogscoonmaaklokaal in die geval van brand of ander gevær, vry en ongehinderd deur enigeen van die deure kan ontsnap.
- (g) Geen droogscoonmaaklokaal mag 'n opening na 'n ander vertrek of gebou toe hê nie: Met dien verstande dat, mits daar aan die voorwaardes hieronder uiteengesit, voldoen word, enige vertrek wat uitsluitend gebruik word of bedoel is om gebruik te word om materiaal wat skoongemaak is of met vlaambare vloeistof behandel is, droog te maak, onder dieselfde dak as die droogscoonmaaklokaal gebou kan word:
- (i) So 'n droogkamer moet deur middel van 'n muur wat van nie-brandbare materiaal gebou is, van die droogscoonmaaklokaal geskei wees; en
 - (ii) die ingang na sodanige droogkamer moet 'n metaaldeur en kosyn hê.
- (h) Geen droogscoonmaaklokaal mag onder of bokant 'n ander vertrek of gebou geleë wees nie.
- (i) Elke droogscoonmaaklokaal moet te alle tye ooreenkomsdig die bepalings van hierdie artikel in stand gehou word.

Stoompype.

- 97.(1) Elke droogscoonmaaklokaal moet minstens een stoompyp met 'n deursnee van minstens 25 mm hê. Elke sodanige pyp moet voorsien wees van —
- (a) gaatjies of sproeiers met 'n deursnee van minstens 6 mm, wat so versprei is dat daar, sover doenlik, 'n eweredige verspreiding van stoom op so 'n wyse kan plaasvind dat die lokaal ingeval van brand onmiddellik met stoom gevul kan word; en

(b) a steam trap or other effective means of preventing the accumulation of water within such pipe.

(2) An adequate steam supply for such pipe or pipes shall be maintained continuously while any flammable liquid is contained in any washing machines, clarifiers, stills or similar appliances.

(3) Such steam supply system shall be provided with a valve placed in the service line and situated outside the building in an easily accessible position in the case of fire.

Ventilation of Dry-Cleaning Room.

98.(1) Every dry-cleaning room shall be ventilated with a mechanical system of exhaust and inlet ventilation of such design, construction and capacity as will adequately remove flammable liquid vapour from such room and discharge such vapour into the open air at a point above the roof of such room and not within 4,5 m of any opening to any building. The motor or motors of such mechanical exhaust and inlet ventilation system shall comply with the provisions of section 86(2).

(2) Such system of ventilation shall be capable of providing an air velocity of a minimum of 0,5 mm per second through any cross-section of the room so as adequately to remove flammable vapour from the room and change the air therein.

(3) The blades of all ventilating fans shall be made of non-ferrous metal.

(4) All exhaust ventilation ducts shall be installed —

- (a) as near ground level as practicable: Provided that where any such duct or any portion thereof is situated at a level which is less than 150 mm above the level of the dry-cleaning room floor, adequate provision shall be made to prevent the escape of flammable liquid therefrom in the case of fire or otherwise;
- (b) as near as practicable to the points of origin of flammable liquid or the dry-cleaning machinery such as washing machines, clarifiers, stills, settling tanks and similar appliances.

(5) Any person discovering a fire in any dry-cleaning room shall immediately take all possible steps to shut down the exhaust ventilating system.

SPECIAL PROVISIONS WHERE CLASS B FLAMMABLE LIQUID IS USED FOR DRY-CLEANING.

Construction of Dry-Cleaning Room.

99. Every dry-cleaning room shall be constructed and maintained in accordance with the following requirements:

- (a) The walls of the room shall be constructed of brick or concrete or other material which, in the opinion of the Chief Fire Officer, is suitable, the floor shall be of concrete or other impervious material, and the roof shall be of reinforced concrete: Provided that the roof may be constructed of other material where no other rooms, buildings or premises are, in the opinion of the Chief Fire Officer, likely to be endangered by an outbreak of fire in the dry-cleaning room.

(b) 'n Stoomafsluiter of 'n ander doeltreffende middel om te voorkom dat water in so 'n pyp vergaar.

(2) 'n Voldoende voorraad stoom vir so 'n pyp of pype moet voortdurend, onderwyl daar vlambare vloeistof in wasmasjiene, suiweringsstoestelle, distilleerketels of soortgelyke toestelle is, beskikbaar gehou word.

(3) So 'n stoomtoevoerstelsel moet voorsien wees van 'n klep wat buite die gebou in die toevooerpyp aangebring is op 'n plek wat, in die geval van brand, maklik toeganklik is.

Ventilasie van Droogskoonmaaklokaal.

98.(1) Elke droogskoonmaaklokaal moet geventileer word deur middel van 'n meganiese stelsel van uit- en inlaatventilasie van sodanige ontwerp, konstruksie en kapasiteit dat dit die dampe van die vlambare vloeistof doeltreffend uit sodanige lokaal verwyder en die dampe in die buitelug uitlaat op 'n plek bokant die dak van sodanige lokaal wat minstens 4,5 m van enige opening van enige gebou af geleë is. Die motor of motors van sodanige meganiese uit- en inlaatventilasiestelsel moet aan die bepalings van artikel 86(2) voldoen.

(2) Sodanige ventilasiestelsel moet in staat wees om 'n stroomsnelheid van minstens 0,5 m per sekonde deur enige deursnee van die lokaal te verskaf ten einde die dampe van die vlambare vloeistof doeltreffend uit die lokaal te verwyder en die lug daarin te wissel.

(3) Die lemme van alle ventilasiewaaiers moet van nie-ysterhoudende metaal vervaardig wees.

(4) Alle ventilasie-uitlaatpype moet —

- (a) so na aan die grondhoogte as doenlik aangebring word: Met dien verstande dat indien sodanige pyp of enige gedeelte daarvan minder as 150 mm bokant die vlak van die droogskoonmaaklokaal se vloer geleë is, daar doeltreffende voorsorg getref moet word om te voorkom dat vlambare vloeistof, in die geval van brand of andersins, daardeur ontsnap;
- (b) so na as doenlik aan die plekke van oorsprong van vlambare vloeistof of die droogskoonmaakmasjinerie, soos wasmasjiene, suiweringsstoestelle, distilleerketels, neerslagtenks en soortgelyke toestelle, aangebring word.

(5) Enigiemand wat 'n brand in 'n droogskoonmaaklokaal ontdek, moet onmiddellik alle moontlike stappe doen om die ventilasieuitlaatstelsel af te sluit.

SPESIALE BEPALINGS IN GEVALLE WAAR VLAMBARE VLOEISTOF KLAS B VIR DROOGSKOONMAAKDOELEINDES GEBRUIK WORD.

Bou van Droogskoonmaaklokaal.

99. Elke droogskoonmaaklokaal moet ooreenkomsdig die volgende vereistes gebou en in stand gehou word:

- (a) Die mure moet van baksteen of beton of van ander gesikte materiaal, na goedunke van die Brandweerhoof, gebou word, die vloer moet van beton of ander syferdigte materiaal en die dak moet van gewapende beton vervaardig wees: Met dien verstande dat die dak van ander materiaal vervaardig kan word na goedunke van die Brandweerhoof in die geval waar daar geen ander vertrekke, geboue of persele is wat deur 'n brand in die droogskoonmaaklokaal in gevaar gestel kan word nie.

- (b) A sill of concrete at least 150 mm in height shall be erected across all door openings at surface level or the floor of the room shall be 150 mm below the adjacent surface level.
- (c) (i) The room shall be provided with at least two doors to be made either of hard-wood of a thickness not less than 50 mm and completely covered with metal of not less than 0,56 mm in thickness or with close-fitting metal doors not less than 3 mm in thickness carried on an angle-iron frame and having an all round overlap of 50 mm. The type of door fitted shall be at the discretion of the Chief Fire Officer.
 (ii) The said doors shall open outwards and be so situated in general and in relation to each other and in particular at such a distance from each other, as to allow the free and unimpeded escape of persons within the room through both of them simultaneously in case of fire or other danger.
- (d) All window frames shall be constructed of metal, glazed with wire woven glass and shall be of the opening type. Each single pane shall not exceed 450 mm x 450 mm.
- (e) No dry-cleaning room shall be situated below or above any other room or building which is not provided to the satisfaction of the Chief Fire Officer with adequate means of escape for its occupants to safety, in the event of fire.
- (f) No dry-cleaning room shall be situated in the basement of a building or at such a depth that the floor level is more than 60 mm below the main level of the ground immediately surrounding it.

Ventilation of Dry-cleaning Room.

100. Every dry-cleaning room shall be ventilated with a mechanical system of exhaust and inlet ventilation conforming to and complying with the provisions of sections 56 and 86(2).

SPRAY ROOMS.

Registration of Spray Room.

101.(1) No person shall spray or cause or permit to be sprayed any vehicle or article with any flammable liquid in any room or building, unless such person is in possession of a spray permit in respect of such room or building.

(2) Such permit shall only be valid for the period terminating on the next succeeding 31st day of December.

(3) The provisions of sections 5 to 12 inclusive and 15 shall apply *mutatis mutandis* to a permit in terms of this section.

Issue of Spray Room Permit.

102. No spray room permit shall be granted in respect of any spray room unless and until such room complies with the requirements of these by-laws.

Construction of Spray Room.

103.(1) Subject to the provisions of subsection (4), every spray room shall be constructed in accordance with the following requirements:

- (b) 'n Drumpel van beton, minstens 150 mm hoog, moet op die grondhoogte dwarsoor al die deuropeninge aangebring word, of die vloer van die vertrek moet 150 mm laer as die aangrensende grondhoogte wees.
- (c) (i) Die lokaal moet minstens twee deure hê wat van hardehout wat minstens 50 mm dik is en geheel en al bedek met metaal van minstens 0,56 mm dik, vervaardig is, óf nousluitende deure van metaal minstens 3 mm dik, wat aan 'n hoekysterraam bevestig is en wat 'n oorslag van minstens 50 mm rondom het. Die tipe deur wat aangebring moet word, moet na goeddunke van die Brandweerhoof wees.
 (ii) Die genoemde deure moet na buite oopgaan en moet in die algemeen so geplaas en in verhouding tot mekaar in besonder sover van mekaar af wees, dat mense binne-in die lokaal in geval van brand of ander gevaaar, vry en ongehinderd by albei die deure gelyktydig kan uitkom.
- (d) Alle vensterrame moet van metaal gemaak wees, moet ruite van splintervrye draadglas in hê, en moet van die tipe wees wat oopgemaak kan word. Elke afsonderlike ruit mag nie groter as 450 mm x 450 mm wees nie.
- (e) Geen droogkoonmaaklokaal mag onder of bokant 'n ander vertrek of gebou wat nie tot voldoening van die Brandweerhoof voorsien is met voldoende fasiliteite vir die veilige ontsnapping van die mense daarin in die geval van brand, geleë wees nie.
- (f) Geen droogkoonmaaklokaal mag in die kelderverdieping van 'n gebou geleë wees nie, of so diep dat die oppervlak van die vloer meer as 600 mm onderkant die algemene vlak van die grond in die onmiddellike omgewing daarvan is nie.

Ventilasie van Droogkoonmaaklokaal.

100. Elke droogkoonmaaklokaal moet geventileer word deur middel van 'n meganiese stelsel van uit- en inlaatventilasie in ooreenstemming met en wat voldoen aan die bepalings van artikels 56 en 86(2).

SPUITLOKALE.

Registrasie van Spuitlokale.

101.(1) Niemand mag enige voertuig of artikel met vlambare vloeistof in 'n vertrek of gebou spuit, laat bespuit, of toelaat dat dit bespuit word nie, tensy sodanige persoon in besit van 'n spuitpermit ten opsigte van sodanige lokaal of gebou, is.

(2) Sodanige permit is slegs tot op die eersvolgende 31ste dag van Desember geldig.

(3) Die bepalings van artikels 5 tot en met 12 en 15 is *mutatis mutandis* van toepassing op 'n permit ingevolge hierdie artikel.

Uitreiking van Spuitlokaalpermit.

102. Geen spuitlokaalpermit word ten opsigte van 'n spuitlokaal uitgercik nie, tensy en alvorens sodanige lokaal aan die vereistes van hierdie verordeninge voldoen.

Bou van Spuitlokaal.

103.(1) Behoudens die bepalings van subartikel (4) moet elke spuitlokaal ooreenkomsdig die volgende vereistes gebou word:

- (a) The walls shall be constructed of brick or concrete of a minimum thickness of 100 mm or any other material which, in the opinion of the Chief Fire Officer, is suitable for the purpose, the floor shall be constructed of concrete or other impervious material to the satisfaction of the Chief Fire Officer and the roof shall be constructed of reinforced concrete.
- (b) The room shall be fitted with hard-wood doors of a thickness of not less than 50 mm and completely covered with metal of not less than 0,56 mm in thickness or with close-fitting metal doors of not less than 3 mm in thickness, carried on an angle-iron frame and having an all-round overlap of not less than 50 mm. Such doors shall open outwards and shall be kept locked after normal working hours. The type of door required to be fitted shall be at the discretion of the Chief Fire Officer.
- (c) All window frames shall be constructed of metal, glazed with wire woven glass and shall be of the non-opening type. Each single pane shall not exceed 450 mm x 450 mm.
- (d) Every spray room shall be ventilated with a mechanical system of exhaust and inlet ventilation capable of providing an air velocity of a minimum of 0,5 m per second through any cross-section of the room so as adequately to remove flammable vapour from the room and change the air therein. The centre line of the inlets to such system shall be at least 450 mm above the level of the floor. The said system shall operate at all times during working hours including any intervals for lunch or tea and shall operate for not less than five minutes after each working period.
- (e) Every spray room with a floor area in excess of 20 m² shall be provided with at least two doors, constructed as prescribed in paragraph (b), situated at such distance from each other as to allow the free and unimpeded escape of persons within the spray room from either door in the case of fire or other danger.
- (f) Where a spray room is subdivided into spray booths as prescribed in paragraph (g), each such booth shall be ventilated in accordance with the provisions of paragraph (d).
- (g) Where part or the whole of any spray room is subdivided by partitions into separate compartments or booths (hereinafter described as spray booths) such spray booth shall be constructed of metal or other non-combustible material.
- (h) All exhaust vents shall be constructed of non-combustible material and so designed and constructed that all vapours are expelled from the interior of a building into the open air at a point not less than 1 m above the apex of the roof of the building: Provided that the Chief Fire Officer may permit such vapours to be expelled into the open air at a lesser distance than 1 m above the apex of the roof if in his opinion, the vapour is not likely to be ignited. In the event of the exhaust vents being external to the spray room and in communication with any other internal portion of the building, such vents shall be protected by either 100 mm brick-work or 50 mm asbestos cement lagging. There shall be no right angle bends in the vents.
- (a) Die mure moet van baksteen of beton wat minstens 100 mm dik is, gebou word of van enige ander materiaal wat, na die mening van die Brandweerhoof, vir die doel geskik is, en die vloer moet van beton of 'n ander sypeldigte materiaal tot voldoening van die Brandweerhoof en die dak van gewapende beton gebou wees.
- (b) Die lokaal moet hardehoutdeure hê wat minstens 50 mm dik is en wat geheel en al bedek is met metaal van minstens 0,56 mm dik, of nousluitende metaaldeure, minstens 3 mm dik wat aan 'n hoekysterraam bevestig is en wat rondom 'n oorslag van minstens 50 mm het. Sodanige deure moet na buite toe oopmaak en moet na die gewone werkure gesluit gehou word. Die tipe deur wat aangebring moet word, moet na goeddunke van die Brandweerhoof wees.
- (c) Alle vensterrame moet van metaal gemaak wees, moet ruite van splintervrye draadglas in hê en moet van die tipe wees wat nie oopgemaak kan word nie. Elke afsonderlike ruit mag nie groter as 450 mm x 450 mm wees nie.
- (d) Elke spuitlokaal moet geventileer word deur middel van 'n meganiese stelsel van uit- en inlaatventilasie wat in staat is om 'n stroomsnelheid van minstens 0,5 m per sekonde deur enige deursnee van die lokaal te verander ten einde die damp van die vlambare vloeistof doeltreffend uit die lokaal te verwyn en die lug daarin te wissel. Die middellyn van die inlaatopeninge van sodanige stelsel moet minstens 450 mm bokant die vloeroppervlakte geleë wees. Genoemde stelsel moet voortdurend tydens werktye, met inbegrip van die eet- en teepouse, en minstens vyf minute na afloop van elke werktydperk, in werking wees.
- (e) Elke spuitlokaal met 'n vloerruimte van meer as 20 m² moet van minstens twee deure, gebou soos in paragraaf (b) voorgeskryf, voorsien wees en sodanige afstand van mekaar geleë wees dat alle persone in die spuitlokaal vry en ongehinderd by elke deur kan ontsnap in geval van 'n brand of ander gevvaar.
- (f) Indien 'n spuitlokaal in spuithokkies, soos in paragraaf (g) omskryf, afgeskort is, moet elke sodanige hokkie ooreenkomsdig die bepalings van paragraaf (d) geventileer word.
- (g) Indien 'n gedeelte van of die hele spuitlokaal deur middel van afskortings in afsonderlike afdelings of hokkies (wat hierna spuithokkies genoem word) verdeel is, moet sodanige spuithokkies van metaal of ander nie-brandbare materiaal vervaardig wees.
- (h) Alle uitlaatopeninge moet van nie-brandbare materiaal gemaak word en so ontwerp en gebou wees dat alle damp van die binnekant van 'n gebou af na die buitelug gevoer word op 'n plek minstens 1 m bokant die toppunt van die dak van die gebou: Met dien verstaande dat die Brandweerhoof kan toelaat dat die damp op 'n plek wat nader as 1 m van die toppunt van die dak af geleë is, na die buitelug gevoer kan word indien die damp, syne insiens, waarskynlik nie aan die brand sal slaan nie. In geval die uitlaatopeninge buite die spuitlokaal is en verbind is met enige ander interne gedeelte van die gebou, moet sodanige openinge beskerm word deur steenwerk van 100 mm dik of 50 mm asbessementplate. Daar mag geen reghoekige buulings in die uitlaatopeninge voorkom nie.

(i) The ventilation inlets shall be of 215 X 140 mm terra-cotta air bricks and honeycombed into the wall opposite the exhaust ventilation system at 215 mm centres, from floor level to a height of not less than 2,5 m. Such inlets shall be substantially equivalent to the exhaust capacity provided in terms of these by-laws.

(j) The blades of any fan used in the spray room shall be of non-ferrous metal.

(2) No electrical equipment shall be installed in the spray room other than —

- (a) electric lights enclosed in outer flame-proof fittings;
- (b) electric wires protected throughout by seamless metal tubes, the junctions of which are screwed together or cables of the armoured type approved by the Chief Fire Officer; and
- (c) electrical apparatus of flame-proof construction used for ventilating purposes.

(3)(a) The spray rooms, fans and vents shall be kept clean and free from flammable deposits and all fans and vents shall be kept in proper working order at all times; any scraping necessary to comply with the provisions of this subsection being carried out with non-ferrous instruments.

(b) All drums, cans or similar vessels containing flammable liquids or substances or which have contained the same and have not been degassed or otherwise rendered harmless, shall be kept securely closed when not in use and shall, after the contents have been used, be removed from the spray room and stored in such a place that, in the opinion of the Chief Fire Officer, they are not likely to cause danger or obstructions or obstruct or impede the escape to safety of persons or animals in the event of fire.

(4) The Chief Fire Officer may in his discretion permit any reasonable deviation from the provisions of this section which he is satisfied will not create or increase the danger of fire or the danger to persons, animals or other property arising in the event of fire.

Danger Notices at Entrance.

104. The words "DANGER — NO SMOKING" in both official languages shall be prominently displayed in letters not less than 150 mm high outside the entrance to every spray room, and shall at all times be maintained in such position and in a clearly legible condition.

When Permit is not Required.

105. Nothing contained in sections 101 to 104 inclusive shall prohibit the spraying with flammable liquid of any vehicle or article in the open air if such spraying is not within a distance of 15 m from any fire, flamme, open light or other agency likely to ignite such flammable liquid or its vapour and, in the opinion of the Chief Fire Officer, such spraying is not likely in the event of fire to impede the escape of persons or animals, or to endanger any room or building.

(i) Die inlaatventilasie-opening moet van 215 x 140 mm terra-cotta lugstene wees wat in 'n heuningkoek-muur teenoor die uitlaatventilasiestelsel op middelpunte van 215 mm vanaf die vloervlak tot 'n hoogte van minstens 2,5 m, aangebring is. Sodanige ventilasie-opening moet wesentlik gelyk wees aan die uitlaatkapasiteit waarvoor daar ingevolge hierdie verordening voorsiening gemaak word.

(j) Die lemme van enige waaiers wat in die sputitlokaal gebruik word, moet van nie-ysterhoudende metaal wees.

(2) Geen elektriese toerusting mag in die sputitlokaal aangebring word nie, behalwe —

- (a) elektriese gloeilampe wat 'n vlamdigte omhulsel buite-on het;
- (b) elektriese draadleidings wat heeltemal deur naatlose metaalbuise, waarvan die lasse vasgeskroef word, beskerm is, of kabels van die gepantserde tipe deur die Brandweerhoof goedgekeur; en
- (c) elektriese apparaat wat vlamdig vervaardig is en vir ventilasiedoeleindes gebruik word.

(3)(a) Die sputitlokale, waaiers en uitlaatopeninge moet skoon en vry van vlambare aanpaksels gehou word, en alle waaiers en openinge moet te alle tye in 'n behoorlike werkende toestand wees, en indien dit skoon geskraap moet word ten einde aan die bepaling van hierdie artikel te voldoen, moet dit met nie-ysterhoudende instrumente geskied.

(b) Alle dromme, blikke of dergelike houers wat vlambare vloeistowwe of bestanddele bevat, of dit bevat het, en nog nie ontgas of op 'n ander manier onskadelik gemaag is nie, moet deeglik toegehou word wanneer dit nie gebruik word nie, en moet, nadat die inhoud gebruik is, uit die sputitlokaal verwyder en op sodanige plek gehou word waar dit, na die mening van die Brandweerhoof, waarskynlik nie gevaaar sal inhou of 'n versperring sal veroorsaak of mense of diere in gevle van 'n brand sal verhinder of belemmer om na veiligheid te ontsnap nie.

(4) Die Brandweerhoof kan na goeddunke redelike afwykings van die bepaling van hierdie artikel toelaat indien hy daarvan oortuig is dat dit nie 'n brandgevaar sal skep, of die gevaaar van brand verhoog of mense, diere of ander eiendom in geval van 'n brand, in gevaaar sal stel nie.

Gevaarkennisgewings by Ingang.

104. Die woord "GEVAAR — MOENIE ROOK NIE" moet opvallend in albei amptelike tale in letters wat minstens 150 mm hoog is, aan die buitekant van die ingang tot elke sputitlokaal aangebring word en moet te alle tye op dié plek in 'n duidelik leesbare toestand in stand gehou word.

Wanneer 'n Permit nie Vereis word nie.

105. Geen bepaling in artikels 101 tot en met 104 vervat, verbied die bespuiting van enige voertuig of artikel in die buitelug met vlambare vloeistof nie indien sodanige bespuiting minstens 15 m van enige vuur, vlam, oop lig of ander middel wat sodanige vlambare vloeistof of die dampie daarvan aan die brand kan laat slaan, plaas vind, en indien die Brandweerhoof van mening is dat sodanige bespuiting in geval van 'n brand nie moontlik mense of diere sal verhinder om te ontkom, of enige vertrek of gebou in gevaaar sal stel nie.

MIXING ROOMS.

106. The provisions of sections 81, 88, 90, 95 and 98 shall apply *mutatis mutandis* to mixing rooms.

Provisions where Class A Flammable Liquids are Used or Handled.

107. The provisions of section 96(a) to (f) inclusive, (h) and (i) shall apply *mutatis mutandis* to Class A flammable liquids.

Provisions where Class B Flammable Liquids are Used or Handled.

108. The provisions of section 99 shall apply *mutatis mutandis* to Class B flammable liquids.

LIQUEFIED PETROLEUM GASES.

109.(1) No person shall cause or permit —

- (a) the filling of any receptacle or vehicle with liquefied petroleum gas on any premises;
- (b) the use, handling or storage of liquefied petroleum gas on any premises; or
- (c) the use of any vehicle for the conveyance of liquefied petroleum gas in or at any public place,

unless the requirements of the Code of Practice for the Handling, Storage and Distribution of Liquefied Petroleum Gas in Domestic, Commercial and Industrial Installations of the South African Bureau of Standards have been complied with and written permission has been obtained from the Chief Fire Officer who may also require compliance with additional safety precautions he may deem necessary, having regard to the particular circumstances of the case.

(2) The Chief Fire Officer may, in his discretion, permit any reasonable deviation from the provisions of subsection (1).

CARBIDE.

Certificate of Registration in Respect of Storage.

110.(1) No person shall keep or store carbide in excess of 900 kg on any premises unless such person is in possession of a certificate of registration in respect of such premises.

(2) No certificate of registration shall be issued in respect of any premises for the storage of carbide until the provisions of these by-laws have been complied with in respect of such premises.

(3) Such certificate —

- (a) shall state the maximum amount of carbide permitted to be stored on the premises;
- (b) may be issued subject to such conditions as are deemed necessary by the Council, having regard to the circumstances pertaining to each application.

(4) Every such certificate shall be valid only until the next succeeding 31st day of December.

(5) No certificate of registration, other than a renewal thereof, shall be issued in respect of any premises until the provisions of section 111 have been complied with and the application therefor has been approved by the Council.

MENGLOKALE.

106. Die bepalings van artikels 81, 88, 90, 95 en 98 is *mutatis mutandis* van toepassing op menglokale.

Bepalings waar Klas A Vlambare Vloeistowwe Gebruik of Hanteer word.

107. Die bepalings van artikel 96(a) tot en met (f), (h) en (i) is *mutatis mutandis* van toepassing op Klas A vlambare vloeistowwe.

Bepalings waar Klas B Vlambare Vloeistowwe Gebruik of Hanteer word.

108. Die bepalings van artikel 99 is *mutatis mutandis* van toepassing op Klas B vlambare vleistowwe.

VLOEIBARE PETROLEUMGASSE.

109.(1) Niemand mag toelaat of veroorsaak —

- (a) dat enige houer of voertuig met vloeibare petroleumgas op enige perseel gevul word nie;
- (b) dat vloeibare petroleumgas op enige perseel gebruik, gehanteer of opgeberg word nie; of
- (c) dat enige voertuig vir die vervoer van vloeibare petroleumgas op of in enige openbare plek gebruik word nie,

tensy die vereistes van die Gebruikskode vir die Hantering, Bewaring en Distribusie van Vloeibare Petroleumgas in Huishoudelike, Kommerciële en Nywerheidsinstallasies van die Suid-Afrikaanse Buro vir Standaarde nagekom en skriftelike toestemming verkry is van die Brandweerhoof wat kan vereis dat bykomende veiligheidsmaatreëls wat hy, met inagneming van die besondere geval nodig mag ag, nagekom word.

(2) Die Brandweerhoof kan, na goeddunke, enige redelike afwyking van die bepalings van subartikel (1) toelaat.

KARBIED.

Registrasiesertifikaat ten Opsigte van Opberging.

110.(1) Niemand mag meer as 900 kg karbied op enige perseel hou of opberg nie, tensy so 'n persoon in besit is van 'n registrasiesertifikaat ten opsigte van sodanige perseel.

(2) Geen registrasiesertifikaat vir die opberging van karbied op 'n perseel word uitgereik alvorens daar aan die bepalings van hierdie verordeninge ten opsigte van sodanige perseel voldoen is nie.

(3) Sodanige sertifikaat —

- (a) moet die grootste hoeveelheid karbied wat op die perseel opberg word, aangee;
- (b) kan uitgereik word, onderworpe aan sodanige voorwaardes as wat die Raad, met inagneming van die omstandighede verbonde aan elke aansoek, noodsaaklik ag.

(4) Elke sodanige sertifikaat is slegs tot op die eersvolgende 31ste dag van Desember geldig.

(5) Geen registrasiesertifikaat, uitgesonderd 'n hernwing daarvan, word ten opsigte van 'n perseel uitgereik alvorens aan die bepalings van artikel 111 voldoen, en die aansoek daarom deur die Raad goedgekeur is nie.

Application for a Certificate of Registration.

111.(1) Every application for a certificate of registration, accompanied by the charges prescribed in Schedule 1 hereto, shall be made in writing to the Council on a form to be provided by the Council for the purpose.

(2) Every such application shall be accompanied by a plan of the premises in respect of which the certificate is required, drawn to a scale of not less than 1:100 and showing the elevation of the premises in relation to adjacent buildings above or below the ground.

(3) Every such application shall also be accompanied by a block plan drawn to a scale of not less than 1:500 which shall specify —

- (a) the premises and all open spaces with stand numbers thereof and the materials of which such premises are constructed or to be constructed;
- (b) the stands with numbers thereof immediately adjoining;
- (c) the names of any streets on which the site abuts and the township in which it is situated; and
- (d) the north point.

(4) Where the plan relates to existing premises in respect of which a certificate of registration has been issued in terms of section 110 and to which it is proposed to make alterations or additions, only a ground plan together with such application form and the prescribed charges shall be submitted. Such ground plan shall be drawn to a scale of not less than 1:100 and shall show such additions or alterations in relation to such existing premises.

(5) All plans shall be —

- (a) signed by the owner of the premises or his agent;
- (b) drawn in Indian ink on tracing linen or clear prints on cloth with white ground; and
- (c) coloured with fixed colours as follows:

*Block Plan:**Proposed premises or alterations:*

Red.

Other existing buildings:

Grey or a neutral colour.

Open spaces:

Uncoloured.

(6) A charge of R3 for every application for approval of a plan or plans shall be paid on submission thereof, and on approval, such plan or plans shall become the property of the Council. On approval of such plan a written notice shall be issued with such conditions thereon as are deemed necessary by the Council.

(7) The approval of plans of premises shall in no way imply the acceptance of any responsibility on the part of the Council in regard to such premises.

(8) The approval by the Council under these by-laws of any plans shall lapse and shall be null and void if the

Aansoek om 'n Registrasiesertifikaat.

111.(1) Elke aansoek om 'n registrasiesertifikaat moet vergesel gaan van die gelde voorgeskryf in Bylae 1 hierby en moet skriftelik by die Raad gedoen word op 'n vorm wat vir dié doel deur die Raad verskaf word.

(2) Elke sodanige aansoek moet vergesel gaan van 'n plan van die perseel ten opsigte waarvan 'n sertifikaat vereis word, wat volgens 'n skaal van minstens 1:100 geteken is, en wat die opstand met betrekking tot die aangrensende geboue, bokant of onderkant die grond, aandui.

(3) Elke sodanige aansoek moet ook vergesel gaan van 'n blokplan wat volgens 'n skaal van minstens 1:500 geteken is, en waarop die volgende besonderhede aangedui word:

- (a) Die perseel en alle oopruimtes en die standplaasnommers daarvan, en die materiaal waarvan sodanige perseel gebou is of gebou staan te word;
- (b) die aangrensende persele en hulle standplaasnommers;
- (c) die naam van strate waaraan die terrein grens en die naam van die dorp waarin dit geleë is; en
- (d) die noordpunt.

(4) Waar die plan betrekking het op 'n bestaande perseel ten opsigte waarvan 'n registrasiesertifikaat ingevolge artikel 110 uitgereik is en ten opsigte waarvan dit die voorname is om veranderings of aanbouings aan te bring, moet slegs 'n grondplan tesame met sodanige aansoekvorm en die voorgeskrewe geldie ingedien word. Sodanige grondplan moet volgens 'n skaal van minstens 1:100 geteken wees en moet sodanige aanbouings of veranderings met betrekking tot die bestaande perseel aandui.

(5) Alle planne moet —

- (a) deur die eienaar van die perseel of sy agent onderteken word;
- (b) met Indiese ink op natreklinne geteken of duidelik op 'n wit doek afgedruk wees; en
- (c) soos volg met vaste kleure ingekleur wees:

*Blokplan:**Voorgestelde persele of veranderings:*

Rooi.

Ander bestaande gebou:

Grys of 'n neutrale kleur.

Ope ruimtes:

Ongekleurd.

(6) Daar moet 'n geld van R3 ten opsigte van elke aansoek om goedkeuring van 'n plan of planne betaal word wanneer dit ingedien word, en nadat die goedgekeur is, word sodanige plan of planne die eiendom van die Raad. Wanneer so 'n plan goedgekeur is, word 'n skriftelike kennisgewing uitgereik wat sodanige voorwaardes bevat as wat die Raad nodig ag.

(7) Die goedkeuring van planne ten opsigte van 'n perseel beteken geensins dat die Raad enige aanspreeklikheid met betrekking tot sodanige perseel aanvaar nie.

(8) Die goedkeuring deur die Raad van enige plan ingevolge hierdie verordeninge, verval en is van nul en gener waarde indien daar nie binne een jaar na die datum

provisions of these by-laws shall not have been complied with within one year after the date of such approval.

Conditions of Certificate of Registration.

112.(1) No person shall store or cause or permit to be stored any quantity of carbide on any premises in excess of the amount stated on the certificate of registration relating to such premises.

(2) Any person in lawful possession of any certificate of registration may make written application to the Council for permission to increase the total quantity of carbide which may be stored in terms of such certificate. Such application shall be granted by the Council only if the proposed increase is permissible in terms of these by-laws. When the Council has granted any such application, such person shall surrender his certificate of registration to the Council for amendment.

Renewal of Certificate of Registration.

113. Application for the annual renewal of a certificate of registration shall be made not later than the 15th day of November of the year prior to that for which such renewal is required, on a form to be provided by the Council, and shall be accompanied by the charges prescribed in Schedule 1 hereto. No plans of the premises in terms of section 111 shall be required in the case of a renewal of a certificate of registration, unless called for at the discretion of the Council.

Transfer of Certificate of Registration.

114.(1) A certificate of registration may be transferred from one person to another.

(2) The person desiring such transfer shall make application in writing to the Council on a form to be provided by the Council for such purpose. Such application shall be accompanied by the prescribed charges, together with the certificate of registration relating to the premises in respect of which such transfer is desired.

(3) No certificate of registration shall be transferable from one premises to another.

Additions and Alterations to Registered Premises.

115. No additions or alterations to any existing registered premises shall be made unless and until a plan prepared in accordance with the provisions of section 111(4) shall have been submitted to and approved by the Council in writing.

Fire Appliances.

116. The person to whom a certificate of registration has been issued shall install or cause to be installed in the premises to which such certificate refers, in an easily accessible and visible position on a wall or other suitable position not less than 1 m above the level of the floor of the premises, 6 fire buckets filled with dry sand, of a capacity of 9 l each, painted red with the word "FIRE" painted in white and legibly maintained thereon.

Rules to be Observed.

117. No person shall store or cause or permit to be stored any carbide on any premises whether registered or unregistered, unless such carbide is stored —

van sodanige goedkeuring, aan die bepalings van hierdie verordeninge voldoen is nie.

Voorwaardes van die Registrasiesertifikaat.

112.(1) Niemand mag meer karbied as die hoeveelheid wat op die registrasiesertifikaat wat op sodanige perseel betrekking het, aangedui word, op 'n perseel opberg, laat opberg, of toelaat dat die daar opgeberg word nie.

(2) Enigiemand wat in wettige besit van enige registrasiesertifikaat is, kan by die Raad skriftelik aansoek doen om toestemming om die totale hoeveelheid karbied wat ingevolge so 'n sertifikaat opgeberg mag word, te vermeerder. Die Raad staan sodanige aansoek slegs toe indien die voorgestelde vermeerdering kragtens hierdie verordeninge toelaatbaar is. Indien die Raad so 'n aansoek toegestaan het, moet sodanige persoon die registrasiesertifikaat by die Raad indien sodat dit gewysig kan word.

Hernuwing van die Registrasiesertifikaat.

113. Daar moet uiterlik op die 15de dag van November van die jaar wat die jaar voorafgaan ten opsigte waarvan hernuwing benodig word, aansoek om die hernuwing deur die Raad verskaf word, en die geldie soos by Bylae I hierby voorgeskryf, moet die aansoek vergesel. Geen planne van die perseel word ingevolge artikel 111 in die geval van 'n hernuwing van 'n registrasiesertifikaat vereis nie, tensy die Raad dit na goeddunke verlang.

Oordrag van 'n Registrasiesertifikaat.

114.(1) 'n Registrasiesertifikaat kan deur een persoon aan 'n ander oorgedra word.

(2) Die persoon wat sodanige oordrag verlang, moet skriftelik by die Raad aansoek daarom doen op 'n vorm wat die Raad vir dié doel verskaf. So 'n aansoek moet vergesel gaan van die voorgeskrewe geldie, asook van die registrasiesertifikaat wat betrekking het op die perseel ten opsigte waarvan sodanige oordrag verlang word.

(3) Geen registrasiesertifikaat is van een perseel op 'n ander perseel oordraagbaar nie.

Aanbouings en Veranderings aan 'n Geregistreerde Perseel.

115. Geen aanbouing of verandering mag aan enige bestaande geregistreerde perseel aangebring word, tensy en alvorens 'n plan wat ooreenkomsdig die bepalings van artikel 111(4) opgestel is, by die Raad ingedien en skriftelik goedgekeur is nie.

Brandblustoestelle.

116. Die persoon aan wie 'n registrasiesertifikaat uitgereik is, moet in die perseel waarop sodanige sertifikaat betrekking het, 6 rooi geverfde brandemmers met 'n inhoudsvermoë van 9 l elk wat vol droë sand is, en waarop die woord "BRAND" in wit geverf is en leesbaar in stand gehou moet word, op 'n maklik toeganklike en sigbare plek aan die muur of op 'n ander geskikte plek wat minstens 1 m bokant die vloeroppervlak van die perseel is, aanbring of laat aanbring.

Reëls wat Nagekom moet word.

117. Niemand mag karbied op 'n geregistreerde of ongeregistreerde perseel opberg, laat opberg of toelaat dat dit opgeberg word nie, tensy sodanige karbied geberg word —

- (a) in such a position that it is not in dangerous proximity to any fire, flame, open light or other agency likely to ignite flammable or explosive gas;
- (b) in a dry and well ventilated position;
- (c) in such a position that in the case of fire or explosion, the escape of persons or animals from such premises will not be prevented or impeded;
- (d) in closed metal containers.

Inspection of Premises.

118.(1) Any authorized officer of the Council may, for any purpose connected with these by-laws, at all reasonable times and without previous notice enter upon any premises whatsoever and make such enquiries or examination thereon as he may deem necessary.

(2) The owner or occupier or, failing their presence on the premises, any other person employed thereon shall upon demand disclose to such authorized officer the presence of any carbide in or upon such premises, and shall answer all enquiries relating either to the observance of these by-laws or to any condition in connection with the certificate of registration.

Construction of Store.

119. Every store, room or building used for the storage of carbide in excess of 200 kg shall —

- (a) be substantially constructed of non-combustible material;
- (b) be of such construction and condition that all the contents thereof shall be maintained in a dry condition;
- (c) be adequately ventilated to prevent the accumulation therein of flammable or explosive gas;
- (d) be so situated that any gases which may be discharged therefrom are not likely to come into contact with any fire, flame, open light or other agency likely to ignite flammable or explosive gas;
- (e) have no opening into or communication with any other room or building in which persons reside or which is used for public assembly or stabling of animals;
- (f) be so constructed and situated that there is no possibility of danger from any fire, flame, open light or other agency likely to ignite flammable or explosive gas;
- (g) be situated at ground level: Provided that any such store, room or building used for the storage of carbide in excess of 200 kg, unless situated at a distance of not less than 30 m from any other building, shall be constructed of brick or concrete and with a roof constructed of non-combustible material and shall have no opening into or communication with any other room or building.

Danger Notice on Store.

120. No person shall use or cause or permit to be used any store, room or building for the storage of carbide in excess of 900 kg unless and until the words "DANGER — CARBIDE" in letters not less than 75 mm in height are legibly painted in both official languages on the outer face of the door of such store, room

- (a) op 'n plek wat nie gevaaerlik naby aan enige vuur, vlam, oop lig of ander middel is wat moontlik vlambare of ontplofbare gas aan die brand kan laat slaan nie;
- (b) op 'n droë en behoorlik-geventileerde plek;
- (c) op so 'n plek dat in die geval van brand of 'n ontploffing die ontkoming van persone of diere van sodanige perseel af, nie verhinder of belemmer word nie;
- (d) in metaalhouers wat toe is.

Ondersoek van Persele.

118.(1) Enige gemagtigde beampete van die Raad kan, vir enige doel in verband met die toepassing van hierdie verordeninge, te alle redelike tye en sonder om vooraf kennis te gee, enige perseel betree en sodanige navrae daar doen of ondersoek instel as wat hy nodig mag ag.

(2) Die eienaar of okkupant, of indien hulle nie op die perseel teenwoordig is nie, enige ander persoon wat daar in diens is, moet sodanige gemagtigde beampete op sy versoek verwittig van enige karbied wat in of op sodanige perseel is, en moet alle navrae met betrekking tot die nakoming van die bepalings van hierdie verordeninge, of met betrekking tot enige voorwaardes in verband met die registrasiesertifikaat, beantwoord.

Bou van Opbergingslokaal.

119. Elke pakkamer, vertrek of gebou wat gebruik word om meer as 200 kg karbied in op te berg moet —

- (a) stewig en van nie-brandbare materiaal gebou wees;
- (b) sodanig gebou en in so 'n toestand wees dat die hele inhoud daarvan droog bly;
- (c) behoorlik geventileer wees sodat vlambare of ontplofbare gas nie daarin vergaar nie;
- (d) sodanig geleë wees dat gas wat daaruit ontsnap nie moontlik in aanraking kan kom met enige vuur, vlam, oop lig of ander middel wat moontlik vlambare of ontplofbare gas aan die brand kan laat slaan nie;
- (e) nie 'n opening hê na, of verbind wees met, 'n ander vertrek of gebou waarin mense woon of wat vir openbare byeenkomste of die huisvesting van diere gebruik word nie;
- (f) sodanig gebou, en geleë wees, dat daar geen moontlikheid van gevaaer van enige vuur, vlam, oop lig of ander middel wat moontlik vlambare of ontplofbare gasse aan die brand kan laat raak, bestaan nie;
- (g) op die grondvlak geleë wees: Met dien verstande dat enige sodanige pakkamer, vertrek of gebou wat gebruik word om meer as 200 kg karbied op te berg, tensy dit minstens 30 m van enige ander gebou af staan, van baksteen of beton en met 'n dak van vuurvaste materiaal gebou moet wees, en mag geen opening na 'n ander vertrek of gebou hê of daarmee verbind wees nie.

Gevaarkennisgewing aan Opbergingslokaal.

120. Niemand mag 'n pakkamer, vertrek of gebou gebruik, laat gebruik of toelaat dat dit gebruik word met die doel om meer as 900 kg karbied daarin op te berg nie, tensy en alvorens die woorde "GEVAAR — KARBIED" leesbaar in albei amptelike tale, in letters wat minstens 75 mm hoog is, op die buitekant van die deur van sodanige pakkamer, vertrek of gebou geverf is. Sodanige

or building. Such notice shall at all times be maintained in such position in a legible condition.

Purity.

121. No person shall store, use, sell or expose for sale any carbide which is not commercially pure: Provided that no carbide containing any impurity liable to generate phosphoretted or silicuretted hydrogen in such quantities as to render the gas generated likely to ignite spontaneously, shall be considered to be commercially pure for the purpose of this section.

Seizure and Removal of Carbide.

122. Where any authorized officer of the Council has reasonable cause to believe that any storage of carbide is contrary to the provisions of these by-laws, he may seize and detain such carbide and may either require the owner or occupier or, failing their presence on the premises, any other person employed thereon to detain the carbide in those premises or in any other premises under his control, or he may remove it in such manner and to such premises as will, in his opinion, least endanger the public safety, and there detain it or take such other measures as may be necessary for the protection of the public.

Breach of Conditions.

123. Any person who commits any breach of any condition endorsed on the approval notice of certificate of registration issued in terms of these by-laws, shall be guilty of an offence in terms of these by-laws.

PENALTIES.

124. Any person contravening any provision of these by-laws shall be guilty of an offence and liable, on conviction —

- (a) to a fine not exceeding R100 or, in default of payment, imprisonment for a period not exceeding 6 months; and
- (b) in the case of a successive or continuing offence, to a fine not exceeding R10 for every day such offence continues.

SCHEDULE 1.

TARIFF OF CHARGES PAYABLE IN RESPECT OF CERTIFICATES OF REGISTRATION, SPRAY PERMITS, RENEWALS AND TRANSFERS.

	<i>Yearly R</i>
1. Bulk Depot	50,00
2. Dry-cleaning Room	10,00
3. Mixing Room	10,00
4. Spray Room	4,00
5. Carbide Store	10,00
6. Premises other than those mentioned above:	
(1) Up to and including 2,3 kl storage capacity	4,00

kennisgewing moet te alle tye op dié plek in 'n leesbare toestand in stand gehou word.

Suiwerheid.

121. Niemand mag karbied wat nie vir handelsgebruik suiwer is nie, opberg, gebruik, verkoop of te koop aanbied nie: Met dien verstande dat geen karbied wat onsuiwerhede bevat wat moontlik soveel fosfor- of silikonwaterstof kan afskei dat die gasse wat vrygestel word, moontlik vanself aan die brand kan slaan, vir die toepassing van hierdie artikel as suiwer handelskarbied beskou word nie.

Beslaglegging op en Verwydering van Karbied.

122. Indien 'n gemagtigde beampte van die Raad op billike gronde vermoed dat karbied,strydig met die bepalings van hierdie verordeninge opgeberg word, kan hy beslag lê op sodanige karbied en dit hou en hy kan die eienaar of okkupant of, indien hulle nie op die perseel teenwoordig is nie, enige ander persoon wat daar in diens is, aansê om die karbied in die perseel of in enige ander perseel onder sy beheer, te hou, of hy kan dit op so 'n wyse en na sodanige perseel toe verwyder as wat, na sy mening, die veiligste vir die publiek is en dit daar hou, of hy kan enige ander reëlings tref wat hy ter beveiliging van die publiek noodsaaklik ag.

Verbreking van die Voorwaardes.

123. Enigiemand wat 'n voorwaarde wat op die goedkeuringskennisgewing of die registrasiesertifikaat wat kragtens hierdie verordeninge uitgereik is, geëndosseer is, verbreek, is skuldig aan 'n misdryf ingevolge hierdie verordeninge.

STRAFBEPALING.

124. Enigiemand wat enige bepaling van hierdie verordeninge oortree is skuldig aan 'n misdryf en by skuldig bevinding strafbaar met —

- (a) 'n boete van hoogstens R100 of by wanbetaling, gevangenisstraf vir 'n tydperk van hoogstens 6 maande; en
- (b) in die geval van agtereenvolgende of voortdurende oortredings, 'n boete van hoogstens R10 vir elke dag wat die misdryf voortduur.

BYLAE 1.

TARIEF VAN GELDE BETAALBAAR TEN OPSIGTE VAN REGISTRASIESERTIFIKATE, SPUITLOKAALPERMITTE, HERNUWINGS EN OORDRAGTE.

	<i>Jaarliks R</i>
1. Grootmaatdepot	50,00
2. Droogskoonmaaklokaal	10,00
3. Menglokaal	10,00
4. Spuitlokaal	4,00
5. Karbiedopbergingslokaal	10,00
6. Persele wat nie hierbo vermeld word nie:	
(1) Tot en met 'n opbergingsvermoë van 2,3 kl	4,00

	Yearly R
(2) Up to and including 4,5 kl storage capacity	6,00
(3) Up to and including 23 kl storage capacity	8,00
(4) Up to and including 45 kl storage capacity	10,00
(5) Above 45 kl storage capacity	20,00

7. Transfer of certificate of registration or spray permit: R1.

8.(1) For the issue of every certificate of registration or spray permit, the yearly charges shall be as prescribed in this Schedule: Provided that if liability to pay the charges arises on or after 1 July in any year, the charges payable shall be half the yearly charges.

(2) For the annual renewal of a certificate of registration or spray permit, the charges shall be as prescribed in this Schedule.

SCHEDULE 2.

TARIFF OF CHARGES IN RESPECT OF EXAMINATION OF VEHICLES FOR TRANSPORT PERMIT.

Description of Vehicle.

	Half yearly R
1. Road tank wagon	4,00
2. Motor vehicle, other than a road tank wagon, designed to be used for the conveyance of flammable liquids in excess of the amount permitted in terms of section 80(1)(a) and (b)	2,00
3. Any vehicle, other than a motor vehicle or road tank wagon, designed to be used for the conveyance of flammable liquids in excess of the amount permitted in terms of section 80(1)(a) and (b)	1,00

PB. 2-4-2-49-10

Administrator's Notice 251 4 March, 1981

CORRECTION NOTICE.

GERMISTON MUNICIPALITY: ELECTRICITY SUPPLY BY-LAWS.

Administrator's Notice 85, dated 28 January, 1981, is hereby corrected by the substitution in item 6A(3)(a) under paragraph 2 for the formula

$$\left(1 + \frac{T}{100}\right) \times \left(1 + \frac{0,45V}{100}\right) - 1 \times 100\%$$

of the formula

$$\left[\left(1 + \frac{T}{100}\right) \times \left(1 + \frac{0,45V}{100}\right) - 1\right] \times 100\%.$$

PB. 2-4-2-36-1

	Jaarliks R
(2) Tot en met 'n opbergingsvermoë van 4,5 kl	6,00
(3) Tot en met 'n opbergingsvermoë van 23 kl	8,00

(4) Tot en met 'n opbergingsvermoë van 45 kl	10,00
(5) Meer as 45 kl opbergingsvermoë	20,00

7. Oordrag van registrasiesertifikaat of sputlokaalpermit: R1.	
--	--

8.(1) Vir die uitreiking van elke registrasiesertifikaat of sputlokaalpermit, is die jaarlikse gelde soos voorgeskryf in hierdie Bylae: Met dien verstande dat indien aanspreeklikheid vir betaling van die gelde op of na 1 Julie van enige jaar ontstaan, die gelde betaalbaar slegs die helfte van die jaarlikse gelde is.

(2) Vir die jaarlikse hernuwing van 'n registrasiesertifikaat of sputlokaalpermit, is die gelde soos in hierdie Bylae uiteengesit.

BYLAE 2.

TARIEF VAN GELDE TEN OPSIGTE VAN DIE ONDERSOEK VAN VOERTUIJE VIR 'N VERVOER-PERMIT.

Beskrywing van Voertuig.

	Half-jaarliks. R
1. Tenkvrugmotor	4,00
2. Motorvoertuig, uitgesonderd 'n tenkvrugmotor, wat ontwerp is vir die vervoer van vlambare vloeistowwe in groter hoeveelhede as wat toelaatbaar is ingevolge artikel 80(1)(a) en (b)	2,00
3. Enige voertuig, uitgesonderd 'n motorvoertuig of tenkvrugmotor, wat ontwerp is vir die vervoer van vlambare vloeistowwe in groter hoeveelhede as wat toelaatbaar is ingevolge artikel 80(1)(a) en (b)	1,00

PB. 2-4-2-49-10

Administratorskennisgewing 251 4 Maart 1981

KENNISGEWING VAN VERBETERING.

MUNISIPALITEIT GERMISTON: ELEKTRISITEITSVOORSIENINGSVERORDENINGE.

Administratorskennisgewing 85 van 28 Januarie 1981, word hierby verbeter deur in item 6A(3)(a) onder paraaf 2 die formule

$$\left(1 + \frac{T}{100}\right) \times \left(1 + \frac{0,45V}{100}\right) - 1 \times 100\%$$

deur die formule

$$\left[\left(1 + \frac{T}{100}\right) \times \left(1 + \frac{0,45V}{100}\right) - 1\right] \times 100\%$$

te vervang.

PB. 2-4-2-36-1

Administrator's Notice 252 4 March, 1981
 CORRECTION NOTICE.

POTCHEFSTROOM MUNICIPALITY: ADOPTION OF STANDARD DRAINAGE BY-LAWS.

Administrator's Notice 91, dated 28 January, 1981, is hereby corrected by amending paragraph 6 by the substitution in paragraph (a) of the Table under Schedule B for the expression "3,85:" of the expression "4,80".

PB. 2-4-2-34-26

Administrator's Notice 253 4 March, 1981
 ERMELO MUNICIPALITY: ALTERATION OF BOUNDARIES.

The Administrator has in terms of section 9(7) of the Local Government Ordinance, 1939 (Ordinance 17 of 1939), altered the boundaries of the Municipality of Ermelo by the incorporation therein of the farm portions described in the Schedule hereto.

PB. 3-2-3-14

SCHEDULE.

List of Properties of area to be included.

The following portions of the farm Witbank 262-I.T.

Portion	Diagram S.G. A.	Area
Remainder of Portion 17	5109/05	7,3175 ha.
Portion 30 (a portion of Portion 2)	1948/26	17,2020 ha.
Remainder of Portion 55	4936/75	100,6752 ha.
Portion 79 (a portion of Portion 20)	4429/78	4,1042 ha.
Portion 80 (a portion of Portion 2)	4430/78	255,1602 ha.
Portion 81 (a portion of Portion 6)	4431/78	21,6451 ha.
Portion 82 (a portion of Portion 19)	4432/78	119,7577 ha.
Portion 83 (a portion of Portion 23)	4433/78	8,7245 ha.
Portion 84 (a portion of Portion 24)	4434/78	68,0325 ha.
Portion 85 (a portion of Portion 50)	4435/78	2294 m ²

Administrator's Notice 254 4 March, 1981

KLERKSDORP AMENDMENT SCHEME 28.

The Administrator hereby, in terms of the provisions of section 89(1) of the Town-planning and Townships

Administrateurskennisgewing 252 4 Maart 1981
 KENNISGEWING VAN VERBETERING.

MUNISIPALITEIT POTCHEFSTROOM: AANNAME VAN STANDAARD RIOLERINGSVERORDENINGE.

Administrateurskennisgewing 91 van 28 Januarie 1981 word hierby verbeter deur paragraaf 6 te wysig deur in die Engelse teks in paragraaf (a) van die Tabel onder Bylae B die uitdrukking "3,85:" deur die uitdrukking "4,80" te vervang.

PB. 2-4-2-34-26

Administrateurskennisgewing 253 4 Maart 1981
 MUNISIPALITEIT VAN ERMELO: VERANDERING VAN GRENSE.

Die Administrator het ingevolge die bepalings van artikel 9(7) van die Ordonnansie op Plaaslike Bestuur, 1939 (Ordonnansie 17 van 1939), die grense van die Munisipaliteit van Ermelo uitgebrei deur die inlywing daarby van die plaasgedeeltes soos omskryf in die bygaande Bylae.

PB. 3-2-3-14

BYLAE.

Lys van Eiendomme van gebied wat ingesluit moet word.

Die volgende gedeeltes van die plaas Witbank 262-I.T.

Gedeelte	Kaart L.G. A.	Grootte
Restant van Gedeelte 17	5109/05	7,3175 ha.
Gedeelte 30 ('n gedeelte van Gedeelte 2)	1948/26	17,2020 ha.
Restant van Gedeelte 55	4936/75	100,6752 ha.
Gedeelte 79 ('n gedeelte van Gedeelte 20)	4429/78	4,1042 ha.
Gedeelte 80 ('n gedeelte van Gedeelte 2)	4430/78	255,1602 ha.
Gedeelte 81 ('n gedeelte van Gedeelte 6)	4431/78	21,6451 ha.
Gedeelte 82 ('n gedeelte van Gedeelte 19)	4432/78	119,7577 ha.
Gedeelte 83 ('n gedeelte van Gedeelte 23)	4433/78	8,7245 ha.
Gedeelte 84 ('n gedeelte van Gedeelte 24)	4434/78	68,0325 ha.
Gedeelte 85 ('n gedeelte van Gedeelte 50)	4435/78	2294 m ²

Administrateurskennisgewing 254 4 Maart 1981

KLERKSDORP-WYSIGINGSKEMA 28.

Die Administrator verklaar hierby ingevolge die bepalings van artikel 89(1) van die Ordonnansie op Dorps-

Ordinance, 1965, declares that he has approved an amendment scheme, being an amendment of Klerksdorp Town-planning Scheme, 1980, comprising the same land as included in the township of Klerksdorp Extension 21.

Map 3 and the scheme clauses of the amendment scheme are filed with the Director of Local Government, Pretoria and the Town Clerk, Klerksdorp and are open for inspection at all reasonable times.

This amendment is known as Klerksdorp Amendment Scheme 28.

PB. 4-9-2-17H-28

Administrator's Notice 255

4 March, 1981

KLERKSDORP AMENDMENT SCHEME 32.

It is hereby notified in terms of section 36(1) of the Town-planning and Townships Ordinance, 1965, that the Administrator has approved the amendment of Klerksdorp Town-planning Scheme, 1980, by the rezoning of Erven 1936, 691, 692 and 693, Klerksdorp (New Town), from "Residential 4" with a density of "One dwelling per erf" to "Public Garage", subject to certain conditions.

Map 3 and the scheme clauses of the amendment scheme are filed with the Director of Local Government, Pretoria and the Town Clerk, Klerksdorp and are open for inspection at all reasonable times.

This amendment is known as Klerksdorp Amendment Scheme 32.

PB. 4-9-2-17H-32

Administrator's Notice 256

4 March, 1981

DECLARATION OF APPROVED TOWNSHIP.

In terms of section 69 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965), the Administrator hereby declares Klerksdorp Extension 21 Township to be an approved township, subject to the conditions set out in the Schedule hereto.

PB. 4-2-2-4856

SCHEDULE.

CONDITIONS UNDER WHICH THE APPLICATION MADE BY CHARLES AUGUSTA KEYSER UNDER THE PROVISIONS OF THE TOWN-PLANNING AND TOWNSHIPS ORDINANCE, 1965, FOR PERMISSION TO ESTABLISH A TOWNSHIP ON REMAINDER OF PORTION 349 OF THE FARM ELANDSHEUVEL 402-I.P., PROVINCE OF TRANS-VAAL, HAS BEEN GRANTED.

I. CONDITIONS OF ESTABLISHMENT.

(1) Name.

The name of the township shall be Klerksdorp Extension 21.

(2) Design.

The township shall consist of erven and a street as indicated on General Plan S.G. A.2605/79.

beplanning en Dorpe, 1965, dat hy 'n wysigingskema synde 'n wysiging van Klerksdorp-dorpsaanlegskema, 1980, wat uit dieselfde grond as die dorp Klerksdorp Uitbreiding 21 bestaan, goedgekeur het.

Kaart 3 en die skemaklousules van die wysigingskema word in bewaring gehou deur die Direkteur van Plaaslike Bestuur, Pretoria en die Stadsklerk, Klerksdorp en is beskikbaar vir inspeksie op alle redelike tye.

Hierdie wysiging staan bekend as Klerksdorp-wysigingskema 28.

PB. 4-9-2-17H-28

Administrator's Notice 255

4 Maart 1981

KLERKSDORP-WYSIGINGSKEMA 32.

Hierby word ooreenkomsdig die bepalings van artikel 36(1) van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965, bekend gemaak dat die Administrateur goedgekeur het dat Klerksdorp-dorpsbeplanningskema, 1980, gewysig word deur die hersonering van Erwe 1936, 691, 692 en 693, Klerksdorp (Nuwe Dorp), van "Residensiel 4" met 'n digtheid van "Een woonhuis per erf" tot "Openbare Garage", onderworpe aan sekere voorwaardes.

Kaart 3 en die skemaklousules van die wysigingskema word in bewaring gehou deur die Direkteur van Plaaslike Bestuur, Pretoria en die Stadsklerk, Klerksdorp en is beskikbaar vir inspeksie op alle redelike tye.

Hierdie wysiging staan bekend as Klerksdorp-wysigingskema 32.

PB. 4-9-2-17H-32

Administrator's Notice 256

4 Maart 1981

VERKLARING TOT GOEDGEKEURDE DORP.

Ingevolge artikel 69 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965), verklaar die Administrateur hierby die dorp Klerksdorp Uitbreiding 21 tot 'n goedgekeurde dorp, onderwoppe aan die voorwaardes uiteengesit in die bygaande Bylae.

PB. 4-2-2-4856

BYLAE.

VOORWAARDEN WAAROP DIE AANSOEK GEOPEN DEUR CHARLES AUGUSTA KEYSER, INGEVOLGE DIE BEPALINGS VAN DIE ORDONNANSIE OP DORPSBEPLANNING EN DORPE, 1965, OM TOESTEMMING OM 'N DORP TE STIG OP RESTANT VAN GEDEELTE 349 VAN DIE PLAAS ELANDSHEUVEL 402-I.P., PROVINSIE TRANS-VAAL, TOEGESTAAN IS.

I. STIGTINGSVOORWAARDEN.

(1) Naam.

Die naam van die dorp is Klerksdorp Uitbreiding 21.

(2) Ontwerp.

Die dorp bestaan uit erwe en 'n straat soos aangedui op Algemene Plan L.G. A.2605/79.

(3) Stormwater Drainage and Street Construction.

- (a) The township owner shall on request of the local authority submit to such authority for its approval a detailed scheme complete with plans, sections and specifications, prepared by a civil engineer approved by the local authority, for the collection and disposal of stormwater throughout the township by means of properly constructed works and for the construction, tarmacadamising, kerbing and channeling of the streets therein together with the provision of such retaining walls as may be considered necessary by the local authority. Furthermore, the scheme shall indicate the route and gradient by which each erf gains access to the street on which it abuts.
- (b) The township owner shall when required to do so by the local authority carry out the approved scheme at his own expense on behalf and to the satisfaction of the local authority under the supervision of a civil engineer approved by the local authority.
- (c) The township owner shall be responsible for the maintenance of the streets to the satisfaction of the local authority until the streets have been constructed as set out in subclause (b).
- (d) If the township owner fails to comply with the provisions of paragraphs (a) and (b) heretof, the local authority shall be entitled to do the work at the cost of the township owner.

(4) Endowment.**(a) Payable to the local authority:**

The township owner shall in terms of the provisions of section 63(1) of the Town-planning and Townships Ordinance, 1965, pay to the local authority as endowment sums of money equal to

- (i) 1% of the land value of erven in the township, which amount shall be used by the local authority for the acquisition of land for a depositing site.
- (ii) 1% of the land value of erven in the township, which amount shall be used by the local authority for the acquisition of land for a cemetery.
- (iii) 1,5% of the land value of erven in the township, which amount shall be used by the local authority for the acquisition and/or development of parks within its area of jurisdiction.

Such endowment shall be paid in accordance with the provisions of section 74 of the said Ordinance.

(b) Payable to the Transvaal Education Department:

The township owner shall, in terms of the provisions of section 63(1)(a) of the Town-planning and Townships Ordinance, 1965, pay a lump sum endowment for educational purposes to the Transvaal Education Department on the land value of special residential land in the township, the extent of which shall be determined by multiplying 48,08 m² by the number of special residential erven in the township.

The value of the land shall be determined in terms of the provisions of section 74(3) and such endowment shall be payable in terms of the provisions of section 73 of the said Ordinance.

(3) Stormwaterdreinering en Straatbou.

- (a) Die dorpseienaar moet op versoek van die plaaslike bestuur aan sodanige bestuur 'n gedetailleerde skema volledig met planne, deursnee en spesifikasies, opgestel deur 'n siviele ingenieur wat deur die plaaslike bestuur goedgekeur is, vir die opgaar en afvoer van stormwater deur die hele dorp deur middel van beoorlik aangelegde werke en vir die aanlê, teermacadamisering, beranding en kanalisering van die strate daarin tesame met die verskaffing van sodanige keermure, as wat die plaaslike bestuur nodig ag, vir goedkeuring voorlê. Verder moet die skema die roete en helling aandui deur middel waarvan elke erf toegang tot die aangrensende straat verkry.
- (b) Die dorpseienaar moet, wanneer dit vereis word deur die plaaslike bestuur, die goedgekeurde skema op eie koste namens en tot bevrediging van die plaaslike bestuur onder toesig van 'n siviele ingenieur deur die plaaslike bestuur goedgekeur, uitvoer.
- (c) Die dorpseienaar is verantwoordelik vir die instandhouding van die strate tot bevrediging van die plaaslike bestuur totdat die strate ooreenkomsdig subklousule (b) gebou is.
- (d) Indien die dorpseienaar versuim om aan die bepalings van paragrawe (a) en (b) hiervan te voldoen, is die plaaslike bestuur geregtig om die werk op koste van die dorpseienaar te doen.

(4) Begiftiging.**(a) Betaalbaar aan die plaaslike bestuur:**

Die dorpseienaar moet ingevolge die bepalings van artikel 63(1) van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965, as begiftiging aan die plaaslike bestuur bedrae geld betaal gelykstaande met

- (i) 1% van die grondwaarde van erwe in die dorp, welke bedrag deur die plaaslike bestuur aangewend moet word vir die verkryging van grond vir 'n stortingsterrein.
- (ii) 1% van die grondwaarde van erwe in die dorp, welke bedrag deur die plaaslike bestuur aangewend moet word vir die verkryging van grond vir 'n begraafplaas.
- (iii) 1,5% van die grondwaarde van erwe in die dorp, welke bedrag deur die plaaslike bestuur aangewend moet word vir die verkryging en/of ontwikkeling van parke binne sy regsgebied.

Sodanige begiftiging moet ooreenkomsdig die bepalings van artikel 74 van genoemde Ordonnansie betaal word.

(b) Betaalbaar aan die Transvaalse Onderwysdepartement:

Die dorpseienaar moet ingevolge die bepalings van artikel 63(1)(a) van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965, aan die Transvaalse Onderwysdepartement as begiftiging vir onderwysdoelendes 'n globale bedrag op die grondwaarde van spesiale woongrond in die dorp betaal, waarvan die grootte bepaal word deur 48,08 m² te vermengvuldig met die getal spesiale woonerwe in die dorp.

Die waarde van die grond word bepaal ingevolge die bepalings van artikel 74(3) en sodanige begiftiging is betaalbaar ingevolge die bepalings van artikel 73 van genoemde Ordonnansie.

(5) Disposal of Existing Conditions of Title.

All erven shall be made subject to existing conditions and servitudes, if any, including the reservation of rights to minerals, but excluding:

- (a) The following right which will not be passed on to the erven in the township:

"entitled to a right of way over Portion 8 and the Remaining Extent of said Portion "H", measuring respectively 5 morgen 460 square roods and 75 morgen 76.5 square roods, as transferred under Deeds of Transfer Nos. 4005/1919 and 6008/1908, Southwards to where the right of way running westwards begins and thence along the latter way to the road leading to Klerksdorp, as shown on the diagram of said right of way S.G. No. A.2351/1918 annexed to Deed of Transfer No. 2375/1979."

- (b) The following servitude which does not affect the township:

"Gedeelte 349 van die plaas Elandsheuvel No. 402 (waarvan die eiendom hiermee getransporteer 'n deel uitmaak) is onderhewig aan —

A servitude of Aqueduct or passage of water in favour of the Klerksdorp Irrigation Board as will more fully appear from the Notarial Deed No. 87/1919-S, registered on the 7th day of February, 1919, a copy of which is annexed to Deed of Transfer No. 6008/1906."

- (c) The following servitude which affects Erf 1951 and a street in the township only:

"Die eiendom hiermee getransporteer is onderhewig aan —

'A servitude of storm water drain six feet wide along the Southern Boundary, in favour of the Town Council of Klerksdorp, as will more fully appear from Notarial Deed No. 269/1949-S.'"

(6) Access.

No ingress from Provincial Road P32-1 to the township and no egress to Provincial Road P32-1 from the township shall be allowed.

2. CONDITIONS OF TITLE.

All erven shall be subject to the following conditions imposed by the Administrator in terms of Ordinance 25 of 1965.

(1) The erf is subject to a servitude 2 m wide, in favour of the local authority, for sewerage and other municipal purposes, along any two boundaries other than a street boundary as determined by the local authority.

(2) No building or other structure shall be erected within the aforesaid servitude area and no large-rooted trees shall be planted within the area of such servitude or within 2 m thereof.

(3) The local authority shall be entitled to deposit temporarily on the land adjoining the aforesaid servitude such material as may be excavated by it during the course of the construction, maintenance or removal of such sewerage mains and other works as it, in its discretion, may deem necessary and shall further be entitled to reasonable access to the said land for the aforesaid

(5) Beskikking oor Bestaande Titelvoorwaardes.

Alle erwe moet onderworpe gemaak word aan bestaande voorwaardes en serwitute, as daar is, met inbegrip van die voorbehou van die regte op minerale, maar uitgesonderd:

- (a) Die volgende reg wat nie aan die erwe in die dorp oorgedra sal word nie:

"entitled to a right of way over Portion 8 and the Remaining Extent of said Portion "H", measuring respectively 5 morgen 460 square roods and 75 morgen 76.5 square roods, as transferred under Deeds of Transfer Nos. 4005/1919 and 6008/1908, Southwards to where the right of way running westwards begins and thence along the latter way to the road leading to Klerksdorp, as shown on the diagram of said right of way S.G. No. A.2351/1918 annexed to Deed of Transfer No. 2375/1919."

- (b) Die volgende serwituit wat nie die dorp raak nie:

"Gedeelte 349 van die plaas Elandsheuvel No. 402 (waarvan die eiendom hiermee getransporteer 'n deel uitmaak) is onderhewig aan —

A servitude of Aqueduct or passage of water in favour of the Klerksdorp Irrigation Board as will more fully appear from the Notarial Deed No. 87/1919-S, registered on the 7th day of February, 1919, a copy of which is annexed to Deed of Transfer No. 6008/1906."

- (c) Die volgende serwituit was slegs Erf 1951 en 'n straat in die dorp raak:

"Die eiendom hiermee getransporteer is onderhewig aan —

'A servitude of storm water drain six feet wide along the Southern Boundary, in favour of the Town Council of Klerksdorp, as will more fully appear from Notarial Deed No. 269/1949-S.'"

(6) Toegang.

Geen ingang van Provinciale Pad P32-1 tot die dorp en geen uitgang tot Provinciale Pad P32-1 uit die dorp word toegelaat nie.

2. TITELVOORWAARDES.

Alle erwe is onderworpe aan die volgende voorwaardes, opgelê deur die Administrateur ingevolge Ordonnansie 25 van 1965.

(1) Die erf is onderworpe aan 'n serwituit, 2 m breed, vir riolerings- en ander munisipale doeleinades, ten gunste van die plaaslike bestuur, langs enige twee grense uitgesonderd 'n straatgrens, soos deur die plaaslike bestuur bepaal.

(2) Geen gebou of ander struktuur mag binne die voornoemde serwituitgebied opgerig word nie en geen grootwortelbome mag binne die gebied van sodanige serwituit of binne 'n afstand van 2 m daarvan geplant word nie.

(3) Die plaaslike bestuur is geregtig om enige materiaal wat deur hom uitgegrawe word tydens die aanleg, onderhoud of verwydering van sodanige rioolhoofpypeleidings en ander werke as wat hy na goedgunke noedsaakklik ag tydelik te plaas op die grond wat aan die voornoemde serwituit grens en voorts is die plaaslike bestuur geregtig tot redelike toegang tot genoemde grond

purpose, subject to any damage done during the process to the construction, maintenance or removal of such sewerage mains and other works being made good by the local authority.

Administrator's Notice 257

4 March, 1981

ALBERTON AMENDMENT SCHEME 2.

It is hereby notified in terms of section 36(1) of the Town-planning and Townships Ordinance, 1965, that the Administrator has approved the amendment of Alberton Town-planning Scheme, 1979, by the rezoning of Erven 370 up to and including 373, 428 and Portion B of Erf 325, Alberton, Erven 13, 14, 18 and 237 up to and including 239 Florentia, Erven 473 and 475 New Redruth, Portion 74 of the farm Elandsfontein 108-I.R. all to "Educational".

Map 3 and the scheme clauses of the amendment scheme are filed with the Director of Local Government, Pretoria and the Town Clerk, Alberton and are open for inspection at all reasonable times.

This amendment is known as Alberton Amendment Scheme 2.

PB. 4-9-2-4H-2

Administrator's Notice 258

4 March, 1981

ERMELO AMENDMENT SCHEME 1/62.

It is hereby notified in terms of section 36(1) of the Town-planning and Townships Ordinance, 1965, that the Administrator has approved the amendment of Ermelo Town-planning Scheme 1, 1954, by the rezoning of Erven 3865 and 3866, Ermelo Extension 13, from "Municipal" to "General Industrial" with a density of "One dwelling per Existing Erf", subject to certain conditions.

Map 3 and the scheme clauses of the amendment scheme are filed with the Director of Local Government, Pretoria and the Town Clerk, Ermelo and are open for inspection at all reasonable times.

This amendment is known as Ermelo Amendment Scheme 1/62.

PB. 4-9-2-14-62

Administrator's Notice 259

4 March, 1981

PRETORIA AMENDMENT SCHEME 638.

It is hereby notified in terms of section 36(1) of the Town-planning and Townships Ordinance, 1965, that the Administrator has approved the amendment of Pretoria Town-planning Scheme, 1974, by the rezoning of Erf 404, Silverton, from "Special Residential" with a density of "One dwelling per erf" to "Special Residential" with a density of "One dwelling per 1 000 m²".

Map 3 and the scheme clauses of the amendment scheme are filed with the Director of Local Government, Pretoria and the Town Clerk, Pretoria and are open for inspection at all reasonable times.

This amendment is known as Pretoria Amendment Scheme 638.

PB. 4-9-2-3H-638

vir die voornoemde doel; onderworpe daaraan dat die plaaslike bestuur enige skade vergoed wat gedurende die aanleg, onderhoud of verwydering van sodanige riolohooplyleidings en ander werke veroorsaak word.

Administrateurskennisgewing 257

4 Maart 1981

ALBERTON-WYSIGINGSKEMA 2.

Hierby word ooreenkomstig die bepalings van artikel 36(1) van die Ordonnansie op Dorpsbeplanning en Dorppe, 1965, bekend gemaak dat die Administrateur goedgekeur het dat Alberton-dorpsbeplanningskema, 1979, gewysig word deur die hersonering van Erwe 370 tot en met 373, 428 en Gedeelte B van Erf 325, Alberton, Erwe 13, 14, 18 en 237 tot en met 239, Florentia, Erwe 473 en 475, New Redruth en Gedeelte 74 van die plaas Elandsfontein 108-I.R., almal tot "Opvoekundig".

Kaart 3 en die skemaklousules van die wysigingskema word in bewaring gehou deur die Direkteur van Plaaslike Bestuur, Pretoria en die Stadslerk, Alberton en is beskikbaar vir inspeksie op alle redelike tye.

Hierdie wysiging staan bekend as Alberton-wysigingskema 2.

PB. 4-9-2-4H-2

Administrateurskennisgewing 258

4 Maart 1981

ERMELO-WYSIGINGSKEMA 1/62.

Hierby word ooreenkomstig die bepalings van artikel 36(1) van die Ordonnansie op Dorpsbeplanning en Dorppe, 1965, bekend gemaak dat die Administrateur goedgekeur het dat Ermelo-dorpsbeplanningskema 1, 1954, gewysig word deur die hersonering van Erve 3865 en 3866, Ermelo Uitbreiding 13, van "Munisipaal" tot "Algemene Nywerheid" met 'n digtheid van "Een woonhuis per Bestaande Erf", onderworpe aan sekere voorwaardes.

Kaart 3 en die skemaklousules van die wysigingskema word in bewaring gehou deur die Direkteur van Plaaslike Bestuur, Pretoria en die Stadslerk, Ermelo en is beskikbaar vir inspeksie op alle redelike tye.

Hierdie wysiging staan bekend as Ermelo-wysigingskema 1/62.

PB. 4-9-2-14-62

Administrateurskennisgewing 259

4 Maart 1981

PRETORIA-WYSIGINGSKEMA 638.

Hierby word ooreenkomstig die bepalings van artikel 36(1) van die Ordonnansie op Dorpsbeplanning en Dorppe, 1965, bekend gemaak dat die Administrateur goedgekeur het dat Pretoria-dorpsbeplanningskema, 1974, gewysig word deur die hersonering van Erf 404, Silverton, van "Spesiale Woon" met 'n digtheid van "Een woonhuis per erf" tot "Spesiale Woon" met 'n digtheid van "Een woonhuis per 1 000 m²".

Kaart 3 en die skemaklousules van die wysigingskema word in bewaring gehou deur die Direkteur van Plaaslike Bestuur, Pretoria en die Stadslerk, Pretoria en is beskikbaar vir inspeksie op alle redelike tye.

Hierdie wysiging staan bekend as Pretoria-wysigingskema 638.

PB. 4-9-2-3H-638

Administrator's Notice 260

4 March, 1981

JOHANNESBURG AMENDMENT SCHEME 155.

It is hereby notified in terms of section 38 of the Town-planning and Townships Ordinance, 1965, that whereas an error occurred in Johannesburg Amendment Scheme 155, the Administrator has approved the correction of the scheme by the substitution of the old schedule with a new amended schedule.

PB. 4-9-2-2H-155

Administrator's Notice 261

4 March, 1981

RANDBURG AMENDMENT SCHEME 286.

It is hereby notified in terms of section 36(1) of the Town-planning and Townships Ordinance, 1965, that the Administrator has approved the amendment of Randburg Town-planning Scheme, 1976, by the deletion of condition 2 on Annexure 3180 and the substitution therefore of the following:

"2. The floor space ratio on the lot shall not exceed 0,8 and the coverage for all buildings shall not exceed 60%".

Map 3 and the scheme clauses of the amendment scheme are filed with the Director of Local Government, Pretoria and the Town Clerk, Randburg and are open for inspection at all reasonable times.

This amendment is known as Randburg Amendment Scheme 286.

PB. 4-9-2-132H-286

Administrator's Notice 262

4 March, 1981

DEVIATION AND WIDENING OF DISTRICT ROAD 115, 869 AND OTHER ROAD ADJUSTMENTS: DISTRICTS OF THABAZIMBI AND RUSTENBURG.

The Administrator:

(a) hereby deviates and increases the reserve width, in terms of the provisions of section 5(1)(d) and section 3 of the Road Ordinance, 1957 (Ordinance 22 of 1957) of the sections of:

- (i) District Road 115 over the farms Beaufort 326-K.Q., Hoogeboom 333-K.Q. and Buffelspan 360-K.Q. to varying widths, as shown on the subjoined sketch plan;
- (ii) District Road 869 over the farms Nooitgedacht 406-K.Q. and Klapperrandje 394-K.Q. to varying widths, as shown on the subjoined sketch plan.

(b) hereby declares, in terms of the provisions of section 5(1)(b), 5(1)(c) and section 3 of the said Ordinance, that a public district road, with varying widths, as shown on the subjoined sketch plan, shall exist as an extension of District Road 115 over the farms Buffelspan 329-K.Q., Zwartkop 331-K.Q., Buffelsfontein 360-K.Q., Welgewaagd 358-K.Q., Middelkop 362-K.Q., Pony 395-K.Q. and Klapperrandje 394-K.Q., districts of Thabazimbi and Rustenburg.

E.C.R. 227, dated 16 February, 1981
DP. 08-086-23/22/869 Vol. 2

Administrateurskennisgiving 260

4 Maart 1981

JOHANNESBURG-WYSIGINGSKEMA 155.

Hierby word ooreenkomstig die bepalings van artikel 38 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965, bekend gemaak dat nademaal 'n fout in Johannesburg-wysigingskema 155 ontstaan het, het die Administrateur goedgekeur dat die skema verbeter word deur vervanging van die ou skedule met 'n nuwe gewysigde skedule.

PB. 4-9-2-2H-155

Administrateurskennisgiving 261

4 Maart 1981

RANDBURG-WYSIGINGSKEMA 286.

Hierby word ooreenkomstig die bepalings van artikel 36(1) van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965, bekend gemaak dat die Administrateur goedgekeur het dat Randburg-dorpsbeplanningskema, 1976, gewysig word deur die skrapping van voorwaarde 2 op Bylae 3180 en die vervanging daarvan deur die volgende:

"2. Die vloerraumteverhouding op die lot moet nie 0,8 oorskry nie, en die dekking van alle geboue moet nie 60 % oorskry nie".

Kaart 3 en die skemaklousules van die wysigingskema word in bewaring gehou deur die Direkteur van Plaaslike Bestuur, Pretoria en die Stadsklerk, Randburg en is beskikbaar vir inspeksie op alle redelike tye.

Hierdie wysiging staan bekend as Randburg-wysigingskema 286.

PB. 4-9-2-132H-286

Administrateurskennisgiving 262

4 Maart 1981

VERLEGGING EN VERBREDING VAN DISTRIKS-PAD 115, 869 EN ANDER PADREËLINGS: DISTRIKTE THABAZIMBI EN RUSTENBURG.

Die Administrateur:



(a) verlê en verbreed hiermee, ingevolge die bepalings van artikel 5(1)(d) en artikel 3 van die Padordonnansie, 1957 (Ordonnansie 22 van 1957) die gedeeltes van:

(i) Distrikspad 115 oor die plase Beaufort 326-K.Q., Hoogeboom 333-K.Q. en Buffelspan 360-K.Q. na afwisselende breedtes, soos aangetoon op die bygaande sketsplan;

(ii) Distrikspad 869 oor die plase Nootgedacht 406-K.Q. en Klapperrandje 394-K.Q. na afwisselende breedtes, soos aangetoon op die bygaande sketsplan.

(b) verklaar hiermee, ingevolge die bepalings van artikel 5(1)(b), 5(1)(c) en artikel 3 van die genoemde Ordonnansie, dat 'n openbare distrikspad met afwisselende breedtes, soos aangetoon op die bygaande sketsplan, oor die plase Buffelspan 329-K.Q., Zwartkop 331-K.Q., Buffelsfontein 360-K.Q., Welgewaagd 358-K.Q., Middelkop 362-K.Q., Pony 395-K.Q. en Klapperrandje 394-K.Q. as 'n verlenging van Distrikspad 115, sal bestaan.

UKB. 227 (30), gedateer 16 Februarie 1981
DP. 08-086-23/22/869 Vol. 2



Administrator's Notice 263

4 March, 1981

DECLARATION OF A PUBLIC PROVINCIAL ROAD P219-1 (K43): DISTRICT OF JOHANNESBURG.

The Administrator hereby declares, in terms of the provisions of sections 5(1)(b), 5(1)(c), 5(2)(b) and section 3 of the Road Ordinance, 1957 (Ordinance 22 of 1957) that a Public Provincial Road P219-1 with varying widths, shall exist within the municipal area of Johannesburg.

The general direction, situation and the extent of the said road is shown with appropriate co-ordinates on the subjoined sketch plans.

In terms of the provisions of subsections (2) and (3) of section 5A of the said Ordinance, it is hereby declared that the ground taken up by the said road has been demarcated by means of boundary beacons.

E.C.R. 935(24), dated 25 June, 1980
DP. 012-23/21/P219-1

Administrateurskennisgewing 263

4 Maart 1981



VERKLARING VAN 'N OPENBARE PROVINSIALE PAD P219-1 (K43): DISTRIK JOHANNESBURG.

Die Administrateur verklaar hiermee, ingevolge die bepalings van artikels 5(1)(b), 5(1)(c), 5(2)(b) en artikel 3 van die Padordonnansie, 1957 (Ordonnansie 22 van 1957) dat 'n Openbare Provinciale Pad P219-1 met afwisselende breedtes, binne die munisipale gebied van Johannesburg, sal bestaan.

Die algemene rigting, ligging en die omvang van die genoemde pad word met die toepaslike koördinate op die bygaande sketsplan aangetoon.

Ooreenkomstig die bepalings van subartikels (2) en (3) van artikel 5A van die genoemde Ordonnansie, word hiermee verklaar dat die grond wat die genoemde pad in beslag neem, met grensbakens afgemeerk is.

U.K.B. 935(24), gedateer 25 Junie 1980
DP. 021-23/21/P219-1



CO-ORDINATE LIST

KOÖRDINAATLYS

Lo 27 METERS

CONSTANTS ± 0,00 Y +2 900 000,00 X KONSTANTE

L 50	- 87 219,97	+9 783,34	R 50	- 87 215,68	+10 106,19
L 51	- 87 240,38	+9 732,48	R 51	- 87 221,91	+10 034,78
L 52	- 87 285,15	+9 647,55	R 52	- 87 232,67	+ 9 969,19
L 53	- 87 355,47	+9 545,17	R 53	- 87 254,79	+ 9 884,43
L 54	- 87 391,61	+9 503,98	R 54	- 87 284,66	+ 9 802,14
L 55	- 87 438,26	+9 432,85	R 55	- 87 350,17	+ 9 663,55
L 56	- 87 485,39	+9 400,48	R 56	- 87 405,68	+ 9 584,38
L 57	- 87 564,63	+9 348,20	R 57	- 87 458,38	+ 9 522,57
L 58	- 87 598,21	+9 323,71	R 58	- 87 536,74	+ 9 448,33
L 59	- 87 670,58	+9 282,00	R 59	- 87 608,76	+ 9 399,09
L 60	- 87 713,81	+9 260,65	R 60	- 87 741,98	+ 9 316,88
L 61	- 87 809,37	+9 221,00	R 61	- 87 832,55	+ 9 278,51
L 62	- 87 852,89	+9 203,88	R 62	- 88 121,56	+ 9 162,02
L 63	- 88 068,70	+9 116,48	R 63	- 88 252,72	+ 9 112,93
L 64	- 88 135,48	+9 089,56	R 64	- 88 345,50	+ 9 075,64
L 65	- 88 227,00	+9 049,12	R 65	- 88 476,06	+ 9 025,07
L 66	- 88 319,60	+9 011,37	R 66	- 88 606,24	+ 8 970,70
L 67	- 88 504,39	+8 934,84	R 67	- 88 668,11	+ 8 942,38
L 68	- 88 595,39	+8 898,04	R 68	- 88 726,59	+ 8 954,48
L 69	- 88 642,08	+8 873,71	R 69	- 88 773,49	+ 8 980,95
L 70	- 88 758,65	+8 883,65	R 70	- 88 803,56	+ 9 031,18
L 71	- 88 774,15	+8 887,08	R 71	- 88 801,61	+ 9 052,72
L 72	- 88 780,02	+8 880,26	R 72	- 88 817,26	+ 9 072,21
L 73	- 88 783,55	+8 927,99	R 73	- 88 838,77	+ 9 075,59
L 74	- 88 832,84	+8 994,59	R 74	- 88 915,38	+ 9 117,77
L 75	- 88 862,46	+9 013,89	R 75	- 88 947,49	+ 9 128,97
L 76	- 88 899,77	+9 060,72	R 76	- 88 969,98	+ 9 168,82
L 77	- 88 944,22	+9 068,84	R 77	- 87 312,76	- 9 705,07
L 78	- 88 960,98	+9 082,97	R 78	- 87 324,10	- 9 715,88
L 79	- 88 977,58	+9 079,75	XRI	- 87 201,08	- 9 821,36

THE FIGURE LETTERED XRI, L 50~L 79, R 76~R 86, LI, RI, XRI REPRESENTS
 PUBLIC ROAD IN TOTAL WIDTH AS INTENDED BY PUBLICATION OF THESE
 ROAD ADJUSTMENT AND DEPICTED IN GREATER DETAIL ON PLANS PRS 78/51/8 V
 PRS 78/51/6 V

FIGUUR XRI, L 50~L 79, R 76~R 86, LI, RI, XRI STEL VOOR OPENBARE PAD
 OP VOLLE BREEDTE SOOS BEDOEL NA AFKONDIGING VAN HIERDIE PADREELING
 EN IN MEER BESONDERHEDE GETOON OP PLANNE PRS 78/51/5 V
 PRS 78/51/6 V

Leer Nr / File Nr 10/4/4/2/79-80/47	UK Besluit / Exco Res 935 (24) (1930-06-25)	Plan No PRS 78/51/5 V & 6 V
--	--	--------------------------------

Administrator's Notice 264

4 March, 1981

INCREASE AND DECREASE OF THE ROAD RESERVE OF PROVINCIAL ROAD P219-1 (K43): DISTRICT OF JOHANNESBURG.

The Administrator hereby increases and decreases, in terms of the provisions of section 3 of the Road Ordinance, 1957 (Ordinance 22 of 1957) the width of the road reserve of Public and Provincial Road P219-1 within the municipal area of Johannesburg.

The extent of the increase and decrease of the width of the said public and provincial road is shown on the subjoined sketch plans with appropriated co-ordinates.

In terms of the provisions of subsections (2) and (3) of section 5A of the said Ordinance, it is hereby declared that the increase and decrease of the road reserve of the said public and provincial road, have been demarcated by means of boundary beacons.

E.C.R. 935(24), dated 25 June, 1980
DP. 021-23/21/P219-1

Administrateurskennisgewing 264

4 Maart 1981

VERMEERDERING EN VERMINDERING VAN DIE PADRESERVE VAN PROVINSIALE PAD P219-1 (K43): DISTRIK JOHANNESBURG.


Die Administrateur vermeerder en verminder hiermee, ingevolge die bepalings van artikel 3 van die Padordonnansie, 1957 (Ordonnansie 22 van 1957) die breedte van die padreserve van Openbare en Provinciale Pad P219-1 binne die munisipale gebied van Johannesburg.

Die omvang van die vermeerdering van die breedte van die padreserve van voormalde openbare en provinsiale pad word op die bygaande sketsplanne met toepaslike koördinate aangetoon.

Ooreenkomstig die bepalings van subartikels (2) en (3) van artikel 5A van genoemde Ordonnansie, word hiermee verklaar dat die vermeerdering en vermindering van die padreserve van genoemde openbare en provinsiale pad met grensbakens afgemerkt is.

U.K.B. 935(24), gedateer 25 Junie 1980
DP. 021-23/21/P219-1

KLIPRIVIERSOOG 299-1Q



Municipality of Johannesburg

CO-ORDINATE LIST

LO 27
METRES METERS

KOORDINAATLYS


CONSTANT Y± 0,00 X + 2 900 000,00 KONSTANTE

XL 6	- 87 219, 65	+10 193, 89	XL 10	- 87 314, 98	+10 251, 97
XL 7	- 87 239, 82	+10 229, 80	XL 11	- 87 280, 00	+10 267, 92
XL 8	- 87 269, 86	+10 226, 13	XL 12	- 87 240, 03	+10 274, 80
XL 9	- 87 297, 15	+10 216, 17	LI 88	- 87 220, 20	+10 310, 21

Figuur XL 6 - XL 12, LI88, XL 6 stel voor n gedeelte van padreservé van pad P 186/1 waarmee padreservé verminder word soos bedoel na afkondiging van hierdie padregeling en in meer besonderhede getoon op plante PRS 78/51/4 V

Figure XL 6 - XL 12, LI88, XL 6 represents a portion of road reserve of road P186/1 whereby road reserve is reduce as intended by publication of these road adjustment and depicted in greater detail on plans: PRS 78/51/4 V

Leer Nr / File Nr 10/4/4/2/79-80/47	IJK Besluit / Exco. Res. 935(24) (1980-06-25)	Plan No PRS 78/51/ 4V
--	--	--------------------------



CO-ORDINATE LIST / KOÖRDINAATLYS

Lo 27
METRES METERS

CONSTANT / KONSTANTE

 $Y \pm 0,00$ $X + 2 900 000,00$

L 1	- 87 324, 10	+ 9 715, 98
L 2	- 87 266, 35	+ 9 797, 75
L 3	- 87 258, 44	+ 9 834, 36
XL 1	- 87 232, 40	+ 9 889, 66
XL 2	- 87 216, 92	+ 9 957, 00
XL 3	- 87 211, 13	+ 10 013, 33
XL 4	- 87 211, 01	+ 10 060, 25
R 50	- 87 215, 68	+ 10 106, 19
R 51	- 87 221, 91	+ 10 034, 78
R 52	- 87 232, 67	+ 9 969, 19
R 53	- 87 254, 79	+ 9 884, 43
R 54	- 87 284, 66	+ 9 802, 14

Figuur L1-L3,XL1-XL 4,R 50-R54,L1 stel voorn gedeelte waarmee padreservé vermeerder word soos bedoel na afkondiging van hierdie padreding en in meer besonderhede getoon op plante : PRS 78/51/5 V

Figure L1-L3,XL1-XL 4,R 50-R54,L1 represents the widening of road reserve as intended by publication of these road adjustment and depicted in greater detail on plans: PRS 78/51/5 V

Leer Nr / File Nr	UK Besluit / Exco. Res.	Plan No
10/4/4/2/79-80/47	935(24) (1980-06-25)	PRS 78/51/5 V

Administrator's Notice 265

4 March, 1981

DECLARATION OF A PUBLIC ROAD: DISTRICT
OF JOHANNESBURG.

The Administrator hereby declares in terms of the provisions of sections 5(2)(b), 5(1)(c) and section 3 of the Road Ordinance, 1957 (Ordinance 22 of 1957) that a public road with varying widths, shall exist within the municipal area of Johannesburg.

The general direction, situation and the extent of the said public road is shown with appropriate co-ordinates on the subjoined sketch plan.

In terms of the provisions of subsections (2) and (3) of section 5A of the said Ordinance, it is hereby declared that the ground taken up by the said road has been demarcated by means of boundary beacons.

E.C.R. 935(24), dated 25 June 1980
DP. 021-23/21/P219-1

Administrateurskennisgewing 265

4 Maart 1981


VERKLARING VAN 'N OPENBARE PAD: DISTRIK
JOHANNESBURG.

Die Administrateur verklaar hiermee ingevolge die bepalings van artikels 5(2)(b), 5(1)(c) en artikel 3 van die Padordonnansie, 1957 (Ordonnansie 22 van 1957) dat 'n openbare pad met afwisselende breedtes, binne die munisipale gebied van Johannesburg sal bestaan.

Die algemene rigting, ligging en die omvang van die genoemde openbare pad word op bygaande sketsplan met toepaslike koördinate aangetoon.

Ooreenkomsdig die bepalings van subartikels (2) en (3) van artikel 5A van die genoemde Ordonnansie, word hiermee verklaar dat die grond wat die genoemde pad in beslag neem, met grensbaken afgemerkt is.

U.K.B. 935(24), gedateer 25 Junie 1980
DP. 021-23/21/P219-1



CO-ORDINATE LIST / KOÖRDINAATLYS

Lo 27
METRES / METERSCONSTANT / KONSTANTE
 $Y \pm 0,00$ $X + 2900\,000,00$

	Y	X
L 50	- 87219,97	+ 9783,34
DL 1	- 87099,90	+ 10232,45
DL 2	- 87113,53	+ 9817,34
DL 3	- 87138,52	+ 9818,16
DL 4	- 87138,12	+ 9830,15
DL 5	- 87144,07	+ 9837,77
DL 6	- 87166,08	+ 9844,44
DL 7	- 87185,07	+ 9834,79
DL 8	- 87165,39	+ 9933,35
DL 9	- 87165,67	+ 9885,97
DL 10	- 87154,99	+ 9867,21
DL 11	- 87142,55	+ 9863,43
DL 12	- 87136,91	+ 9867,13
DL 13	- 87126,70	+ 10177,98
XR 1	- 87201,08	+ 9821,36
XR 2	- 87191,70	+ 9842,17

Figuur DL1-DL7, L 50, XR 1, XR 2, DL 8-DL13,
DL1 stel voor Openbare Pad op volle breedte
soos bedoel na aankondiging van hierdie pad-
reeling en in meer besonderhede getoon op
planne PRS 78/51/4V&5V

Figure DL1-DL7, L 50, XR 1, XR 2, DL 8-DL13,
DL1 represents Public Road in total width as
intended by publication of these road
adjustment and depicted in greater detail on
plans: PRS 78/51/4V&5V

Leer Nr / Fisie Nr	UK Besluit / Exco.Res	Plan No
10/4/4/2/79-80/47	935(24) (1980-06-25)	PRS 78/51/4&5V

Administrator's Notice 266

4 March, 1981

DECLARATION OF A PUBLIC DISTRICT ROAD AND RELATIVE ROAD ADJUSTMENTS: DISTRICT OF POTGIELTERSRSUS.

The Administrator —

- A. hereby declares, in terms of the provisions of section 5(1)(b), 5(1)(c) and section 3 of the Road Ordinance, 1957 (Ordinance 22 of 1957) that a public district road with a reserve width of 40 metre shall exist as an extension of District Road 2420 over the farms George Wellington 795-L.R., Gemsbokfontein 585-L.R. and Baviaansdraai 587-L.R., district of Potgietersrus.
- B. hereby deviates and increases, in terms of the provisions of section 5(1)(d) and section 3 of the said Ordinance the width of the road reserve of:
 - (a) District Road 579 over the farms Baviaansdraai 587-L.R., Kwarriehoek 584-L.R., Rhynosterfontein 583-L.R. and Daggakraal 591-L.R. to 40 metre.
 - (b) District Road 888 over the farm Rhynosterfontein 583-L.R. to varying widths of 25 metre to 115 metre.
- C. hereby closes, in terms of the provisions of section 5(1)(d) of the said Ordinance, the section of District Road 888 over the farms Daggakraal 591-L.R. and Rhynosterfontein 583-L.R.
- D. hereby declares, in terms of the provisions of section 48(1)(a) of the said Ordinance, that an access road with a minimum reserve width of 16 metre, shall exist over the farms Daggakraal 591-L.R. and Rhynosterfontein 583-L.R.

The general direction and situation of the deviations and the extent of the road reserve widths of the said roads, are shown on the subjoined sketch plan.

In terms of the provisions of subsections (2) and (3) of section 5A of the said Ordinance, it is hereby declared that the land taken up by the various road adjustments, has been demarcated by means of cairns.

E.C.R. 1810(23), dated 11 November, 1980
DP. 03-033-23/22/2420

Administrateurskennisgewing 266

4 Maart 1981

VERKLARING VAN OPENBARE DISTRIKSPAD EN VERWANTE PADREËLINGS: DISTRIK POTGIELTERSRSUS.


Die Administrateur —

- A. Verklaar hiermee, ingevolge die bepalings van artikels 5(1)(b), 5(1)(c) en artikel 3 van die Padordonnansie, 1957 (Ordonnansie 22 van 1957) dat 'n openbare distrikspad met 'n reserwebreedte van 40 meter, as 'n verlenging van Distrikspad 2420 oor die plase George Wellington 795-L.R., Gemsbokfontein 585-L.R. en Baviaansdraai 587-L.R., distrik Potgietersrus, sal bestaan.
- B. Verlê en vermeerder hiermee, ingevolge die bepalings van artikel 5(1)(d) en artikel 3 van genoemde Ordonnansie, die reserwebreedte van:
 - (a) Distrikspad 579 oor die plase Baviaansdraai 587-L.R., Kwarriehoek 584-L.R., Rhynosterfontein 583-L.R. en Daggakraal 591-L.R. na 40 meter.
 - (b) Distrikspad 888 oor die plaas Rhynosterfontein 583-L.R., na afwisselende breedtes van 25 meter tot 115 meter.
- C. Sluit hiermee, ingevolge die bepalings van artikel 5(1)(d) van genoemde Ordonnansie, die gedeelte van Distrikspad 888 oor die plase Daggakraal 591-L.R. en Rhynosterfontein 583-L.R.
- D. Verklaar hiermee, ingevolge die bepalings van artikel 48(1)(a) van genoemde Ordonnansie, dat 'n toegangspad met 'n minimum reserwebreedte van 16 meter, oor die plase Daggakraal 591-L.R. en Rhynosterfontein 583-L.R., sal bestaan.

Die algemene rigting en ligging van die verleggings en die omvang van die reserwebreedtes van genoemde paaie, word op bygaande sketsplan aangetoon.

Ooreenkomsdig die bepalings van subartikels (2) en (3) van artikel 5A van genoemde Ordonnansie, word hiermee verklaar dat die grond, wat die onderskeie padreëlings in beslag neem, met klipstapels afgemerkt is.

U.K.B. 1810(23), gedateer 11 November 1980
DP. 03-033-23/22/2420



Administrator's Notice 267

4 March, 1981

CLOSING OF AN UNNUMBERED PUBLIC ROAD
OVER THE FARM BOK 356-L.S., DISTRICT OF
PIETERSBURG.

With reference to Administrator's Notice 1862, dated 19 November, 1980, the Administrator hereby closes in terms of the provisions of section 29(6) of the Road Ordinance, 1957 (Ordinance 22 of 1957) the unnumbered public road, as shown on the subjoined sketch plan, over the farm Bok 356-L.S., district of Pietersburg.

Approved 10 February, 1981
DP. 03-032-23/24/B-6


Administratorskennisgewing 267

4 Maart 1981

SLUITING VAN 'N ONGENOMMERDE OPENBARE
PAD OOR DIE PLAAS BOK 356-L.S., DISTRIK PIETERSBURG.

Met verwysing na Administratorskennisgewing 1862, gedateer 19 November 1980 sluit die Administrateur hiermee, ingevolge die bepalings van artikel 29(6) van die Padordonnansie, 1957 (Ordonnansie 22 van 1957) die ongenommerde openbare pad, soos op die bygaande sketsplan aangetoon, oor die plaas Bok 356-L.S., distrik Pietersburg.

Goedgekeur 10 Februarie 1981
DP. 03-032-23/24/B-6



Administrator's Notice 268

4 March, 1981

DECLARATION AND WIDENING OF PUBLIC ROAD: DISTRICT OF KLERKS DORP.

The Administrator:

- (a) hereby declares, in terms of the provisions of sections 5(1)(a) and 5(1)(c) of the Road Ordinance, 1957 (Ordinance 22 of 1957) that the road over the farms Paardeplaats 265-I.P. and Rietfontein 266-I.P., district of Klerksdorp, shall exist as Public District Road 2473;
- (b) hereby increases, in terms of the provisions of section 3 of the said Ordinance, the reserve width of the said District Road 2473 over the said farms to varying widths of 25 metre to 115 metre.

The general direction and situation and the extent of the increase of the reserve width of the said road, is shown on the subjoined sketch plan.

In terms of the provisions of subsections (2) and (3) of section 5A of the said Ordinance, it is hereby declared that the land taken up by the said road, has been demarcated by means of iron pegs.

E.C.R. 713(2), dated 10 May, 1980
DP. 07-073-23/22/2473

Administrateurskennisgewing 268

4 Maart 1981

VERKLARING EN VERBREDING VAN OPENBARE DISTRIKSPAD: DISTRIK KLERKS DORP.


Die Administrateur:

- (a) verklaar hiermee, ingevolge die bepaling van artikels 5(1)(a) en 5(1)(c) van die Padordonnansie, 1957 (Ordonnansie 22 van 1957) dat die pad oor die plase Paardeplaats 265-I.P. en Rietfontein 266-I.P., distrik Klerksdorp, as Openbare Distrikspad 2473 sal bestaan;
- (b) vermeerder hiermee, ingevolge die bepaling van artikel 3 van genoemde Ordonnansie, die reserwebreedte van genoemde Distrikspad 2473 oor genoemde plase na afwisselende breedtes van 25 meter tot 115 meter.

Die algemene rigting en ligging van genoemde pad en die omvang van die vermeerdering van die reserwebreedte daarvan word op bygaande sketsplan aangetoon.

Ooreenkomsdig die bepaling van subartikels (2) en (3) van artikel 5A van genoemde Ordonnansie, word hiermee verklaar dat die grond wat genoemde pad in beslag neem, met ysterpenne afgemerkt is.

U.K.B. 713(2), gedateer 10 Mei 1980
DP. 07-073-23/22/2473



General Notices

NOTICE 161 OF 1981.

MIDDELBURG AMENDMENT SCHEME 41.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, Estate Late Charles Deiner, Co. Messrs. Rosmarin, Els and Taylor, P.O./ Box 32004, Braamfontein for the amendment of Middelburg Town-planning Scheme, 1974, by rezoning of Portion 1 of Erf 43, situated on Lang Street and Hendrik Potgieter Street, Middelburg Township from "Special Residential" with a density of "One dwelling per 1 500 m²" to "General Business".

The amendment will be known as Middelburg Amendment Scheme 41. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Middelburg and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria and the Town Clerk, P.O. Box 14, Middelburg, 1050, at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,

Director of Local Government.

Pretoria, 25 February, 1981.

PB. 4-9-2-21H-41

NOTICE 162 OF 1981.

PRETORIA AMENDMENT SCHEME 699.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, Raymond Michael White, Private Bag X428, Pretoria for the amendment of Pretoria Town-planning Scheme, 1974, by rezoning Erf 183, situated on Hastie Street, Kilnerpark Township from "Special Residential" with a density of "One dwelling per erf" to "Special

Algemene Kennisgewings

KEENNISGEWING 161 VAN 1981.

MIDDELBURG-WYSIGINGSKEMA 41.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, boedel wyle Charles Deiner, P/a. mnre. Rosmarin, Els en Taylor, Posbus 32004, Braamfontein aansoek gedoen het om Middelburg-dorpsbeplanningskema, 1974, te wysig deur die hersonering van Gedeelte 1 van Erf 43, geleë aan Langstraat en Hendrik Potgieterstraat, dorp Middelburg van "Spesiale Woon" met 'n digtheid van "Een woonhuis per 1 500 m²" tot "Algemene Besigheid".

Verdere besonderhede van hierdie wysigingskema (wat Middelburg-wysigingskema 41 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Middelburg ter insae.

Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovermelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 14, Middelburg, 1050, skriftelik voorgelê word.

S. W. B. BRITS,

Direkteur van Plaaslike Bestuur.

Pretoria, 25 Februarie 1981.

PB. 4-9-2-21H-41

KENNISGEWING 162 VAN 1981.

PRETORIA-WYSIGINGSKEMA 699.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, Raymond Michael White, Privaatsak X427, Pretoria aansoek gedoen het om Pretoria-dorpsbeplanningskema, 1974, te wysig deur die hersonering van Erf 183, geleë aan Hastiestraat, dorp Kilnerpark van "Spesiale Woon" met 'n digtheid van "Een woonhuis per erf" tot

Residential" with a density of "One dwelling per 1 250 m²".

The amendment will be known as Pretoria Amendment Scheme 699. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Pretoria and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and the Town Clerk, P.O. Box 440, Pretoria, 0001, at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 25 February, 1981.

PB. 4-9-2-3H-699

"Spesiale Woon" met 'n digtheid van "Een woonhuis per 1 250 m²".

Verdere besonderhede van hierdie wysigingskema (wat Pretoria-wysigingskema 699 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Pretoria ter insae.

Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovenmelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 440, Pretoria, 0001, skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur,
Pretoria, 25 Februarie 1981.

PB. 4-9-2-3H-699

NOTICE 163 OF 1981.

EDENVALE AMENDMENT SCHEME 16.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, Protea Calendars (Proprietary) Limited, C/o. Mr. E. X. Laubscher, Rand Publishers (Pty.) Ltd., P.O. Box 777, Edenvale for the amendment of Edenvale Town-planning Scheme, 1980 by rezoning Lot 494, situated on Fifteenth Avenue, Edenvale Township from "Residential 1" with a density of "One dwelling per 700 m²" to "Special" for the purposes of publishing/printing works and purposes incidental thereto only.

The amendment will be known as Edenvale Amendment Scheme 16. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Edenvale and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria and the Town Clerk, P.O. Box 25, Edenvale, 1610, at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 25 February, 1981.

PB. 4-9-2-13H-16

KENNISGEWING 163 VAN 1981.

EDENVALE-WYSIGINGSKEMA 16.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, Protea Calendars (Proprietary) Limited, P/a. mnr. E. X. Laubscher, Rand Publishers (Pty.) Ltd., Posbus 777, Edenvale aansoek gedoen het om Edenvale-dorpsbeplanningskema, 1980, te wysig deur die hersoneering van Lot 494, geleë aan Vyftiende Laan, dorp Edenvale van "Residensieel 1" met 'n digtheid van "Een woonhuis per 700 m²" tot "Spesiaal" vir die doeleindes van 'n drukkery/publiseringswerk en doeleindes in verband daarmee.

Verdere besonderhede van hierdie wysigingskema (wat Edenvale-wysigingskema 16 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Edenvale ter insae.

Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovenmelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 25, Edenvale, 1610, skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 25 Februarie 1981.

PB. 4-9-2-13H-16

NOTICE 164 OF 1981.

NYLSTROOM AMENDMENT SCHEME 1/16.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, Gysbertus Johannes Joubert, 53 Church Street, Elsburg for the amendment of Nylstroom Town-planning Scheme, 1963, by rezoning of Remainder of Erf 1139, situated on Allen Street and Potgieter Street, Nylstroom Extension 2 Township from "Special Residential" with a density of "One dwelling per 1 000 m²" to "Special" for a public garage and restaurant.

KENNISGEWING 164 VAN 1981.

NYLSTROOM-WYSIGINGSKEMA 1/16.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, Gysbertus Johannes Joubert, Kerkstraat 53, Elsburg aansoek gedoen het om Nylstroom-dorpsaanlegskema, 1963, te wysig deur die hersoneering van die Restant van Erf 1139, geleë aan Allenstraat en Potgieterstraat, dorp Nylstroom Uitbreiding 2 van "Spesiale Woon" met 'n digtheid van "Een woonhuis per 1 000 m²" tot "Spesiaal" vir 'n publieke garage en restaurant.

The amendment will be known as Nylstroom Amendment Scheme 1/16. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Nylstroom and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and the Town Clerk, Private Bag 1008, Nylstroom, 1510, at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 25 February, 1981.

PB. 4-9-2-65-16

Verdere besonderhede van hierdie wysigingskema (wat Nylstroom-wysigingskema 1/16 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Nylstroom ter insae.

Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovenmelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 1008, Nylstroom, 1510, skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 25 Februarie 1981.

PB. 4-9-2-65-16

NOTICE 165 OF 1981.

SANDTON AMENDMENT SCHEME 378.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, Michael William Harrison, C/o. Messrs. Tompkins & Scott, P.O. Box 52161, Saxonwold, for the amendment of Sandton Town-planning Scheme, 1980, by rezoning Erf 10, situated on Culross Road and Main Road, Bryanston Township from "Residential 1" with a density of "One dwelling per erf" to "Residential 1" with a density of "One dwelling per 3 000 m²".

The amendment will be known as Sandton Amendment Scheme 378. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Sandton, and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and the Town Clerk, P.O. Box 78001, Sandton, 2146, at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 25 February, 1981.

PB. 4-9-2-116H-378

NOTICE 166 OF 1981.

BRAKPAN AMENDMENT SCHEME 1/72.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, Hertzel Yellin, C/o. Messrs. Gillespie Archibald & Partners, P.O. Box 589, Benoni for the amendment of Brakpan Town-planning Scheme, 1980, by rezoning of Lot 952, situated on Queen Avenue and Gordon Street, Brakpan Township from "General Residential" with a density of "Two dwellings per erf" to "Public Garage".

The amendment will be known as Brakpan Amendment Scheme 1/72. Further particulars of the scheme are open for inspection at the office of the Town Clerk,

KENNISGEWING 165 VAN 1981.

SANDTON-WYSIGINGSKEMA 378.

Hierby word ooreenkomstig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, Michael William Harrison, P/a. mnre. Tompkins & Scott, Posbus 52161, Saxonwold aansoek gedoen het om Sandton-dorpsbeplanningskema, 1980, te wysig deur die hersonering van Erf 10, geleë aan Culrossweg en Mainweg, dorp Bryanston van "Residensieel 1" met 'n digtheid van "Een woonhuis per erf" tot "Residensieel 1" met 'n digtheid van "Een woonhuis per 3 000 m²".

Verdere besonderhede van hierdie wysigingskema (wat Sandton-wysigingskema 378 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Sandton ter insae.

Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovenmelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 78001, Sandton, 2146, skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 25 Februarie 1981.

PB. 4-9-2-116H-378

KENNISGEWING 166 VAN 1981.

BRAKPAN-WYSIGINGSKEMA 1/72.

Hierby word ooreenkomstig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, Hertzel Yellin, P/a. mnre. Gillespie Archibald & Vennote, Posbus 589, Benoni, aansoek gedoen het om Brakpan-dorpsbeplanningskema, 1980, te wysig deur die hersonering van Lot 952, geleë aan Queenslaan en Gordonstraat, dorp Brakpan van "Algemene Woon" met 'n digtheid van "Twee woonhuise per erf" tot "Openbare Garage".

Verdere besonderhede van hierdie wysigingskema (wat Brakpan-wysigingskema 1/72 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur,

Brakpan, and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and the Town Clerk, P.O. Box 15, Brakpan, 1540, at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 25 February, 1981.

PB. 4-9-2-9-72

NOTICE 167 OF 1981.

SANDTON AMENDMENT SCHEME 377.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, Johannes Bartholomeus van Schalkwyk, C/o. Messrs. Tompkins & Scott, P.O. Box 52161, Saxonwold for the amendment of Sandton Town-planning Scheme, 1980, by rezoning Erf 17, situated on Sloane Street and Eaton Avenue, Bryanston Township from "Residential 1" with a density of "One dwelling per erf" to "Residential 1" with a density of "One dwelling per 4 000 m²".

The amendment will be known as Sandton Amendment Scheme 377. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Sandton and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and the Town Clerk, P.O. Box 78001, Sandton, 2146, at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 25 February, 1981.

PB. 4-9-2-116H-377

NOTICE 168 OF 1981.

SANDTON AMENDMENT SCHEME 371.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, Hilary May Johnson, C/o. Messrs. Haacke Belling Partnership, P.O. Box 31080, Braamfontein for the amendment of Sandton Town-planning Scheme, 1980, by rezoning Erf 140, situated on Summit Road and Woodburn Road, Morningside Extension 2 Township from "Residential 1" with a density of "One dwelling per erf" to "Residential 2" Height Zone 4.

The amendment will be known as Sandton Amendment Scheme 371. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Sandton and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Brakpan ter insae.

Enige beswaar of vertoe teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovemelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 15, Brakpan, 1540, skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 25 Februarie 1981.

PB. 4-9-2-9-72

KENNISGEWING 167 VAN 1981.

SANDTON-WYSIGINGSKEMA 377.

Hierby word ooreenkomstig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, Johannes Bartholomeus van Schalkwyk, P/a. mnre: Tompkins & Scott, Posbus 52161, Saxonwold aansoek gedoen het om Sandton-dorpsbeplanningskema, 1980, te wysig deur die hersonering van Erf 17, geleë aan Sloanestraat en Eatonlaan, dorp Bryanston van "Residensieel 1" met 'n digtheid van "Een woonhuis per erf" tot "Residensieel 1" met 'n digtheid van "Een woonhuis per 4 000 m²".

Verdere besonderhede van hierdie wysigingskema (wat Sandton-wysigingskema 377 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Sandton ter insae.

Enige beswaar of vertoe teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovemelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 78001, Sandton, 2146, skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 25 Februarie 1981.

PB. 4-9-2-116H-377

KENNISGEWING 168 VAN 1981.

SANDTON-WYSIGINGSKEMA 371.

Hierby word ooreenkomstig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, Hilary May Johnson, P/a. mnre. Haacke Belling Venootskap, Posbus 31080, Braamfontein, aansoek gedoen het om Sandton-dorpsaanlegskema, 1980, te wysig deur die hersonering van Erf 140, geleë aan Summitweg en Woodburnweg, dorp Morningside Uitbreiding 2 van "Residensieel 1" met 'n digtheid van "Een woonhuis per erf" tot "Residensieel 2" Hoogtesone 4.

Verdere besonderhede van hierdie wysigingskema (wat Sandton-wysigingskema 371 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Sandton ter insae.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and the Town Clerk, P.O. Box 78001, Sandton 2146, at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 25 February, 1981.

PB. 4-9-2-116H-371

NOTICE 169 OF 1981.

PRETORIA AMENDMENT SCHEME 704.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, EMDE Properties (Proprietary) Limited, C/o. Mr. E. R. Bryce and Associates, P.O. Box 28528, Sunnyside, Pretoria, for the amendment of Pretoria Town-planning Scheme, 1974, by rezoning of Lot 455, situated on Moot Street and Taljaard Street, Daspoort Township from "Special" for the purposes of a warehouse, and cold storage and the parking and maintenance of vehicles "Special" for offices and "Special Residential" with a density of "One dwelling per erf" to "Special" for the purposes of a warehouse, meat processing, cold storage, offices, dwelling-houses, parking and the maintenance of vehicles subject to certain conditions.

The amendment will be known as Pretoria Amendment Scheme 704. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Pretoria and at the office of the Director of Local Government, 11th Floor, Mérino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and the Town Clerk, P.O. Box 440, Pretoria, 0001, at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 25 February, 1981.

PB. 4-9-2-3H-704

NOTICE 170 OF 1981.

PRETORIA AMENDMENT SCHEME 703.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, Lidia Braunholz, C/o. Messrs. M. P. Dix, 458 Monica Road, Lynnwood, Pretoria for the amendment of Pretoria Town-planning Scheme, 1974, by rezoning the northern part of the Remaining Extent of Erf 1542, Pretoria Township from "Special Residential" with a density of "One dwelling per 500 m²" to "Special" for a warehouse subject to certain conditions.

The amendment will be known as Pretoria Amendment Scheme 703. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Pre-

Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovermelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 78001, Sandton, 2146, skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 25 Februarie 1981.

PB. 4-9-2-116H-371

KENNISGEWING 169 VAN 1981.

PRETORIA-WYSIGINGSKEMA 704.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, EMDE Properties (Proprietary) Limited, P/a. mnr. E. R. Bryce en Medewerkers, Posbus 28528, Sunnyside, Pretoria aansoek gedoen het om Pretoria-dorpsbeplanningskema, 1974, te wysig deur die hersonering van Lot 455, geleë aan Mootstraat en Taljaardstraat, dorp Daspoort, van "Spesiaal" vir die doeleindes van 'n pakhuis, en koelkamers en die parkering en onderhou van voertuie, "Spesiaal" vir kantore en "Spesiale Woon" met 'n digtheid van "Een woonhuis per Erf" tot "Spesiaal" vir die doeleindes van 'n pakhuis, vleisverwerking, koelkamers, kantore, woonhuise, parkering en die onderhou van voertuie onderworpe aan sekere voorwaardes.

Verdere besonderhede van hierdie wysigingskema (wat Pretoria-wysigingskema 704 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v, Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Pretoria ter insae.

Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovermelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 440, Pretoria, 0001, skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 25 Februarie 1981.

PB. 4-9-2-3H-704

KENNISGEWING 170 VAN 1981.

PRETORIA-WYSIGINGSKEMA 703.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, Lidia Braunholz, P/a. mnr. M. P. Dix, Monicaweg 458, Lynnwood, Pretoria, aansoek gedoen het om Pretoria-dorpsbeplanningskema, 1974, te wysig deur die hersonering van die noordelike deel van die Resterende Gedeelte van Erf 1542, dorp Pretoria van "Spesiale Woon" met 'n digtheid van "Een woonhuis per 500 m²" tot "Spesiaal" vir 'n pakhuis onderworpe aan sekere voorwaardes.

Verdere besonderhede van hierdie wysigingskema (wat Pretoria-wysigingskema 703 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de

toria and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and the Town Clerk, P.O. Box 440, Pretoria, 0001, at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 25 February, 1981.

PB. 4-9-2-3H-703

NOTICE 172 OF 1981.

PROPOSED ESTABLISHMENT OF TOWNSHIPS.

It is hereby notified in terms of section 58(8)(2) of the Town-planning and Townships Ordinance, 1965, that applications to establish the townships mentioned in the annexure hereto have been received.

The applications, together with the relevant plans, documents and information are open for inspection at the office of the Director of Local Government, Room B206(a), Second Floor, Block B, Provincial Building, Pretorius Street, Pretoria for a period of 8 weeks from 4 March, 1981.

Any person who desires to object to the granting of any of the applications or who desires to make any representations in regard thereto, must notify the Director of Local Government in writing of his reasons therefor within a period of 8 weeks from the date of first publication hereof.

Objections and representations in duplicate should be addressed to the Director of Local Government, Private Bag X437, Pretoria, 0001.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 4 March, 1981.

ANNEXURE.

Name of township: Delmas Extension 12.

Name of applicant: Jacobus Lodewikus Prinsloo Giliomee.

Number of erven: Residential 3: 2; Public Open Space: 1.

Description of land: Portion 24 (portion of Portion 15) of the farm Witklip 232-I.R., district Delmas.

Situation: North of and abuts Portion 32 of the farm Witklip 232-I.R. east of and abuts Van der Walt Street and Delmas Extension 2 Township.

Reference No.: PB-4-2-2-6235.

Name of township: Morningside Extension 38.

Name of applicant: Cyrie James McBride.

Number of erven: Residential 1: 1; Residential 2: 4.

Description of land: Portion 416 (a portion of Portion 119) of the farm Zandfontein No. 42-I.R., district Johannesburg.

Vloer, Merino Gebou, h/v. Bosman- en Pretoriussstraat, Pretoria en in die kantoor van die Stadsklerk van Pretoria ter insae.

Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovemelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 440, Pretoria, 0001, skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 25 Februarie 1981.

PB. 4-9-2-3H-703

KENNISGEWING 172 VAN 1981.

VOORGESTELDE STIGTING VAN DORPE.

Ingevolge artikel 58(8)(2) van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 word hiermee bekend gemaak dat aansoeke om die dorpe in die bylae hierby gemeld te stig, ontvang is.

Die aansoeke tesame met die tersaaklike planne, dokumente en inligting lê ter insae by die kantoor van die Direkteur van Plaaslike Bestuur, Kamer B206(a), 2de Vloer, Blok B, Provinciale Gebou, Pretoriussstraat, Pretoria vir 'n tydperk van 8 weke vanaf 4 Maart 1981.

Iedereen wat beswaar teen die toestaan van 'n aansoek wil maak of begerig is om enige vertoë in verband daar mee te rig, moet die Direkteur van Plaaslike Bestuur binne 'n tydperk van 8 weke van die datum van eerste publikasie hiervan, nl. 4 Maart 1981 skriftelik van sy redes in kennis stel.

Besware en vertoë moet in duplo ingedien word en moet gerig word aan die Direkteur van Plaaslike Bestuur, Privaatsak X437, Pretoria 0001.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 4 Maart 1981.

BYLAE.

Naam van dorp: Delmas Uitbreiding 12.

Naam van aansoekdoener: Jacobus Lodewikus Prinsloo Giliomee.

Aantal erwe: Residensieel 3: 2; Openbare Oop Ruimte: 1.

Beskrywing van grond: Gedeelte 24 (gedeelte van Gedeelte 15) van die plaas Witklip 232-I.R., distrik Delmas.

Liggings: Noord van en grens aan Gedeelte 32 van die plaas Witklip 232-I.R., oos van en grens aan Van der Waltstraat en Delmas Uitbreiding 2 Dorp.

Verwysingsnommer: PB: 4-2-2-6235.

Naam van dorp: Morningside Uitbreiding 38.

Naam van aansoekdoener: Cyrie James McBride.

Aantal erwe: Residensieel 1: 1; Residensieel 2: 4.

Beskrywing van grond: Geleë op Gedeelte 416 ('n gedeelte van Gedeelte 119) op die plaas Zandfontein No. 42-I.R., distrik Johannesburg.

Situation: East of and abuts Summit Road, south of and abuts Kelvin Drive.

Remarks: This advertisement supersedes all previous advertisements in respect of Morningside Extension 38.

Reference No.: PB. 4-2-2-2659.

Name of township: Bryanston Extension 42.

Name of applicant: Bryanmore Estate Limited.

Number of erven: Residential 1: 7; Residential 3: 7; Public Open Space: 1.

Description of Land: Portion 196, Portion 198 and Remainder of Portion 191 of the farm Driefontein 41-I.R., district Johannesburg.

Situation: East of and abuts Bryanston Extension 7 and north of and abuts Bryanston Extension 13.

Reference No.: PB. 4-2-2-6221.

NOTICE 173 OF 1981.

SANDTON AMENDMENT SCHEME 226.

The Director of Local Government hereby gives notice in terms of section 31 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965), that the Town Council of Sandton has submitted an interim scheme, which is an amendment scheme, to wit, the Sandton Amendment Scheme 226 to amend the relevant town-planning Scheme in operation, to wit, the Sandton Town-planning Scheme, 1980.

This draft scheme contains the following proposals:

The addition to Clause 21 of the following proviso:

"21(6) Notwithstanding any provision contained in this scheme to the effect that only one dwelling-house per erf may be built, one dwelling-unit may, subject to the approval of the local authority, be erected on any erf on which a dwelling-house is in existence or is being erected in terms of the provisions of this scheme, subject to the following conditions:

- (a) (i) The area of such dwelling unit shall not exceed 90 m² measured over the outside of the walls, or in a case where part of an existing two or more storey house is partly converted into a dwelling unit, such area shall not exceed 90 m² or the area of one existing storey of such a house, whichever is the larger.
- (ii) The local authority may grant approval for the area of such dwelling-unit to exceed that set out in (a)(i) above where the buildings on the erf were in existence on 1 January, 1980.
- (b) The dwelling-unit shall be satisfactorily linked to and architecturally integrated with the main dwelling-house: Provided that the local authority may relax the provisions of this sub-clause.
- (c) A minimum of one off-street motorcar parking bay shall be provided on the erf to serve the exclusive needs of the dwelling-unit.
- (d) The design of the dwelling-unit including any garage or car-port associated therewith, as well as the location thereof, access to and egress from the site

Ligging: Oos van en grens aan Summit Road, suid van en grens aan Kelvin Drive.

Opmerkings: Hierdie advertensie vervang alle vorige advertenties met betrekking tot Morningside Uitbreiding 38.

Verwysingsnommer: PB. 4-2-2-2659.

Naam van dorp: Bryanston Uitbreiding 42.

Naam van aansoekdoener: Bryanmore Estate Limited.

Aantal erwe: Residensieel 1: 7; Residensieel 3: 7; Openbare Oop Ruimte: 1.

Beskrywing van grond: Gedeelte 196, Gedeelte 198 en die Restant van Gedeelte 191 van die plaas Driefontein 41-I.R., distrik Johannesburg.

Ligging: Oos van en grens aan Bryanston Uitbreiding 7 en noord van en grens aan Bryanston Uitbreiding 13.

Verwysingsnommer: PB. 4-2-2-6221.

KENNISGEWING 173 VAN 1981.

SANDTON-WYSIGINGSKEMA 226.

Die Direkteur van Plaaslike Bestuur gee hierby kennis kragtens artikel 31 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965), dat die Stadsraad van Sandton 'n voorlopige skema, wat 'n wysigingskema is, te wete die Sandton-wysigingskema 226 voorgelê het om die betrokke dorpsbeplanningskema in werking te wete, die Sandton-dorpsbeplanningskema 1980 te wysig.

Hierdie ontwerpskema bevat die volgende voorstelle: —

Die byvoeging van die volgende sub-klousule tot Klousule 21.

"21(6) Ondanks enige bepaling vervaat in hierdie skema waarvolgens slegs een woonhuis per erf gebou mag word, mag onderhewig aan die goedkeuring van die plaaslike bestuur en onderhewig aan die volgende voorwaardes een wooneenheid opgerig word, op enige erf waarop 'n woonhuis bestaan of opgerig word: —

- (a) (i) Die oppervlakte van sodanige wooneenheid mag nie 90 m², gemeet vanaf die buitekant van die mure, oorskry nie, of in 'n geval waar 'n gedeelte van 'n bestaande twee of meer verdieping huis gedeeltelik in 'n wooneenheid omskep word, mag sodanige oppervlakte nie 90 m², of die oppervlakte van een bestaande verdieping van sodanige huis, watter ookaal die grootste is, oorskry nie.
- (ii) Waar die geboue op die erf op 1 Januarie 1980 bestaan het, mag die plaaslike bestuur goedkeuring verleen dat die oppervlakte van sodanige wooneenheid die oppervlakte omskryf in (a)(i) hierby oorskry.
- (b) Die wooneenheid moet bevredigend verbind en argitektonies ingeskakel wees met die hoof woonhuis. Met dien verstande dat die plaaslike bestuur die bepaling van hierdie sub-klousule mag verslap.
- (c) 'n Minimum van een buitenstraatse motorparkeerplek moet op die erf voorsien word om aan die uitsluitlike behoeftes van die wooneenheid te voorseen.
- (d) Die ontwerp van die wooneenheid, insluitende enige motorhuis of motorafdak verbonde daarmee, so wel

and parking arrangements shall be architecturally integrated with and harmoniously related to the dwelling-house, to the satisfaction of the local authority.

(c) Prior to the submission of building plans, a sketch plan indicating the full extent of the proposed development shall be submitted. Such plan shall indicate at least the following:

- (i) Points of access to and egress from the erf, internal driveways and parking arrangements;
- (ii) All existing and/or proposed development, including buildings, garden walls, pools, tennis courts and other structures;
- (iii) The location of existing/proposed sewer lines and water mains;
- (iv) Access points to buildings;
- (v) The height of all buildings;
- (vi) The elevational treatment of all buildings and structures (existing and proposed); and
- (vii) Side and rear spaces.

When considering this plan the local authority shall be satisfied that the proposed development will not be detrimental to the harmonious development of the erf, and furthermore that it will have no detrimental effect on residential amenity within the locality; especially the overlooking of outdoor living and garden areas on neighbouring properties.

(f) The local authority may either grant or withhold its approval, and may impose such conditions in any particular case as it may deem fit.

(g) The provision of essential services shall be to the satisfaction of the local authority.

(h) The local authority may relax any of the conditions contained in this sub-clause where the buildings on a particular erf were in existence on 1 January, 1980.

(i) For the purpose of this sub-clause "dwelling-unit" means a suite of rooms which includes a bathroom and kitchen, designed for occupation by a single family.

The aforesaid interim scheme is open for inspection at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Pretorius and Bosman Streets, Pretoria and at the office of the Town Clerk of the Town Council of Sandton.

Where in terms of section 32 of the aforesaid Ordinance, any owner or occupier of immovable property and any local authority have the right to lodge an objection or to make representations in respect of the said interim scheme, such owner or occupier or local authority shall submit such objection or may make such representations in writing to the Director of Local Government, at the above address or Private Bag X437, Pretoria within a period of four weeks from the date of the first publication of this notice in the *Provincial Gazette*.

S. W. B. BRITS,

Director of Local Government.

Pretoria, 4 March 1981.

PB: 4-9-2-116H-226

as die ligging daarvan, ingang tot en uitgang vanaf die terrein en parkering moet argitektonies ingeskakel en harmonieus in verband staan met die woonhuis, tot die bevrediging van die plaaslike bestuur.

(e) Alvorens die indiening van bouplanne, moet 'n sketsplan wat die volle omvang van die voorgestelde ontwikkeling aantoon ingedien word. Sodaanige plan moet ten minste die volgende aantoon:

- (i) Punte van ingang tot en uitgang vanaf die erf, interne rylane en parkeering;
- (ii) Alle bestaande en/of voorgestelde ontwikkeling, insluitend geboue, tuinmure, swembaddens, tennisbane en ander strukture;
- (iii) Die ligging van bestaande/voorgestelde rioollyne en hoof waterpype;
- (iv) Ingange tot geboue;
- (v) Die hoogte van alle geboue;
- (vi) Die aansigbehandeling van alle geboue en strukture (bestaande en voorgestelde); en
- (vii) Kant- en agterkantruimtes.

Wanneer hierdie plan oorweeg word, moet die plaaslike bestuur oortuig wees dat die voorgestelde ontwikkeling nie nadelig sal wees vir die harmonieuze ontwikkeling van die erf en bowendien dat dit nie 'n nadelige invloed sal hê op die woongebied in die omgewing nie, veral die uitsig op buitelugwoon- en tuinarea van aangrensende eiendomme.

(f) Die plaaslike bestuur mag of sy goedkeuring verleen of weerhou, en mag na goeddunke enige sodanige voorwaardes neerlaai.

(g) Die voorsiening van noodsaaklike dienste moet tot die bevrediging van die plaaslike bestuur wees.

(h) Waar die geboue op 'n bepaalde erf op 1 Januarie 1980 bestaan het, mag die plaaslike bestuur enige van die voorwaardes wat in hierdie sub-klausule vervat is, verslap.

(i) Vir die doeleindes van hierdie sub-klausule beteken "wooneenheid" 'n stel kamers wat 'n badkamer en kombuis insluit en ontwerp is vir die bewoning van 'n enkele gesin.

Die voornoemde voorlopige skema is vir inspeksie beskikbaar in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en van die Stadsklerk van die Stadsraad van Sandton.

Waar, kragtens die bepalings van artikel 32 van voorname Ordonnansie, enige eienaar of besitter van onroerende eiendom en enige plaaslike bestuur die reg het om 'n beswaar in te dien of vertoë te rig in verband met sodanige voorlopige skeema, moet sodanige beswaar of sodanige vertoë binne vier weke vanaf die eerste publicasie van hierdie kennisgewing in die *Provinsiale Koerant* skriftelik aan die Direkteur van Plaaslike Bestuur by bogemelde adres of Privaatsak X437, Pretoria, voorgelê word.

S. W. B. BRITS,

Direkteur van Plaaslike Bestuur.

Pretoria, 4 Maart 1981.

PB: 4-9-2-116H-226

NOTICE 174 OF 1981.

POTCHEFSTROOM AMENDMENT SCHEME 35.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965), that application has been made by the owner, Jack Joseph Patlansky, Paarl-Potch (Eiendoms) Beperk, Irene Patlansky, C/o. Mr. P. L. le Roux, Dorpsbeplanningskonsultant 206, Church Street, Potchefstroom for the amendment of Potchefstroom Town-planning Scheme, 1980 by rezoning Portion 8 of Erf 164, Portion 4 of Erf 114, Remaining Extent of Portion 10 of Erf 191, Portion 14 of Erf 191, Portion 16 of Erf 191 and the Remaining Extent of Portion 15 of Erf 191, situated on Potgieter Street and River Street Potchefstroom Township from "Residential 1" with a density of "One dwelling per erf" to "Business 1" subject to certain conditions.

The amendment will be known as Potchefstroom Amendment Scheme 35. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Potchefstroom and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and the Town Clerk, P.O. Box 113, Potchefstroom, 2520 at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 4 March, 1981.

PB. 4-9-2-26H-35

NOTICE 175 OF 1981.

ALBERTON AMENDMENT SCHEME 34.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965), that application has been made by the owner, Marigo Stathoulis, C/o. Mr. F. J. Visser, 13 Somerset Street Alberante, Alberton, for the amendment of Alberton Town-planning Scheme, 1979, by rezoning Lot 699, situated on Gerrit Maritz Street and Seventh Avenue, Alberton Township, from "Residential 4" to "Business 1".

The amendment will be known as Alberton Amendment Scheme 34. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Alberton and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and the Town Clerk, P.O. Box 4, Alberton 1450, at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 4 March, 1981.

PB. 4-9-2-4H-34

KENNISGEWING 174 VAN 1981.

POTCHEFSTROOM-WYSIGINGSKEMA 35.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, Jack Joseph Patlansky, Paarl-Potch (Eiendoms) Beperk, Irene Patlansky, P/a. mnr. P. L. le Roux, Dorpsbeplanningskonsultant, Kerkstraat 206, aansoek gedoen het om Potchefstroom-dorpsbeplanningskema, 1980 te wysig deur die hersonering van Gedeelte 8 van Erf 164, Gedeelte 4 van Erf 114, Resterende Gedeelte van Gedeelte 10 van Erf 191, Gedeelte 14 van Erf 191, Gedeelte 16 van Erf 191, Resterende Gedeelte van Gedeelte 15 van Erf 191, geleë aan Potgieterstraat en Rivierstraat Corp Potchefstroom van "Residensieel 1" met 'n digtheid van "Een woonhuis per erf" tot "Besigheid 1" onderworpe aan sekere voorwaardes.

Verdere besonderhede van hierdie wysigingskema (wat Potchefstroom-wysigingskema 35 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Potchefstroom ter insae.

Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovermelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 113, Potchefstroom, 2520 skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 4 Maart 1981.

PB. 4-9-2-26H-35

KENNISGEWING 175 VAN 1981.

ALBERTON-WYSIGINGSKEMA 34.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965), bekend gemaak dat die eienaar, Marigo Stathoulis, P/a. mnr. F. J. Visser, Somersetstraat 13, Alberante, Alberton, aansoek gedoen het om Alberton-dorpsbeplanningskema, 1979, te wysig deur die hersonering van Lot 699; geleë aan Gerrit Maritzstraat en Sewendelaan, dorp Alberton, van "Residensieel 4" tot "Besigheid 1".

Verdere besonderhede van hierdie wysigingskema (wat Alberton-wysigingskema 34 genoem sal word), lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Alberton ter insae.

Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovermelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 4, Alberton, 1450 skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 4 Maart 1981.

PB. 4-9-2-4H-34

NOTICE 176 OF 1981.

JOHANNESBURG AMENDMENT SCHEME 451.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965), that application has been made by the owner, Aloe Grove Centre (Proprietary), Limited, C/o. Mr. R. L. Faccio, P.O. Box 32134, Braamfontein, for the amendment of Johannesburg Town-planning Scheme, 1979, by rezoning Lots 1919 to 1961, situated on 15th, 16th and 17th Streets and 12th Avenue, Orange Grove Township, from:

1. Lots 1919 to 1937, a part of Lot 1938, Lots 1939, 1941 to 1942: "Residential 4" and a part of Lot 1943.
2. A part of Lot 1938, Lots 1937 to 1942, a part of Lot 1943 and Lots 1958 to 1961: "Public open space".
3. A part of Lot 1949, Lots 1951, 1953, 1955, 1957: "Business 3".
4. Lots 1944, 1945, 1946, 1947, 1948: "Parking", a part of Lot 1949, 1950, a part of Lot 1951, 1952, 1954, 1956 to —
 - (1) Lots 1919, 1940: "Residential 1", a part of Lots 1941 and 1942 and Lot 1943.
 - (2) Lots 1944 to 1959: "Business 4", a part of Lots 1960 and 1961.
 - (3) A part of Lots 1960, 1961, and a part of Lots 1941 and 1942: "Proposed New Road Widening".

The amendment will be known as Johannesburg Amendment Scheme 451. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Johannesburg and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Street, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government, in writing at the above address or Private Bag X437, Pretoria and the Town Clerk, P.O. Box 1049, Johannesburg 2000 at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 4 March, 1981.

PB. 4-9-2-2H-451

NOTICE 177 OF 1981.

HALFWAY-HOUSE AND CLAYVILLE AMENDMENT SCHEME 53.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965), that application has been made by the owner, Cullinan Properties Limited, C/o. Messrs. Viljoen, Van Zyl, Gunning & Stead, P.O. Box 1889, Pretoria, for the amendment of Halfway-House and Clayville Town-planning Scheme, 1976, by rezoning of Erf 1244, situated on Premier Street and Patricia Avenue, Clayville Extension 3 Township, from "Residential 1" with a density of "One dwelling per erf" to "Business 2".

KENNISGEWING 176 VAN 1981.

JOHANNESBURG-WYSIGINGSKEMA 451.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965), bekend gemaak dat die eienaar Aloe Grove Centre (Proprietary) Limited, P/a. mn. R. L. Faccio, Posbus 32134, Braamfontein, aansoek gedoen het om Johannesburg-dorpsbeplanskema, 1979, te wysig deur die hersonering van Lotte 1919 tot 1961, geleë aan 15de-, 16de- en 17de Strate en 12de Laan, dorp Orange Grove, van:

1. Lotte 1919 tot 1937, 'n deel van Lot 1938, Lotte 1939, 1941 tot 1942 en 'n deel van Lot 1943: "Residensieel 4".
 2. 'n Deel van Lot 1938, Lotte 1937, 1942, 'n deel van Lot 1943, en Lotte 1958 tot 1961: "Openbare oopruimte".
 3. 'n Deel van Lot 1949, Lotte 1951, 1953, 1955, 1957: "Besigheid 3".
 4. Lotte 1944, 1945, 1946, 1947, 1948: 'n deel van Lot 1949, 1950, 'n deel van Lot 1951, 1952, 1954, 1956: Parkering" tot —
 - (1) Lotte 1919, 1940, 'n deel van Lotte 1941 en 1942: "Residensieel 1".
 - (2) Lotte 1944 tot 1959, 'n deel van Lotte 1960 en 1961: "Besigheid 4".
 - (3) Deel van Lotte 1960 en 1961: Deel van Lotte 1941 en 1942: "Voorgestelde Pad en Verbreeding".
- Verdere besonderhede van hierdie wysigingskema (wat Johannesburg-wysigingskema 451 genoem sal word), lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Johannesburg ter insae.
- Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovermelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 1049, Johannesburg 2000 skriftelik voorgelê word.
- S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 4 Maart 1981.
- PB. 4-9-2-2H-451

KENNISGEWING 177 VAN 1981.

HALFWAY-HOUSE EN CLAYVILLE-WYSIGINGSKEMA 53.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965), bekend gemaak dat die eienaar, Cullinan Properties Limited, P/a. mnre. Viljoen, Van Zyl, Gunning & Stead, Posbus 1889, Pretoria, aansoek gedoen het om Halfway-House en Clayville-dorpsbeplanskema, 1976, te wysig deur die hersonering van Erf 1244, geleë aan Premierstraat en Patriciaalaan, dorp Clayville Uitbreiding 3, van "Residensieel 1" met 'n digtheid van "Een woonhuis per erf" tot "Besigheid 2".

The amendment will be known as Halfway-House and Clayville Amendment Scheme 53. Further particulars of the scheme are open for inspection at the office of the Secretary of the Transvaal Board of the Development of Peri-Urban Areas and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and The Secretary of the Transvaal Board for the Development of Peri-Urban Areas, P.O. Box 1341, Pretoria, 0001 at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 4 March, 1981.

PB. 4-9-2-149-53

Verdere besonderhede van hierdie wysigingskema (wat Halfway-House en Clayville-wysigingskema 53, genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h.v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Sekretaris van die Transvalse Raad vir die Ontwikkeling van Buitestedelike Gebiede ter insae.

Enige beswaar of vertoe teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovermelde adres of Privaatsak X437, Pretoria en die Sekretaris van die Transvalse Raad vir die Ontwikkeling van Buitestedelike Gebiede, Posbus 1341, Pretoria 0001 skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 4 Maart, 1981.

PB. 4-9-2-149-53

NOTICE 178 OF 1981.

SANDTON AMENDMENT SCHEME 379.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, Harry Shapiro, C/o. Mr. J. H. Smith, P.O. Box 78019, Sandton for the amendment of Sandton Town-planning Scheme, 1980, by rezoning Erf 358, situated on Edward Rubenstein Drive and Marion Street, Sandown Extension 24 Townsh p from "Residential 1" with a density of "One dwelling per 4 000 m²" to "Residential 1" with a density of "One dwelling per 2 000 m²".

The amendment will be known as Sandton Amendment Scheme 379. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Sandton and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and the Town Clerk, P.O. Box 78001, Sandton, 2146, at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.
Pretoria, 4 March, 1981.

PB. 4-9-2-116H-379

NOTICE 179 OF 1981.

PRETORIA AMENDMENT SCHEME 711.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, Jossbro Investments (Proprietary) Limited, C/o. Mr. M. P. Dix, 458 Monica Road, Lynnwood, Pretoria for the amendment of Pretoria Town-planning Scheme, 1974, by rezoning of Remaining Extent and Portion 1 of Erf 365, situated on Proes Street, Arcadia Township from "General Residential (1)" with a density of "One

KENNISGEWING 178 VAN 1981.

SANDTON-WYSIGINGSKEMA 379.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, Harry Shapiro, P/a. mnr. J. H. Smith, Posbus 78019, Sandton, aansoek gedoen het om Sandton-dorpsbeplanningskema, 1980, te wysig deur die hersonering van Erf 358, geleë aan Edward Rubensteinrylaan en Marionstraat, dorp Sandown Uitbreiding 24 van "Residensieel 1" met 'n digtheid van "Een woonhuis per 4 000 m²" tot "Residensieel 1" met 'n digtheid van "Een woonhuis per 2 000 m²".

Verdere besonderhede van hierdie wysigingskema (wat Sandton-wysigingskema 379 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h.v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Sandton ter insae.

Enige beswaar of vertoe teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovermelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 78001, Sandton, 2146, skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.

Pretoria, 4 Maart 1981.

PB. 4-9-2-116H-379

KENNISGEWING 179 VAN 1981.

PRETORIA-WYSIGINGSKEMA 711.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, Jossbro Investments (Proprietary) Limited, P/a. mnr. M. P. Dix, Monicaweg 458, Lynnwood, Pretoria, aansoek gedoen het om Pretoria-dorpsbeplanningskema, 1974, te wysig deur die hersonering van Resterende Gedeelte en Gedeelte 1 van Erf 365, geleë aan Proesstraat, dorp Arcadia van "Algemene Woon (1)" met 'n digtheid

dwelling per 1 000 m²" to "Special" Use Zone XVI for General Residential purposes and a parking garage and the storage and parking of motor vehicles subject to certain conditions.

The amendment will be known as Pretoria Amendment Scheme 711. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Pretoria and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria and the Town Clerk, P.O. Box 440, Pretoria, 0001 at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.

Pretoria, 4 March, 1981.

PB. 4-9-2-3H-711

NOTICE 180 OF 1980.

PRETORIA AMENDMENT SCHEME 712.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owners, Simon Ruben Lan and Julius Joseph Lan, 50 Weavind Street, Colbyn for the amendment of Pretoria Town-planning Scheme, 1974, by rezoning Erf 334, situated on Weavind Street and Manning Street, Colbyn Township from "Special Residential" with a density of "One dwelling per erf" to "Special" for the purposes of duplex residential and/or for the purposes of dwelling units attached or detached, subject to certain conditions.

The amendment will be known as Pretoria Amendment Scheme 712. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Pretoria and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objections or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria and the Town Clerk, P.O. Box 440, Pretoria, 0001 at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,
Director of Local Government.

Pretoria, 4 March, 1981.

PB. 4-9-2-3H-712

NOTICE 181 OF 1981.

MIDDELBURG AMENDMENT SCHEME 42.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965) that application has been made by the owner, Hendrik Erwee Botha, C/o. Messrs. Rosmarin, Els & Taylor, P.O. Box 32004, Braamfontein for the amendment of Middelburg Town-planning Scheme, 1974,

van "Een woonhuis per 1 000 m²" tot "Spesiaal" Gebruiksone XVI vir algemene woondoeleindes, 'n parkeergarage, en die stoor en parkering van motorvoertuie onderworpe aan sekere voorwaardes.

Verdere besonderhede van hierdie wysigingskema (wat Pretoria-wysigingskema 712 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Pretoria ter insae.

Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovermelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 440, Pretoria, 0001 skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 4 Maart 1981.

PB. 4-9-2-3H-711

KENNISGEWING 180 VAN 1981.

PRETORIA-WYSIGINGSKEMA 712.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaars, Simon Ruben Lan en Julius Joseph Lan, Weavindstraat 50, Colbyn, aansoek gedoen het om Pretoria-dorpsbeplanningskema, 1974, te wysig deur die hersonering van Erf 334, geleë aan Weavindstraat en Manningstraat, dorp Colbyn van "Spesiale Woon" met 'n digtheid van "Een woonhuis per erf" tot "Spesiaal" vir die doeleindes van dupleks-woon en/of vir die doeleindes van wooneenhede, aanmekaargeskakel of losstaande, onderworpe aan sekere voorwaardes.

Verdere besonderhede van hierdie wysigingskema (wat Pretoria-wysigingskema 712 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriusstraat, Pretoria en in die kantoor van die Stadsklerk van Pretoria ter insae.

Enige beswaar of vertoë teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovermelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 440, Pretoria, 0001 skriftelik voorgelê word.

S. W. B. BRITS,
Direkteur van Plaaslike Bestuur.
Pretoria, 4 Maart 1981.

PB. 4-9-2-3H-712

KENNISGEWING 181 VAN 1981.

MIDDELBURG-WYSIGINGSKEMA 42.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar, Hendrik Erwee Botha, P/a. mnre. Rosmarin, Els & Taylor, Posbus 32004, Braamfontein aansoek gedoen het om Middelburg-dorpsbeplanningskema, 1974, te wysig deur die hersonering van Erf 842, geleë aan Vil-

by rezoning Erf 842, situated on Viljoen Street, Middelburg Township from "Special Residential" with a density of "One dwelling per 1 500 m²" to "General Residential 2" with a density of "One dwelling per 1 500 m²".

The amendment will be known as Middelburg Amendment Scheme 42. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Middelburg and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria and the Town Clerk, P.O. Box 14, Middelburg, 1050 at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,

Director of Local Government.

Pretoria, 4 March, 1981.

PB. 4-9-2-21H-42

NOTICE 182 OF 1981.

KLERKSDORP AMENDMENT SCHEME 27.

It is hereby notified in terms of section 46 of the Town-planning and Townships Ordinance, 1965 (Ordinance 25 of 1965), that application has been made by the owner, Dordor Investments (Proprietary) Limited C/o. Mr. A. J. P. de Wet and Partners, P.O. Box 1504, Klerksdorp for the amendment of Klerksdorp Town-planning Scheme, 1980 by rezoning of Erven 489 and 490 situated on Kock Street and Commissioner Street, Klerksdorp Township from "Municipal" to "Business 1".

The amendment will be known as Klerksdorp Amendment Scheme 27. Further particulars of the scheme are open for inspection at the office of the Town Clerk, Klerksdorp and at the office of the Director of Local Government, 11th Floor, Merino Building, cor. Bosman and Pretorius Streets, Pretoria.

Any objection or representations in regard to the application shall be submitted to the Director of Local Government in writing at the above address or Private Bag X437, Pretoria, and the Town Clerk, P.O. Box 99, Klerksdorp, 2570 at any time within a period of 4 weeks from the date of this notice.

S. W. B. BRITS,

Director of Local Government.

Pretoria, 4 March, 1981.

PB. 4-9-2-17H-27

NOTICE 183 OF 1981.

PROPOSED EXTENSION OF BOUNDARIES OF HENDRINA EXTENSION 1.

It is hereby notified in terms of section 82(4) of the Town-planning and Townships Ordinance, 1965, that application has been made by Joy Manufacturing Company (Afrika) Pty Limited for permission to extend the boundaries of Hendrina Extension 1 township to include Portion 13 (a portion of Portion 6) of the farm Grasfontein No. 199-I.S. district Hendrina.

The relevant portion is situated east of and abuts Road 1398 and north of and abuts Hendrina Extension 1 and

joenstraat, dorp Middelburg van "Spesiale Woon" met 'n digtheid van "Een woonhuis per 1 500 m²" tot "Algemene Woon 2" met 'n digtheid van "Een woonhuis per 1 500 m²".

Verdere besonderhede van hierdie wysigingskema (wat Middelburg-wysigingskema 42 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriussstraat, Pretoria en in die kantoor van die Stadsklerk van Middelburg ter insae.

Enige beswaar of vertoe teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovemelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 14, Middelburg, 1050 skriftelik voorgelê word.

S. W. B. BRITS,

Direkteur van Plaaslike Bestuur.

Pretoria, 4 Maart 1981.

PB. 4-9-2-21H-42

KENNISGEWING 182 VAN 1981.

KLERKSDORP-WYSIGINGSKEMA 27.

Hierby word ooreenkomsdig die bepalings van artikel 46 van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 (Ordonnansie 25 van 1965) bekend gemaak dat die eienaar Dordor Investments (Proprietary) Limited P/a. mnr. A. J. P. de Wet en Vennoté, Posbus 1504, Klerksdorp dorpsbeplanningskema, 1980 te wysig deur die hersonering van Erve 489 en 490, geleë aan Kockstraat en Commissionerstraat, Klerksdorp van "Munisipaal" tot "Besigheid 1".

Verdere besonderhede van hierdie wysigingskema (wat Klerksdorp-wysigingskema 27 genoem sal word) lê in die kantoor van die Direkteur van Plaaslike Bestuur, 11de Vloer, Merino Gebou, h/v. Bosman- en Pretoriussstraat, Pretoria en in die kantoor van die Stadsklerk van Klerksdorp ter insae.

Enige beswaar of vertoe teen die aansoek kan te eniger tyd binne 'n tydperk van 4 weke vanaf die datum van hierdie kennisgewing aan die Direkteur van Plaaslike Bestuur by bovemelde adres of Privaatsak X437, Pretoria en die Stadsklerk, Posbus 99, Klerksdorp, 2570 skriftelik voorgelê word.

S. W. B. BRITS,

Direkteur van Plaaslike Bestuur.

Pretoria, 4 Maart 1981.

PB. 4-9-2-17H-27

KENNISGEWING 183 VAN 1981.

VOORGESTELDE UITBREIDING VAN GRENSE DORP HENDRINA UITBREIDING 1.

Ingevolge artikel 82(4) van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965 word hierby bekend gemaak dat Joy Manufacturing Company (Afrika) (Edms) Beperk aansoek gedoen het om die uitbreiding van die grense van dorp Hendrina Uitbreidings 1 om Gedeelte 13 ('n gedeelte van Gedeelte 6) van die plaas Grasfontein, No. 199-I.S., distrik Hendrina te omyat.

Die betrokke gedeelte is geleë oos van en grens aan Pad 1398 en noord van en grens aan Hendrina Uitbrei-

is to be used for Industrial, Warehouse and Office purposes.

The application together with the relevant plans, documents and information, is open for inspection at the office of the Director, Room B206A, 2nd Floor, Block B, Provincial Building, Pretorius Street, Pretoria, for a period of four weeks from the date hereof.

Any person who wishes to object to the granting of the application or who is desirous of being heard or of making representations in the matter, shall communicate in writing with the Director of Local Government. Such communication shall be received by the Director not later than four weeks from the date of the first publication of this notice in the *Provincial Gazette*.

All objections must be lodged in duplicate, and addressed to the Director of Local Government, Private Bag X437, Pretoria, 0001.

E. UYS,
Director of Local Government.
Pretoria, 4 March, 1981.

ding 1 en sal vir Nywerheid, Pakhuis en Kantoor doelendes gebruik word.

Die aansoek en die betrokke planne, dokumente en inligting lê ter insae by die kantoor van die Direkteur, Kamer B206A, 2de Vloer, Blok B, Provinciale Gebou, Pretoriussstraat, Pretoria, vir 'n tydperk van vier weke na datum hiervan.

Iedereen wat beswaar wil maak teen die toestaan van die aansoek of wat begerig is om in die saak gehoor te word of vertoe te rig, moet die Direkteur skriftelik in kennis stel. Sodanige kennisgewing moet nie later nie as vier weke vanaf die datum van die eerste publikasie van hierdie kennisgewing in die *Provinciale Koerant* deur die Direkteur van Plaaslike Bestuur ontvang word.

Alle besware moet in duplo ingedien word en gerig word aan die Direkteur, Departement van Plaaslike Bestuur, Privaatsak X437, Pretoria, 0001.

E. UYS,
Direkteur van Plaaslike Bestuur.
Pretoria, 4 Maart 1981.

TENDERS

N.B. — Tenders previously published and where the closing dates have not yet passed, have not been repeated in this notice. Tenders are normally published 3-5 weeks before the closing date.

TRANSVAAL PROVINCIAL ADMINISTRATION.**TENDERS.**

Tenders are invited for the following services / supplies / sales. (Unless otherwise indicated in the description tenders are for supplies): —

TENDERS

L.W. — Tenders wat voorheen gepubliseer is en waarvan die sluitingsdatum nog nie verstreke is nie, word nie in hierdie kennisgewing herhaal nie. Tenders word normaalweg 3-5 weke voor die sluitingsdatum gepubliseer.

TRANSVAALSE PROVINSIALE ADMINISTRASIE.**TENDERS.**

Tenders vir die volgende dienste/voorrade/verkope word ingewag. (Tensy dit in die uiteensetting anders aangegee word, word tenders vir voorrade bedoel): —

Tender No.	Description of Service Beskrywing van Diens	Closing Date Sluitingsdatum
R.F.T. 18/81P	Props for 15 m steel shuttering for bridges / Stutte vir 15 m-staalbekisting vir brûe	03/04/1981
T.E.D. 1A/81	Stationery and school requisites / Skryfbehoeftes en skoolbenodigdhede	24/04/1981
T.O.D.		
W.F.T.B. 92/81	Barberton Museum: Erection / Barberton-museum: Oprigting. Item 4019/78	27/03/1981
W.F.T.B. 93/81	Bryanston Primary School, Johannesburg: Erection of grades-rooms, class-rooms and laboratory / Oprigting van gradekamers, klaskamers en laboratorium. Item 1089/80	27/03/1981
W.F.T.B. 94/81	Laerskool Dagbreek, Carletonville: Erection of grades-rooms, class-rooms and laboratory / Oprigting van gradekamers, klaskamers en laboratorium. Item 1164/80	27/03/1981
W.F.T.B. 95/81	Discovery Primary School, Roodepoort: Erection of grades-rooms, class-rooms and laboratory / Oprigting van gradekamers, klaskamers en laboratorium. Item 1114/80	27/03/1981
W.F.T.B. 96/81	H. F. Verwoerd Hospital, Pretoria: Steam and condensate reticulation/ H. F. Verwoerd-hospitaal, Pretoria: Stoom- en kondensaatretilikulasie. Item 2004/77	27/03/1981
W.F.T.B. 97/81	H. F. Verwoerd Hospital, Pretoria: Erection of special service block / H. F. Verwoerd-hospitaal, Pretoria: Oprigting van spesiale diensteblok. Item 2099/75	10/04/1981
W.F.T.B. 98/81	Hoërskool Lichtenburg: Central heating installation / Sentrale verwarmingsinstallasie. Item 1703/78	27/03/1981
W.F.T.B. 99/81	Middelburg Hospital: Erection of flats for medical staff / Middelburg-hospitaal: Oprigting van woonstelle vir mediese personeel. Item 2065/74	27/03/1981
W.F.T.B. 100/81	Laerskool Noordval, Orkney: Erection of grades-rooms, class-rooms and laboratory / Oprigting van gradekamers, klaskamers en laboratorium. Item 1168/80	27/03/1981
W.F.T.B. 101/81	Baragwanath Hospital, Nurses' Residence: Nurses' call system / Baragwanath-hospitaal, Verpleegsterstehuis: Verpleegstersroepstelsel. Item 2080/71	27/03/1981
W.F.T.B. 102/87	Witbank Hospital: Erection of a residence for maintenance officer / Witbankse Hospitaal: Oprigting van 'n woning vir onderhoudsbeampte. Item 4029/70	27/03/1981

IMPORTANT NOTES.

1. The relative tender documents including the Administration's official tender forms, are obtainable on application from the relative address indicated below. Such documents and any tender/contract conditions not embodied in the tender documents are also available for inspection at the said address:

Tender Ref.	Postal address Pretoria	Office in New Provincial Building, Pretoria			
		Room No.	Block	Floor	Phone Pretoria
HA 1 & HA 2	Director of Hospital Services, Private Bag X221.	A740	A	7	28-9260
HB	Director of Hospital Services, Private Bag X221.	A728	A	7	28-9205
HC	Director of Hospital Services, Private Bag X221.	A728	A	7	28-9206
HD	Director of Hospital Services, Private Bag X221.	A730	A	7	28-0354
PFT	Provincial Secretary (Purchases and Supplies), Private Bag X64.	A1119	A	11	28-0924
RFT	Director, Transvaal Roads Department, Private Bag X197.	D307	D	3	28-0530
TED	Director, Transvaal Education Department, Private Bag X76.	A489 A490	A	4	28-9231 28-9437
WFT	Director, Transvaal Department of Works, Private Bag X228.	C119	C	1	28-9254
WFTB	Director, Transvaal Department of Works, Private Bag X228.	E105	E	1	28-0306

2. The Administration is not bound to accept the lowest or any tender and reserves the right to accept a portion of a tender.

3. In the case of each W.F.T.B. tender the tenderer must pay a deposit of R4 before he will be supplied with the tender documents. Such deposit must be in the form of cash, a bank initialised cheque, or a department standing deposit receipt (R10). The said deposit will be refunded if a bona fide tender is received from the tenderer or if the tender documents including plans, specifications and bills of quantities are returned by the tenderer within 14 days after the closing date of the tender to the relative address shown in note 1 above.

4. All tenders must be submitted on the Administration's official tender forms.

5. Each tender must be submitted in a separate sealed envelope addressed to the Chairman, Transvaal Provincial Tender Board, P.O. Box 1040, Pretoria, and must be clearly superscribed to show the tenderer's name and address, as well as the number, description and closing date of the tender. Tenders must be in the hands of the Chairman by 11h00 on the closing date indicated above.

6. If tenders are delivered by hand, they must be deposited in the Formal Tender Box at the Enquiry Office in the foyer of the New Provincial Building at the Pretorius Street main entrance (near Bosman Street corner), Pretoria, by 11h00 on the closing date.

J. H. Conradie, Chairman, Transvaal Provincial Tender Board, Pretoria, 18 February, 1981.

BELANGRIKE OPMERKINGS.

1. Die betrokke tenderdokumente, met inbegrip van die amptelike tendervorms van die Administrasie, is op aanvraag by die onderstaande adresse verkrybaar. Sodanige dokumente asmede enige tender / kontrakvoorraad wat nie in die tenderdokumente opgeneem is nie, is ook by die genoemde adres vir inspeksie verkrybaar:

Tender verwy sing	Posadres te Pretoria	Kantoor in Nuwe Provinciale Gebou, Pretoria.			
		Kamer No.	Blok	Verdieping	Foon Pretoria
HA 1 & HA 2	Direkteur van Hospitaaldienste, Privaatsak X221.	A740	A	7	28-9260
HB	Direkteur van Hospitaaldienste, Privaatsak X221.	A728	A	7	28-9205
HC	Direkteur van Hospitaaldienste, Privaatsak X221.	A728	A	7	28-9206
HD	Direkteur van Hospitaaldienste, Privaatsak X221.	A730	A	7	28-0354
PFT	Provinsiale Sekretaris (Aankope en Voorrade), Privaatsak X64.	A1119	A	11	28-0924
RFT	Direkteur, Transvaalse Paaiededepartement, Privaatsak X197.	D307	D	3	28-0530
TOD	Direkteur, Transvaalse Onderwysdepartement, Privaatsak X76.	A489 A490	A	4	28-9231 28-9437
WFT	Direkteur, Transvaalse Werkedepartement, Privaatsak X228.	C119	C	1	28-9254
WFTB	Direkteur, Transvaalse Werkedepartement, Privaatsak X228.	E105	E	1	28-0306

2. Die Administrasie is nie daartoe verplig om die laagste of enige tender aan te neem nie en behou hom die reg voor om 'n gedeelte van 'n tender aan te neem.

3. In die geval van iedere W.F.T.B.-tender moet die tenderaar 'n deposito van R4 stort alvorens hy van die tenderdokumente voorsien sal word. Sodanige deposito moet in kontantgeld wees, 'n tjeuk deur die bank geparafeer of 'n departementeleg oder kwitansie (R10). Genoemde depositobedrag sal terugbetaal word as 'n bona fide-inskrywing van die tenderaar ontvang word of as die tenderdokumente, met inbegrip van planne, spesifikasies en hoeveelheidsllys, binne 14 dae na die sluitingsdatum van die tenderaar teruggestuur word na die betrokke adres in opmerking 1 hierbo aangetoon.

4. Alle tenders moet op die amptelike tendervorm van die Administrasie voorgelê word.

5. Iedere inskrywing moet in 'n afsonderlike koevert ingedien word, geadresseer aan die Voorsitter, Die Transvaalse Provinciale Tenderraad, Posbus 1040, Pretoria, en moet duidelik van die opskrif voorsien wees ten einde die tenderaar se naam en adres aan te toon, asook die nommer, beskrywing en sluitingsdatum van die tender. Inskrywings moet teen 11h00 op die sluitingsdatum hierbo aangetoon, in die Voorsitter se hande wees.

6. Indien inskrywings per hand ingedien word, moet hulle teen 11h00 op die sluitingsdatum in die Formele Tenderbus geplaas wees by die navraagkantoor in die voorportaal van die nuwe Provinciale Gebou by die hoofingang aan Pretoriusstraat se kant (naby die hoek van Bosmanstraat), Pretoria.

J. H. Conradie, Voorsitter, Transvaalse Provinciale Tenderraad, Pretoria, 18 Februarie 1981.

Notices By Local Authorities

Plaaslike Bestuurskennisgewings

TOWN COUNCIL OF BOKSBURG.

PROCLAMATION OF ROAD WIDENINGS
OVER PORTIONS OF THE FARM KLIPFONTEIN 83 - I.R. AND RAVENSWOOD AGRICULTURAL HOLDINGS.

Notice is hereby given in terms of the Local Authorities Roads Ordinance (No. 44 of 1904), as amended, that the Town Council of Boksburg, has petitioned the honourable, the Administrator, to proclaim as public road, the road widenings described in the schedule appended hereto.

A copy of the petition can be inspected at Room No. 219, Second Floor, Civic Centre, Boksburg, during office hours, from the date hereof until the 13 April, 1981.

Objections, if any to the proposed proclamation of the road widenings must be lodged in writing and in duplicate, with the Administrator of Transvaal, Private Bag X437, Pretoria and the Town Clerk of Boksburg, on or before the 13 April, 1981.

LEON FERREIRA,
Town Clerk.

Civic Centre,
Boksburg.
25 February, 1981.
Notice No. 6/81.

SCHEDULE.

PROCLAMATION FOR ROAD WIDENINGS
OVER PORTIONS OF THE FARM KLIPFONTEIN 83 - I.R. AND RAVENSWOOD AGRICULTURAL HOLDINGS SETTLEMENT.

It is proposed to widen Edgar Road as follows:—

From Rietfontein Road, on the North side over Portions 41 and 165 Klipfontein and Holdings 9, 10 and 11 Ravenswood by 4,26 metres narrowing down to zero, over Holding 11.

On the South side, over Holdings 17 and 18 by widths of 6,64 metres to 10,54 metres and then narrowing down to zero over Portions 35, 36 and 63 Klipfontein. On the North side over Portion 21 Klipfontein from zero to 10,54 metres, up to Trichardts Road, where it is splayed 10 metres.

These proposed Road Widenings are more fully described on a plan signed by Surveyor R. E. Johnston lying for inspection also in Room 219, Second Floor, Civic Centre, Boksburg.

STADSRAAD VAN BOKSBURG.

PROKLAMERING VAN PADVERBREDINGS
OOR GEDEELTES VAN DIE PLAAS KLIPFONTEIN 83 - I.R. EN RAVENSWOOD LANDBOUHOEWES.

Kennis geskied hiermee ingevolge die bepalings van die "Local Authorities Roads Ordinance, (No. 44 of 1904)", soos gewysig, dat die Stadsraad van Boksburg, 'n versoekskrif aan Sy Edele die Administrateur gerig het om die padverbredings omskrywe in bygaande bylae, as openbare pad te proklameer.

'n Afskrif van die versoekskrif lê gedurende kantoortuur vanaf datum hiervan tot en met 13 April 1981 ter insae in Kamer 219, Tweede Vloer, Burgersentrum, Boksburg.

Besware teen die voorgestelde proklamasie van die padverbredings indien enige, moet skriftelik in tweevoud, by Sy Edele die Administrateur van Transvaal, Privaatsak X437, Pretoria en die Stadsklerk van Boksburg, voor of op 13 April 1981 ingediend word.

LEON FERREIRA,
Stadsklerk.

Burgersentrum,
Boksburg.
25 Februarie 1981.
Kennisgewing No. 6/81.

BYLAE.

PROKLAMERING VAN PADVERBREDINGS
OOR GEDEELTES VAN DIE PLAAS KLIPFONTEIN 83 - I.R. EN RAVENSWOOD LANDBOUHOEWES.

Dit word beoog om Edgarweg soos volg te verbreed:—

Vanaf Rietfonteinweg aan die Noordekant oor Gedeeltes 41 en 165 van Klipfontein en Hoeve 9, 10 en 11 Ravenswood met 4,26 meter om geleidelik tot nul oor Hoeve 11 te versmal.

Aan die Suidekant, oor Hoeves 17 en 18 met breedtes van 6,64 meter tot 10,54 meter en dan tot nul te versmal oor Gedeeltes 35, 36 en 63 van Klipfontein. Aan die Noordekant oor Gedeelte 21 van Klipfontein van nul tot 10,54 meter by Trichardtsweg, waar dit met 10 meter afgeskuins word.

Hierdie voorgestelde padverbredings is meer volledig aangebeeld op 'n plan wat deur Landmeter R. E. Johnston opgestel is en in Kamer 219, Tweede Vloer, Burgersentrum, Boksburg ter insae lê.

146—25—4—11

CITY OF JOHANNESBURG.

PROPOSED AMENDMENT TO JOHANNESBURG TOWN PLANNING SCHEME 1979
(AMENDMENT SCHEME 438).

The City Council of Johannesburg has prepared a draft Town Planning Scheme, to be known as Johannesburg Amendment Scheme 438.

This scheme will be an amendment scheme and contains the following proposal:

To rezone the closed portion of Du Toit Street between Rif and Schoeman Streets, and the closed portion of Kamp Street extending eastwards from Marais Road in the township of Paarlshoop from Existing Public Road (Use Zone XXXI) to Residential 4 (Use Zone IV).

Particulars of this scheme are open for inspection at Room 703, Seventh Floor, Civic Centre, Braamfontein, Johannesburg, for a period of four weeks from the date of the first publication of this notice, which is 25 February, 1981.

Any objection or representation in connection with this scheme shall be submitted in writing to the Town Clerk, P.O. Box 1049, Johannesburg, within a period of four weeks from the above-mentioned date.

S. D. MARSHALL,
City Secretary.

Civic Centre,
Braamfontein,
Johannesburg.
25 February, 1981.

STAD JOHANNESBURG.

VOORGESTELDE WYSIGING VAN DIE JOHANNESBURGSE DORPSBEPLANNINGSKEMA 1979 (WYSIGINGSKEMA 438)

Die Stadsraad van Johannesburg het 'n konsep-dorpsbeplanningskema opgestel wat bekend sal staan as die Johannesburgse Wysigingskema 438.

Die skema sal 'n wigsigingskema wees en beval die volgende voorstel:

Om die gesluite gedeelte van Du Toitstraat, tussen Rif- en Schoemanstraat, en die gesluite gedeelte van Kampstraat wat ooswaarts van Maraisweg strek, in die dorp Paarlshoop van Bestaande Openbare Pad (Gebruiksone XXXI) na Residensieel 4 (Gebruiksone IV) te hersoneer.

Besonderhede van hierdie skema lê vier weke lank vanaf die datum van die eerste publikasie van hierdie kennisgewing, naamlik 25 Februarie 1981, in Kamer 703, Sewende Verdieping, Burgersentrum, Braamfontein, Johannesburg, ter insae.

Enige beswaar of vertoe in verband met hierdie skema moet binne 'n tydperk van vier weke vanaf bovenoemde datum skriftelik by die Stadsklerk, Posbus 1049, Johannesburg, ingediend word.

S. D. MARSHALL,
Stadssekretaris.

Burgersentrum,
Braamfontein,
Johannesburg.
25 Februarie 1981.

151—25—4

CITY COUNCIL OF PRETORIA.

PROPOSED AMENDMENT TO THE PRETORIA TOWN-PLANNING SCHEME, 1974:
TOWN-PLANNING AMENDMENT SCHEME 565.

The City Council of Pretoria has prepared a draft amendment to the Pretoria Town-planning Scheme, 1974, to be known as Town-planning Scheme 565.

This draft scheme contains the following proposal:

The rezoning of Erf 282, Meyerspark, from "Municipal" to "Special Residential" with a density of "One dwelling per erf".

The property is registered in the name of the City Council of Pretoria.

Particulars of this scheme are open for inspection at Rooms 603W and 362W, Munitoria, Van der Walt Street, Pretoria, for a period of four weeks from the date of the first publication of this notice, which is 25 February, 1981.

The Council will consider whether or not the scheme should be adopted.

Any owner or occupier of immovable property within the area of the Pretoria Town-planning Scheme, 1974, or within two kilometres of the boundary thereof, has the right to object to the scheme or to make representations in respect thereof, and, if he wishes to do so, he shall, within four weeks of the first publication of this notice, which is 25 February, 1981, inform the Town Clerk, P.O. Box 440, Pretoria, 0001, in writing of such objection or representation and shall state whether or not he wishes to be heard by the local authority.

P. DELPORT,
Town Clerk.

25 February, 1981.
Notice No. 70/1981.

STADSRAAD VAN PRETORIA.

VOORGESTELDE WYSIGING VAN DIE PRETORIA-DORPSBEPLANNINGSKEMA, 1974: DORPSBEPLANNINGSWYSIGING- SKEMA 565.

Die Stadsraad van Pretoria het 'n ontwerp-wysiging van die Pretoria-dorpsbeplanningskema, 1974, opgestel wat bekend sal staan as Dorpsbeplanningwysigingskema 565.

Hierdie ontwerp-skema bevat die volgende voorstel:

Die hersonering van Erf 282, Meyerspark, van "Munisipaal" tot "spesiale Woon" met 'n digitheid van "een woonhuis per erf".

Die eiendom/me is op naam van die Stadsraad van Pretoria geregistreer.

Besonderhede van hierdie skema lê ter insae in Kamers 603W en 362W, Munitoria, Van der Waltstraat, Pretoria, vir 'n tydperk van vier weke van die datum van die eerste publikasie van hierdie kennisgewing af, naamlik 25 Februarie 1981.

Die Raad sal die skema oorweeg en besluit of dit aangeneem moet word.

Enige eienaar of okkuperder van vaste eiendom binne die gebied van die Pretoria-dorpsbeplanningskema, 1974, of binne twee kilometer van die grens daarvan, het die reg om teen die skema beswaar te maak of om vertoe ten opsigte daarvan te rig en, indien hy dit wil doen, moet hy die Stadsklerk, Posbus 440, Pretoria, 0001, binne vier weke van die eerste publikasie van hierdie kennisgewing, naamlik 25 Februarie 1981, skriftelik van sodanige beswaar of vertoe in kennis stel en vermeld of hy deur die plaaslike bestuur gehoor wil word al dan nie.

P. DELPORT,
Stadsklerk.

25 Februarie 1981.
Kennisgewing No. 70/1981.

157-25-4

VILLAGE COUNCIL OF TRICHARDT.

LOCAL AUTHORITY OF TRICHARDT.

SUPPLEMENTARY VALUATION ROLL FOR THE FINANCIAL YEAR 1979/1982.

Notice is hereby given in terms of section 16(4)(a) of the Local Authorities Rating Ordinance, 1977 (Ordinance 11 of 1977), that the supplementary valuation roll for the financial years 1979/1982 of all rateable property within the

municipality has been certified and signed by the chairman of the valuation board and has been therefore become fixed and binding upon all persons concerned as contemplated in section 16(3) of the Ordinance.

However, attention is directed to section 17 or 38 of the said Ordinance, which provide as follows:

"Right of appeal against decision of valuation board.

17.(1) An objector who has appeared or has been represented before a valuation board, including an objector who has lodged or presented a reply contemplated in section 15(4), may appeal against the decision of such board in respect of which he is an objector within thirty days from the date of the publication in the Provincial Gazette of the notice referred to in section 16(4)(a) or, where the provisions of section 16(5) are applicable, within twenty-one days after the day on which the reasons referred to therein, were forwarded to such objector, by lodging with the secretary of such board a notice of appeal in the manner and in accordance with the procedure prescribed and such secretary shall forward forthwith a copy of such notice of appeal to the valuer and to the local authority concerned.

(2) A local authority which is not an objector may appeal against any decision of a valuation board in the manner contemplated in subsection (1) and any other person who is not an objector but who is directly affected by a decision of a valuation board may, in like manner, appeal against such decision."

A notice of appeal form may be obtained from the secretary of the valuation board.

M. J. VAN DER MERWE,
Secretary, Valuation Board.

Village Council,
Trichardt,
P.O. Box 52,
Trichardt.
2300.
25 Februarie 1981.

DORPSRAAD VAN TRICHARDT.

PLAASLIKE BESTUUR VAN TRICHARDT.

AANVULLENDE WAARDERINGSLYS VIR DIE BOEKJAAR 1979/1982.

Kennis word hierby ingevolge artikel 16(4)(a) van die Ordonnansie op Eiendomsbelasting van Plaaslike Bestuur, 1977 (Ordonnansie 11 van 1977), gegee dat die aanvullende waarderingslys vir die boekjare 1979/1982 van alle belasbare eiendom binne die munisipaliteit deur die Voorzitter van die waarderingsraad gesertifiseer en geteken is en gevoldig, finaal en bindend geword het op alle betrokke persone soos in artikel 16(3) van daardie Ordonnansie beoog.

Die aandag word egter gevestig op artikel 17 of 38 van die gemelde Ordonnansie wat soos volg bepaal:

"Reg van appèl teen beslissing van waarderingsraad.

17.(1) 'n Beswaarmaker wat voor 'n waarderingsraad verskyn het of verteenwoordig was, met ingegrif van 'n beswaarmaker wat 'n antwoord soos in artikel 15(4) beoog, ingedien of voorgelê het, kan teen die beslissing van sodanige raad ten opsigte waarvan hy 'n beswaarmaker is, binne dertig dae vanaf datum van die publikasie in die Provinciale Koerant van die kennisgewing in artikel 16(4)(a) genoem, of, waar die bepalings van artikel 16(5) van toepassing is, binne een-en-twintig dae na die dag waarop die redes daarin genoem, aan sodanige beswaarmaker gestuur is,

appèl aanteken deur by die Sekretaris van sodanige raad 'n kennisgewing van appèl op die wyse soos voorgeskryf en in ooreenstemming met die prosedure soos voorgeskryf in te dien en sodanige Sekretaris stuur onverwyd 'n afskrif van sodanige kennisgewing van appèl aan die waardeerde en aan die betrokke Plaaslike Bestuur.

(2) 'n Plaaslike Bestuur wat nie 'n beswaarmaker is nie, kan teen enige beslissing van 'n waarderingsraad appèl aanteken op die wyse van subartikel (1) beoog en enige ander persoon wat nie 'n beswaarmaker is nie, maar wat regstreeks deur 'n beslissing van 'n waarderingsraad geraak word, kan op dergelyke wyse, teen sodanige beslissing appèl aanteken."

'n Vorm vir kennisgewing van appèl kan van die Sekretaris van die waarderingsraad verkry word.

M. J. VAN DER MERWE,
Sekretaris: Waarderingsraad.

Dorpsraad van Trichardt,
Posbus 52,
Trichardt.
2300.
25 Februarie 1981.

164-25-4

TOWN COUNCIL OF BRAKPAN.

AMENDMENT TO THE FIRE DEPARTMENT BY-LAWS AND DETERMINATION OF CHARGES

1. Notice is hereby given in terms of section 96 of the Local Government Ordinance, 17 of 1939, that the Council proposes to amend the Fire Department By-laws published under Administrator's Notice 877 of 8 October, 1952, as amended, in order to revoke the Ambulance Tariff.

2. Notice is hereby given in terms of section 80B(3) of the Local Government Ordinance, 17 of 1939, that the Council has by special resolution determined a new Ambulance Tariff with effect from 1 February, 1981. The determination differs from the tariff contained in the by-laws mainly in the increase thereof in order to defray expenses.

Particulars of the proposed amendment and determination will be open for inspection at Room 12, Town Hall Buildings, Brakpan for a period of fourteen days from 4 March, 1981.

Any person who desires to object to the proposed amendment or the determination must do so in writing to the Town Clerk before 20 March, 1981.

A. S. VAN JAARSVELD,
Act. Town Clerk.
Town Hall,
Brakpan.
4 March, 1981.
Notice No. 29/1981.

STADSRAAD VAN BRAKPAN.

WYSIGING VAN BRANDWEERVERORDENINGE EN VASSTELLING VAN TARIEWE.

1. Hiermee word bekend gemaak kragtens artikel 96 van die Ordonnansie op Plaaslike Bestuur, 17 van 1939, dat die Stadsraad van voorname is om die Brandweerverordeninge afgekondig by Administrateurskennisgewing 877 van 8 Oktober 1952, soos gewysig, verder te wysig ten einde die Ambulanstarief te herroep.

2. Hiermee word bekend gemaak kragtens artikel 80B(3) van die Ordonnansie op Plaaslike Bestuur, 17 van 1939, dat die Stadsraad by spesiale besluit nuwe Ambulanstariewe vasgestel

het met ingang 1 Februarie 1981. Die vasstelling verskil van die tafel verwant in die verordeninge hoofsaklik weens die verhoging daarvan ten einde verhoogde algemene bedryfskoste te bestry.

Besonderhede van die voorgestelde wysiging en vasstelling is beskikbaar vir besigtiging in gewone kantoortyd by Kamer 12, Stadhuis, Brakpan, vir 'n tydperk van veertien dae vanaf 4 Maart 1981.

Iemand wat beswaar wil maak teen die voorgestelde wysiging of vasstelling moet dit skriftelik rig aan die Stadsklerk voor 20 Maart 1981.

A. S. VAN JAARSVELD,
Wnd. Stadsklerk.

Stadhuis,
Brakpan.
4 Maart 1981.
Kennisgewing No. 29/1981.

171—4

hiervoor kennisgewing in die *Provinciale Koerant* by die ondergetekende doen.

B. J. DU TOIT,
Stadsklerk.

Munisipale Kantore,
Posbus 40,
Bronkhorstspruit.
4 Maart 1981.

172—4

TOWN COUNCIL OF BRITS.

AMENDMENT OF BY-LAWS.

Notice is hereby given in terms of the provisions of section 96 of the Local Government Ordinance, 1939, as amended of the Council's intention to amend the following by-laws:

1. Standard Financial By-laws published under Administrator's Notice 768 dated 24 July, 1968.

2. The Cleansing Services By-laws published under Administrator's Notice 392 dated 2 April, 1980.

Copies of these amendments are open for inspection at Room 21, Department of the Town Secretary, Municipal Offices, Brits, for a period of fourteen days from the date of publication hereof in the *Official Gazette*.

Any person who desires to record his objection to the said amendment must do so in writing to the undermentioned within 14 days after the date of publication of this notice in the *Official Gazette*.

A. J. BRINK,
Town Clerk.

Municipal Offices,
P.O. Box 106,
Brits.
0250.
4 March, 1981.
Notice No. 13/1981.

TOWN COUNCIL OF BRONKHORST-SPRUIT.

AMENDMENT OF BY-LAWS.

It is hereby notified in terms of section 96 of the Local Government Ordinance 17 of 1939, that the Town Council intends amending its Water Supply By-laws published under Administrator's Notice No. 21 of 5 January, 1977.

The general purport of these amendments are:

Amendment of charges for the supply and laying of a communication pipe and for the fixing of a meter supplied by the Council.

Copies of these by-laws and resolution are open for inspection at the office of the Town Council for a period of fourteen days from the date of publication hereof.

Any person who desires to record his/her objection to the by-laws, must do so in writing to the undermentioned within fourteen days after the date of publication of this notice in the *Provincial Gazette*.

B. J. DU TOIT,
Town Clerk.

Municipal Offices,
P.O. Box 40,
Bronkhorstspruit.
4 March, 1981.

STADSRAAD VAN BRONKHORST-SPRUIT.

WYSIGING VAN VERORDENINGE.

Daar word hiermee ingevolge artikel 96 van die Ordonnansie op Plaaslike Bestuur 17 van 1939, bekend gemaak dat die Stadsraad van voornemens is om sy Watervoorsieningsverordeninge afgekondig by Administrateurskennisgewing No. 21 van 5 Januarie 1977 te wysig.

Die algemene strekking van die wysiging behels die volgende:

Wysiging van die vordering vir die verskaffing en aanlê van 'n verbindingspyp en vir die aanbring van 'n meter deur die Raad voorsien.

Afskrifte van hierdie verordeninge en besluit lê ter insae by die kantoor van die Stadsraad vir 'n tydperk van veertien dae vanaf die datum van publikasie hiervan.

Enige persoon wat beswaar teen genoemde verordeninge wens aan te teken moet dit skriftelik binne 14 dae na die datum van publikasie van hierdie kennisgewing in die *Offisiële Koerant*, by ondergenoemde indien.

A. J. BRINK,
Town Clerk.

Town Hall,
Van Velden Street,
P.O. Box 106,
Brits.
0250.
4 March, 1981.
Notice No. 2/1981.

STADSRAAD VAN BRITS.

VASSTELLING VAN GELDE VIR DIE LEWERING VAN DIVERSE DIENSTE AAN DIE PUBLIEK.

Kennis geskied hierby ingevolge die bepaling van artikel 80B(3) van die Ordonnansie op Plaaslike Bestuur, No. 17 van 1939, soos gewysig, dat die Stadsraad van voornemens is om by spesiale besluit gelde vir die levering van diverse dienste aan die publiek soos die verwydering van bye, voorziening van turf, die bou van tweede ingange vir motorvoertuie tot privaat persele en die nasien van brandblusser, vas te stel om met ingang 1 Mei 1981, van krag te word.

'n Afskrif van die vasstelling van geld waarna bieroor verwys word, lê ter insae by Kamer 21, Departement van die Stadssekretaris, Stadhuis, Brits, vir 'n tydperk van veertien (14) dae vanaf die datum van publikasie van hierdie kennisgewing in die *Offisiële Koerant*.

Enige persoon wat beswaar teen bogenoemde vasstelling wens aan te teken moet dit skriftelik binne veertien (14) dae na die datum van publikasie van hierdie kennisgewing in die *Offisiële Koerant*, by ondergenoemde indien.

A. J. BRINK,
Stadsklerk.

Stadhuis,
Van Veldenstraat,
Posbus 106,
Brits.
0250.
4 Maart 1981.
Kennisgewing No. 2/1981.

173—4

Stadhuis,
Posbus 106,
Brits.
0250.
4 Maart 1981.
Kennisgewing No. 13/1981.

174—4

EDENVALE TOWN COUNCIL.

PROPOSED AMENDMENT OF THE EDENVALE TOWN-PLANNING SCHEME 1980: AMENDMENT SCHEME 1/17.

The Town Council of Edenvale has prepared a draft amendment town-planning scheme to be known as Amendment Scheme 1/17.

This draft scheme contains the following proposal:

The amendment of the zoning of Portion 3 of Erf 22, Edendale from "Residential 1" to "Residential 3" with a height restriction of 2 storeys and a coverage of 40%. The property is situated in a residential area.

Particulars of this scheme are open for inspection at the Council's office building, Room 330, Municipal Building, Van Riebeeck Avenue, Edenvale, during normal office hours for a period of four weeks from the date of the first publication of this notice, which is 4 March, 1981.

Any owner or occupier of immovable property situated within the area to which the above-named draft scheme applies or within 2 kilometres of the boundary thereof may in writing lodge any objection with or may make any representations to the above-named local authority in respect of such draft scheme within four weeks of the first publication of this notice, which is 4 March, 1981 and he may when lodging any such objection or making such representations, request in writing that he be heard by the local authority.

P. J. G. VAN OUDTSOORN,
Town Clerk.

Municipal Offices,
P.O. Box 25,
Edenvale.
1610.
4 March, 1981.
Notice No. 13/81.

STADSRAAD VAN EDENVALE.

VOORGESTELDE WYSIGING VAN DIE EDENVALESE DORPSBEPLANNINGSKEMA 1980:
WYSIGINGSKEMA 1/17.

Die Stadsraad van Edenvale het 'n wysigingsontwerpdorpsbeplanningskema opgestel wat bekend sal staan as Wysigingskema No. 1/17.

Hierdie ontwerpskema bevat die volgende voorstel:

Die wysiging van die sonering van Gedeelte 3 van Erf 22, Edendale van "Residensieel 1" na "Residensieel 3" met 'n hoogte beperk van 2 verdiepings en 'n dekking van 40%. Die eiendom is in 'n bestaande residensiële gebied geleë.

Besonderhede en planne van hierdie skema lêter insas by die Raad se kantore, Kamer 330, Municipale Gebou, Van Riebeecklaan, Edenvale, gedurende gewone kantoourure vir 'n tydperk van vier (4) weke van die datum van die eerste publikasie hiervan, naamlik 4 Maart 1981.

Enige eienaar of besitter van onroerende eiendom geleë binne 'n gebied waarop bogenoemde ontwerpskema van toepassing is of binne 2 kilometer van die grens daarvan, kan skriftelik enige beswaar indien by of vertoë tot bogenoemde plaaslike bestuur rig ten opsigte van sodanige ontwerpskema binne vier (4) weke vanaf die eerste publikasie van hierdie kennisgewing naamlik 4 Maart 1981 en wanneer hy enige sodanige beswaar indien of sodanige vertoë rig, kan hy skriftelik versoeck dat hy deur die plaaslike bestuur aangehoor word.

P. J. G. VAN OUDTSOORN,
Stadsklerk.

Municipale Kantore,
Posbus 25,
Edenvale.
1610.
4 Maart 1981.
Kennisgewing No. 13/81.

175-4-11

TOWN COUNCIL OF GREYLINGSTAD. DETERMINATION OF CHARGES.

In terms of the provisions of section 80B of the Local Government Ordinance 1939 (Ordinance 17 of 1939), it is hereby notified that the Town Council of Greylingsstad intend by special resolution to determine the charges payable in terms of the Council's Pound By-laws with effect from 1 January, 1981.

The general purpose of the determination of charges is to increase the charges payable in terms of the by-laws in respect of motor vehicles.

Copies of the amendments of the by-laws, of the determination and amendment of the charges and of the relevant resolution lie for inspection during office hours at the office of the Town Clerk, Municipal Office, Greylingsstad for a period of fourteen (14) days from the date of publication of this notice in the Provincial Gazette.

Any person desirous of objecting to the amendments or determination of charges, should do so in writing to the Town Clerk within fourteen (14) days from the date of publication of this notice in the Provincial Gazette.

J. S. OLIVIER,
Town Clerk.

P.O. Box 11,
Greylingsstad.
4 March, 1981.
Notice No. 2/1981.

STADSRAAD VAN GREYLINGSTAD.

VASSTELLING VAN GELDE.

Ingevolge artikel 80B van die Ordonnansie op Plaaslike Bestuur, 1939, (Ordonnansie 17 van 1939), word hierby bekend gemaak dat die Stadsraad van Greylingsstad van voorneme is om geldie betaalbaar kragtens die Raad se Skutverordeninge met ingang vanaf 1 Januarie 1981 by spesiale besluit vas te stel.

Die algemene strekking van die vasstelling is om die geldie betaalbaar kragtens die verordeninge ten opsigte van motorvoertuie te verhoog.

Afskrifte van die wysigings van die verordeninge van die vasstellings en wysigings van die geldie en van die betrokke besluit lê vir insas gedurende kantoourure by die kantoor van die Stadsklerk, Municipale Kantore, Greylingsstad vir 'n tydperk van veertien (14) dae vanaf datum van publikasie van hierdie kennisgewing in die Provinciale Koerant.

Enige persoon wat beswaar teen die wysigings of vasstellings wil maak, moet dit skriftelik by die Stadsklerk doen binne veertien (14) dae na die datum van publikasie van hierdie kennisgewing in die Provinciale Koerant.

J. S. OLIVIER,
Stadsklerk.

Posbus 11,
Greylingsstad.
4 Maart 1981.
Kennisgewing No. 2/1981.

176-4

CITY OF JOHANNESBURG. PERMANENT CLOSING OF LANE AND PART OF LAWLEY ROAD, WESTCLIFF.

(Notice in terms of sections 67(3) and 79(17)(b) of the Local Government Ordinance, 1939)

The Council intends, subject to the approval of the Administrator, to close permanently the portion of Lawley Road, Westcliff, extending northwards from the southern boundary of Erf 212 and an unnamed lane extending from Lawley Road northwards to Woolston Road between Erf

256 to the west and Erven 212 and 189 to the east, and to donate the stand formed thereby to the Ridge School.

A plan showing the portion of road and the lane the Council proposes to close and donate may be inspected during ordinary office hours at Room 249, Block A, Civic Centre, Braamfontein.

Any person who objects to the proposed closing and donation or who will have any claim for compensation if the closing is effected must lodge his objection or claim in writing with me on or before 4 May, 1981.

S. D. MARSHALL,
City Secretary.

Civic Centre,
Braamfontein.
4 March, 1981.

STAD JOHANNESBURG.

PERMANENTE SLUITING VAN STEEG EN GEDEELTE VAN LAWLEYWEG, WESTCLIFF.

(Kennisgewing ingevolge artikel 67(3) en 79(17)(b) van die Ordonnansie op Plaaslike Bestuur, 1939)

Die Raad is voornemens om, onderworpe aan die goedkeuring van die Administrateur, die gedeelte van Lawleyweg, Westcliff, wat noordwaarts vanaf die suidelike grens van Erf 212 strek, en 'n steeg sonder naam wat vanaf Lawleyweg noordwaarts tot by Woolstonweg tussen Erf 256 na die westekant en Erwe 212 en 189 aan die oostekant strek, permanent te sluit en die standplaas wat sodoende gevorm word, aan die Ridge-skool te skenk.

'n Plan waarop die padgedeelte en die steeg wat die Raad voornemens is om te sluit, en te skenk, aangedui word, is gedurende gewone kantoourure in Kamer 249, Blok A, Burgersentrum, Braamfontein, ter insas.

Iemand wat teen die voorgestelde sluiting en skenkning beswaar het of wat na die sluiting 'n eis om vervoeding sal hê, moet sy beswaar of eis uiters op 4 Mei 1981 by my indien.

S. D. MARSHALL,
Stadssekretaris.

Burgersentrum,
Braamfontein.
4 Maart 1981.

177-4

NABOOMSPRUIT TOWN COUNCIL.

PROPOSED LEASE OF PROPERTY: (18/11/1).

Notice is hereby given in terms of section 79(18) of the Local Government Ordinance No. 17 of 1939, as amended, that it is the intention of the Town Council, subject to the approval of the Administrator, to lease the following property:-

Portion of Townlands, known as the Abattoir Building, to Messrs R. & H Konstruksie.

Details regarding the terms of lease are open for inspection during office hours in the office of the Town Clerk, Municipal Offices, Naboomspruit.

Any person who wishes to object to the proposed lease of the above-mentioned property must lodge such objection in writing with the undersigned not later than 16h00 on the 19th March, 1981.

J. T. POTGIETER,
Town Clerk.

Municipal Offices,
Private Bag X340,
Naboomspruit.
0560.
4 March, 1981.
Notice No. 3/81.

STADSRAAD VAN NABOOMSPRUIT.

VOORGESTELDE VERHURING VAN EIENDOM: (18/11/1)

Kennis geskied hiermee ingevolge die bepaling van artikel 79(18) van die Ordonnansie op Plaaslike Bestuur, No. 17 van 1939, soos gewysig, dat die Stadsraad van Naboomspruit van voorname is om onderworpe aan die goedkeuring van die Administrateur, die volgende eiendom te verhuur:-

Gedeelte van Dorpsgronde, bekend as die Abattoir Gebou aan mnre. R.&H. Konstruksië.

Besonderhede ten opsigte van die voorwaarde van verhuring is gedurende kantoore ter insae in die kantoor van die Stadsklerk, Munisipale Kantoor, Naboomspruit.

Enige belanghebbende persoon wat beswaar teen die voorgestelde verhuring van' genoemde eiendom wil maak, moet 'n skrifstelike beswaar nie later nie as 16h00 op 19 Maart 1981 by die ondergetekende indien.

J. T. POTGIETER,
Stadsklerk.

Munisipale Kantoor,
Privaatsak X340,
Naboomspruit.
0560.

4 Maart 1981.
Kennisgewing No. 3/81.

178—4

CITY COUNCIL OF PRETORIA.

PROPOSED AMENDMENT TO THE PRETORIA TOWN-PLANNING SCHEME, 1974:

TOWN-PLANNING AMENDMENT SCHEME 732.

The city of Pretoria has prepared a draft amendment to the Pretoria Town-planning Scheme, 1974, to be known as Town-planning Amendment Scheme 732.

This draft scheme contains the following proposal:

The rezoning of the closed portions of Betsie and Erra Streets, Wonderboom Agricultural Holdings Extension 1, from "street" to "agricultural".

The properties are registered in the name of the City Council of Pretoria.

Particulars of this scheme are open for inspection at Rooms 603W and 362W, Munitoria, Van der Walt Street, Pretoria, for a period of four weeks from the date of the first publication of this notice, which is 4 March, 1981.

The Council will consider whether or not the scheme should be adopted.

Any owner or occupier of immovable property within the area of the Pretoria Town-planning Scheme, 1974, or within two kilometres of the boundary thereof, has the right to object to the scheme or to make representations in respect thereof and, if he wishes to do so, he shall, within four weeks of the first publication of this notice, which is 4 March, 1981, inform the Town Clerk, P.O. Box 440, Pretoria 0001, in writing of such objection or representation and shall state whether or not he wishes to be heard by the local authority.

P. DELPORT,
Town Clerk.

4 March, 1981.
Notice No. 69/1981.

STADSRAAD VAN PRETORIA.

VOORGESTELDE WYSIGING VAN DIE PRETORIA-DORPSBEPLANNINGSKEMA, 1974:

DORPSBEPLANNINGSWYSIGINGSKEMA 732.

Die Stadsraad van Pretoria het 'n ontwerpwy siging opgestel wat bekend sal staan as Pretoria-dorpsbeplanningswysigingskema 732.

Hierdie ontwerpskema bevat die volgende voorstel:

Die hersonering van die gesloten gedeeltes van Betsie- en Errastraat, Wonderboomlandbouhoeves-uitbreiding 1, van "straat" na "landbou".

Die eiendomme is op die naam van die Stadsraad van Pretoria geregistreer.

Besonderhede van hierdie skema lê ter insae in Kamers 603W en 362W, Munitoria, Van der Waltstraat, Pretoria, vir 'n tydperk van vier weke vanaf die datum van die eerste publikasie van hierdie kennisgewing naamlik 4 Maart 1981.

Die Raad sal die skema oorweeg en besluit of dit aangeneem moet word.

Enige eienaar of okkuperder van vaste eiendom binne die gebied van die Pretoria-dorpsbeplanningskema, 1974, of binne twee kilometer van die grens daarvan, het die reg om teen die skema beswaar te maak of om vertoe ten opsigte daarvan te rig en, indien hy dit wil doen, moet hy die Stadsklerk, Posbus 440, Pretoria 0001, binne vier weke van die eerste publikasie van hierdie kennisgewing, naamlik 4 Maart 1981, skriftelik van sodanige beswaar of vertoe in kennis stel en vermeld of hy deur die plaaslike bestuur gehoor wil word al dan nie.

P. DELPORT,
Stadsklerk.

4 Maart 1981.
Kennisgewing No. 69/1981.

179—4—11

MUNICIPALITY OF RANDFONTEIN.

AMENDMENT TO RIEBEECK LAKE BY-LAWS.

Notice is hereby given in terms of section 96 of the Local Government Ordinance, 1939, as amended, that the Council intends amending the Riebeeck Lake By-laws.

The general purport of this amendment is to provide for a progressive monthly increase in rental where a rondavel or a stand in the caravan park is rented for an uninterrupted period of 4 weeks, to a maximum of 12 weeks, during any one year.

Copies of the amendment are open for inspection at the office of the Town Secretary (Room C) for a period of fourteen (14) days from the date of publication hereof in the Provincial Gazette.

Any person who desires to record his objection to the amendment of the said by-laws must do so in writing to the undersigned within fourteen (14) days after date of publication of this notice in the Provincial Gazette.

C. J. JOUBERT,
Town Clerk.

P.O. Box 218,
Randfontein.
1760.
Tel. 693-2271.
4 March, 1981.
Notice No. 11/1981.

MUNISIPALITEIT RANDFONTEIN.

WYSIGING VAN RIEBEECKMEER-VERORDENINGE.

Daar word hierby ingevolge artikel 96 van die Ordonnansie op Plaaslike Bestuur, 1939, soos gewysig, bekend gemaak dat die Raad voornemens is om die Riebeeckmeerverordeninge te wysig.

Die algemene strekking van hierdie wysiging is om voorsiening te maak vir 'n progressiewe maandelikse verhoging in huurgeld namate die ononderbroke tydperk van huur vir 'n rondavel of 'n staanplek in die karavaanpark toeneem van 4 weke tot 'n maksimum tydperk van 12 weke gedurende enige jaar.

Afskrifte van hierdie wysiging lê ter insae in die kantoor van die Stadssekretaris (Kamer C) vir 'n tydperk van veertien (14) dae vanaf datum van publikasie hiervan in die Provinciale Koerant.

Enige persoon wat beswaar teen die wysiging van die genoemde verordeninge wens aan te teken moet dit skriftelik binne veertien (14) dae na datum van publikasie van hierdie kennisgewing in die Provinciale Koerant, by die ondergetekende doen.

C. J. JOUBERT,
Stadsklerk.

Posbus 218,
Randfontein.
1760.
Tel. 693-2271.
4 Maart 1981.
Kennisgewing No. 11/1981.

180—4

CITY COUNCIL OF ROODEPOORT.

LOCAL AUTHORITY OF ROODEPOORT SUPPLEMENTARY VALUATION ROLL FOR THE FINANCIAL YEARS 1979 AND 1980.

Notice is hereby given in terms of section 37 of the Local Authorities Rating Ordinance, 1977 (Ordinance 11 of 1977), that the supplementary valuation roll for the financial years 1979/80 of all rateable property within the municipality has been certified and signed by the chairman of the valuation board and has therefore become fixed and binding upon all persons concerned as contemplated in section 37(3) of that Ordinance.

However, attention is directed to section 17 of the said Ordinance, which provides as follows:

"Right of appeal against decision of valuation board.

17. (1) An objector who has appeared or has been represented before a valuation board, including an objector who has lodged or presented a reply contemplated in section 15(4), may appeal against the decision of such board in respect of which he is an objector within thirty days from the date of publication in the Provincial Gazette of the notice referred to in section 16(4)(a) or, where the provisions of section 16(5) are applicable, within twenty-one days after the day on which the reasons referred to therein, were forwarded to such objector, by lodging with the secretary of such board a notice of appeal in the manner and in accordance with the procedure prescribed and such secretary shall forward forthwith a copy of such notice of appeal to the valuer and to the local authority concerned.

(2) A local authority which is not an objector may appeal against any decision of a valuation board in the manner contemplated in subsection (1) and any other person who is not an objector but who is directly affected by a decision of a valuation board may, in like manner, appeal against such decision."

A notice of appeal form may be obtained from the secretary of the valuation board.

W. J. LOURENS,
Secretary: Valuation Board.

Municipal Office,
Roodepoort.
4 March, 1981.
Notice No. 7/81.

STADSRAAD VAN ROODEPOORT.

PLAASLIKE BESTUUR VAN ROODEPOORT AANVULLENDE WAARDERINGSLYS VIR DIE BOEKJARE 1979 EN 1980.

Kennis word hierby ingevolge artikel 37 van die Ordonnansie op Eiendomsbelasting van Plaaslike Besture, 1977 (Ordonnansie 11 van 1977), gegee dat die aanvullende waarderingslys vir die boekjare 1979/80 van alle belasbare eiendom binne die munisipaliteit deur die voorzitter van die waarderingsraad gesertifiseer en geteken is en gevoldigk finala en bindend geword het op alle betrokke persone soos in artikel 37(3) van daardie Ordonnansie beoog.

Die aandag word egter gevëstig op artikel 17 van gemelde Ordonnansie wat soos volg bepaal:

"Reg van appèl teen beslissing van waarderingsraad.

17. (1) 'n Beswaarmaker wat voor 'n waarderingsraad verskyn het of verteenwoordig was, met inbegrip van 'n beswaarmaker wat 'n antwoord soos in artikel 15(4) beoog, ingedien of voorgelê het, kan teen die beslissing van sodanige raad ten opsigte waarvan hy 'n beswaarmaker is, binne dertig dae vanaf die datum van die publikasie in die *Provinciale Koerant* van die Kennisgewing in artikel 16(4)(a) genoem of, waar die bepalings van artikel 16(5) van toepassing is, binne een-en-twintig dae na die dag waarop die redes daarin genoem, aan sodanige beswaarmaker gestuur is, appèl op die wyse soos voorgeskryf en in ooreenstemming met die procedure soos voorgeskryf in te dien en sodanige sekretaris stuur onverwyd 'n afskrif van sodanige kennisgewing van appèl aan die waardeerdeer en aan die betrokke plaaslike bestuur.

(2) 'n Plaaslike bestuur wat nie 'n beswaarmaker is nie, kan teen enige beslissing van 'n waarderingsraad appèl aanteken op die wyse in subartikel (1) beoog en enige ander persoon wat nie 'n beswaarmaker is nie maar wat regstreeks deur 'n beslissing van 'n waarderingsraad geraak word, kan op dergelyke wyse, teen sodanige beslissing appèl aanteken."

'n Vorm vir kennisgewing van appèl kan van die sekretaris van die waarderingsraad verkry word.

W. J. LOURENS,
Sekretaris: Waarderingsraad.

Munisipale Kantoor,
Roodepoort.
4 Maart 1981.
Kennisgewing No. 7/81.

181-4-11

MUNICIPALITY OF SCHWEIZER-RENEKE.

ELECTRICITY BY-LAWS: DETERMINATION OF TARIFF OF CHARGES.

In terms of the provisions of section 80B(8) of the Local Government Ordinance, 1939 (Ordinance 17 of 1939), it is hereby notified that the Village Council of Schweizer-Reneke has by special resolution on 24 November, 1980, resolved to amend the tariff of charges, as published in *Provincial Gazette* No. 4109 of 15 October, 1980, by the substitution for item 5 of the new, item 5 as indicated hereunder, with

effect from the consumption as from 1 January, 1981:-

"5. SURCHARGE:

A surcharge of 41% shall be levied on the charges payable by any consumer for KW.h consumed in terms of items 2, 3 and 4."

N. T. P. VAN ZYL,
Town Clerk.

Municipal Office,
Schweizer-Reneke.
4 March, 1981.
Notice No. 2/1981.

MUNISIPALITEIT SCHWEIZER-RENEKE.

ELEKTRISITEITSVERORDENING: VAS- STELLING VAN TARIEF VAN GELDE.

Ingevolge die bepalings van artikel 80B(8) van die Ordonnansie op Plaaslike Bestuur, 1939 (Ordonnansie 17 van 1939), word hierby bekend gemaak dat die Dorpsraad van Schweizer-Reneke op 24 November 1980 by spesiale besluit, besluit het om die tarief van gelde, soos gepubliseer in *Provinciale Koerant* No. 4109 van 15 Oktober 1980, te wysig deur item 5 van die Tarief van Gelde met ingang van die verbruik vanaf 1 Januarie 1981, deur die nuwe item 5, soos hieronder aangedui, te vervang:

"5. TOESLAG:

'n Toeslag van 41% word gehef op alle gelde betaalbaar deur enige verbruiker vir KW.h verbruik ingevolge items 2, 3 en 4."

N. T. P. VAN ZYL,
Town Clerk.

Munisipale Kantoor,
Schweizer-Reneke.
4 Maart 1981.
Kennisgewing No. 2/1981.

182-4

VILLAGE COUNCIL OF SWARTRUGGENS

AMENDMENT TO ELECTRICITY BY-LAWS.

It is hereby notified in terms of section 96 of the Local Government Ordinance, 1939, that the Village Council of Swartruggens proposed to amend the Electricity By-laws of the Council, published under Administrator's Notice No. 392 dated 22 May, 1957, as amended.

The general purport of this amendment is to increase tariffs. The increase became necessary because of the increase in tariffs by Escom.

Copies of the amendment are open to inspection at the offices of the Council for a period of 14 days from the date of publication hereof.

Any person who desires to record his objection to the said amendment must do so in writing to the undermentioned within 14 days from the date of publication of this notice in the *Provincial Gazette*.

F. J. COETZEE,
Town Clerk.

Municipal Offices,
P.O. Box 1,
Swartruggens.
2835.
4 March, 1981.
Notice No. 16/1981.

DORPSRAAD VAN SWARTRUGGENS.

WYSIGING VAN ELEKTRISITEITSVERORDENINGE.

Daar word hierby ingevolge artikel 96 van die Ordonnansie op Plaaslike Bestuur 1939, bekend gemaak dat die Dorpsraad van Swartruggens

voornemens is om die Elektrisiteitsverordeninge van die Dorpsraad afgekondig by Administrateurskennisgewing No. 392 van 22 Mei 1957, soos gewysig, verder te wysig.

Die algemene strekking van hierdie wysiging is om voorsiening te maak vir 'n verhoging in die tariewe. Die verhoging het nodig geword omdat Evkom sy tariewe verhoog het.

Afskrifte van hierdie wysiging lê ter insae by die kantoor van die Raad vir 'n tydperk van 14 dae vanaf die datum van publikasie hiervan.

Enige persoon wat beswaar teen genoemde wysigings wil aanteken, moet dit skriftelik binne 14 dae na datum van publikasie van hierdie kennisgewing in die *Provinciale Koerant*, by die ondergetekende doen.

F. J. COETZEE,
Stadsklerk.

Munisipale Kantore,
Posbus 1,
Swartruggens.
2835.
4 Maart 1981.
Kennisgewing No. 16/1981.

183-4

TOWN COUNCIL OF THABAZIMBI.

AMENDMENT TO STANDARD FINANCIAL BY-LAWS.

It is hereby in terms of section 96 of the Local Government Ordinance, No. 17 of 1939, as amended published that the Town Council of Thabazimbi intends to amend its Standard Financial By-laws to be in unison with section 35 of the Local Government Ordinance, No. 17 of 1939.

The general purport of this amendment is to increase the amount for which the Council can buy articles before it is obligated to invite tenders.

Copies of these amendments are open for inspection at the offices of the Council for a period of fourteen (14) days from date of publication hereof in the *Provincial Gazette*.

Any person who desires to record his objection to the said amendments, must do so in writing to the undermentioned within fourteen (14) days after publication hereof in the *Provincial Gazette*.

DIRK W. VAN ROOYEN,
Town Clerk.

Municipal Offices,
P.O. Box 90,
Thabazimbi.
0380.
Tel. 105.
4 March, 1981.
Notice No. 6/81.

STADSRAAD VAN THABAZIMBI.

WYSIGING VAN STANDAARD FINANSIELLE VERORDENINGE.

Daar word hierby ingevolge die bepalings van artikel 96 van die Ordonnansie op Plaaslike Bestuur, No. 17 van 1939, soos gewysig bekend gemaak dat die Stadsraad van Thabazimbi van voorneme is om die Standaard Finansiële Verordeninge te wysig om in ooreenstemming met artikel 35 van die Ordonnansie op Plaaslike Bestuur, No. 17 van 1939, te kom.

Die algemene strekking van hierdie wysiging behels die verhoging van die bedrag waarvoor die Raad aankope kan maak voordat hy verplig is om tenders te vra.

Afskrifte van hierdie wysiging lê ter insae by die kantoor van die Raad vir 'n tydperk van veertien (14) dae vanaf datum van publikasie hiervan in die *Provinciale Koerant*.

Enige persoon wat beswaar, teen genoemde wysigings wens aan te teken, moet dit skriftelik binne veertien (14) dae vanaf datum van publikasie van hierdie kennisgewing in die *Provinsiale Koerant* by ondergetekende doen.

DIRK W. VAN ROOYEN,
Stadsklerk.

Munisipale Kantore,
Posbus 90,
Thabazimbi.
0380.
Tel. 105.
4 Maart 1981.
Kennisgewing No. 6/81.

184—4

TRICHARDT VILLAGE COUNCIL.

ADOPTION OF STANDARD DRAINAGE BY-LAWS.

Notice is hereby given in terms of section 96 of the Local Government Ordinance, 1939, that the Trichardt Village Council intends to adopt the Standard Drainage By-laws as promulgated under Administrator's Notice 665 of 8 June, 1977, with amendments.

Copies of these by-laws will lie for inspection during normal office hours at the office of the Town Clerk, Municipal Offices for a period of 14 days from date of publication hereof in the *Provincial Gazette*.

Any person who desires to record his objection to the adoption of the by-laws, must do so in writing to the undersigned within 14 days from date of publication hereof in the *Provincial Gazette*.

M. J. V.D. MERWE,
Town Clerk.
4 March, 1981.

TRICHARDT DÖRPSRAAD.

AANNAME VAN STANDAARD RIOLE-RINGSVERORDENINGE.

Daar word hierby ingevolge artikel 96 van die Ordonnansie op Plaaslike Bestuur, 1939, bekend gemaak dat die Dorpsraad van Trichardt van voorname is om die Standaard Riole-Ringsverordeninge afgekondig by Administratierskennisgewing 665 van 8 Junie 1977, met wysigings aan te neem.

Afskrifte van die verordeninge lê ter insae gedurende gewone kantoorure by dié kantoor van die Stadsklerk, Munisipale Kantore vir 'n tydperk van 14 dae vanaf die datum van publikasie van hierdie kennisgewing in die *Provinsiale Koerant*.

Enige persoon wat beswaar teen die aanneming van die genoemde verordeninge wens aan te teken, moet dit skriftelik binne 14 dae na datum van die publikasie hiervan in die *Provinsiale Koerant* by die ondergetekende indien.

M. J. V.D. MERWE,
Stadsklerk.
4 Maart 1981.

TOWN COUNCIL OF VEREENIGING.

PROPOSED PERMANENT CLOSING AND ALIENATION OF PORTION OF REMAINDER ERF 643 (PUBLIC OPEN SPACE), DUNCANVILLE.

Notice is hereby given in accordance with sections 67, 68 and 79(18)(b) of the Local Government Ordinance, 1939, that it is the intention of the Town Council of Vereeniging to close permanently and alienate to Johan de Waal Transport (Pty) Limited, at a price of R14 400

plus costs, a portion of the Remainder of Erf 643 (Public Open Space), Duncanville, for parking and purposes incidental thereto, as more fully described in the appended schedule.

Drawing TP. 19/15/2 showing the proposed closing can be inspected during normal office hours at the office of the Town Secretary (Room 104), Municipal Offices, Vereeniging.

Any person who has any objection to the proposed permanent closing, or who may have any claim for compensation if such closing is carried out, must lodge his objection or claim in writing with the Town Clerk, Municipal Offices, Vereeniging, not later than Thursday, 30 April, 1981.

J. J. ROODT,
Town Clerk.

Municipal Offices,
Vereeniging.
4 March, 1981.
Notice No. 8855.

SCHEDULE.

A portion of the Remainder Erf 643 (Public Open Space), Duncanville Township (vide General Plan S.G. A5240/49), approximately 2 190 m² in extent, situated adjacent to the northern boundary of Erf 535, as more fully shown by the letters ABCDEFG on Drawing TP19/15/2.

STADSRAAD VAN VEREENIGING.

VOORGESTELDE PERMANENTE SLUITING EN VERVREEMDING VAN GEDEELTE VAN RESTANT ERF 643 (OPENBARE OOPRUIMTE), DUNCANVILLE.

Hierby word ingevolge die bepalings van artikels 67, 68 en 79(18)(b) van die Ordonnansie op Plaaslike Bestuur, 1939, bekend gemaak dat die voorname van die Stadsraad van Vereeniging is om gedeelte van die Restant van Erf 643 (Openbare Oopruimte), Duncanville, soos in die onderstaande bylae omskrywe, permanent te sluit en aan Johan de Waal Transport (Edns.) Beperk teen 'n prys van R14 400 plus koste, vir parkering en verwante gebruikte, te verkoop.

Tekening TP. 19/15/2 wat die voorgestelde sluiting aantoon kan gedurende gewone kantoorure by die kantoor van die Stadssekretaris (Kamer 104), Munisipale Kantoor, Vereeniging, besigtig word.

Enigemand wat enige beswaar teen die voorgenome permanente sluiting het, of wat vergoeding mag eis indien sodanige sluiting plaasvind, moet sy beswaar of eis skriftelik nie later nie as Donderdag, 30 April, 1981, by die Stadsklerk, Munisipale Kantoor, Vereeniging, indien.

J. J. ROODT,
Stadsklerk.

Munisipale Kantoor,
Vereeniging.
4 Maart 1981.
Kennisgewing No. 8855.

BYLAE.

'n Gedeelte van Restant Erf 643 (Openbare Oopruimte) Duncanville Dorp (vide Algemeng Plan L.G. No. A5240/49), ongeveer 2 190 m² groot, geleë aangrensend aan die noordelike grens van Erf 535, soos meer volledig aangetoon deur die letters ABCDEFG op Tekening TP19/15/2.

186—4

TOWN COUNCIL OF VEREENIGING.

VEREENIGING DRAFT TOWN-PLANNING AMENDMENT SCHEME 1/182.

Notice in terms of section 26(1)(a) of the Town-planning and Townships Ordinance, 1965.

The Town Council of Vereeniging has prepared a draft town-planning amendment scheme, to be known as Vereeniging Amendment Scheme 1/182.

This scheme will be an amendment scheme and contains a proposal for the rezoning of portions of the Remainder of Erf 643, Duncanville to "Special for parking of vehicles and ancillary uses" and "Public Open Space."

Particulars of this amendment scheme are open for inspection at the office of the Town-Secretary (Room 104), Municipal Offices, Vereeniging, for a period of four weeks from the date of first publication of this notice, which is 4 March, 1981.

Any objection or representations in connection with this scheme shall be submitted in writing to the Town Council of Vereeniging within a period of four weeks from the above-mentioned date.

J. J. ROODT,
Town Clerk.

Municipal Offices,
P.O. Box 35,
Vereeniging.
4 March, 1981.
Notice No. 8856.

STADSRAAD VAN VEREENIGING.

VEREENIGING ONTWERP-DORPSBEPLANNING-WYSIGINGSKEMA 1/182.

Kennisgewing ingevolge artikel 26(1)(a) van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965.

Die Stadsraad van Vereeniging het 'n ontwerp-dorpsbeplanningskema opgestel wat bekend sal staan as Vereeniging-wysigingskema 1/182.

Hierdie skema sal 'n wysigingskema wees en bevat 'n voorstel vir die hersonering van dele van die Restant van Erf 643, Duncanville na "Spesial vir parkering van voertuie en verwante gebruikte" en "Openbare Oopruimte".

Besonderhede van hierdie skema lê ter insae in die kantoor van die Stadssekretaris (Kamer 104), Munisipale Kantoor, Vereeniging, vir 'n tydperk van vier weke vanaf die datum van die eerste publikasie van hierdie kennisgewing, naamlik 4 Maart 1981.

Enige beswaar of vertoe in verbond met hierdie skema moet skriftelik aan die Stadsraad van Vereeniging, binne 'n tydperk van vier weke vanaf bogenoemde datum voorgelê word.

J. J. ROODT,
Stadsklerk.

Munisipale Kantoor,
Posbus 35,
Vereeniging.
4 Maart 1981.
Kennisgewing No. 8856.

187—4—11

TOWN COUNCIL OF VEREENIGING.

VEREENIGING DRAFT TOWN-PLANNING AMENDMENT SCHEME 1/186.

Notice in terms of section 26(1)(a) of the Town-planning and Townships Ordinance, 1965.

The Town Council of Vereeniging has prepared a draft Town-planning Amendment Scheme, to be known as Vereeniging Amendment Scheme 1/186.

This scheme will be an amendment scheme and contains a proposal for the rezoning of two portions of Union Street, Vereeniging, from "Public Road" to "Municipal".

Particulars of this amendment scheme are open for inspection at the office of the Town Secretary (Room 104), Municipal Offices, Vereeniging, for a period of four weeks from the date of first publication of this notice, which is 4 March, 1981.

Any objection or representations in connection with this scheme shall be submitted in writing to the Town Council of Vereeniging within a period of four weeks from the above-mentioned date.

J. J. ROODT,
Town Clerk.

Municipal Offices,
P.O. Box 35,
Vereeniging,
4 March, 1981.
Notice No. 8857.

STADSRAAD VAN VEREENIGING.

VEREENIGING ONTWERP-DORPSBEPLANNING-WYSIGINGSKEMA 1/186.

Kennisgewing ingevolge artikel 26(1)(a) van die Ordonnansie op Dorpsbeplanning en Dorpe, 1965.

Die Stadsraad van Vereeniging het 'n ontwerp-dorpsbeplanningskema opgestel wat bekend sal staan as Vereeniging-wysigingskema 1/186.

Hierdie skema sal 'n wysigingskema wees en bevat 'n voorstel vir die hersonering van twee dele van Unionstraat, Vereeniging van "Openbare Pad" na "Munispaal".

Besonderhede van hierdie skema lê ter insae in die kantoor van die Stadssekretaris (Kamer 104), Municipale Kantoer, Vereeniging, vir 'n tydperk van vier weke vanaf die datum van die eerste publikasie van hierdie kennisgewing, naamlik 4 Maart 1981.

Enige beswaar of vertoë in verband met hierdie skema moet skriftelik aan die Stadsraad van Vereeniging, binne 'n tydperk van vier weke vanaf bovenoemde datum voorgelê word.

J. J. ROODT,
Stadsklerk.

Municipale Kantoer,
Posbus 35,
Vereeniging,
4 Maart 1981.
Kennisgewing No. 8857.

188—4—11

CONTENTS

Administrator's Notices.

159. Transvaal Board for the Development of Peri-Urban Areas: Proposed raising of status of the Komatiport Local Area Committee	593
160. Kempton Park Municipality: Alteration of Boundaries	593
178. Town Council of Fochville: Withdrawal of Exemption from Rating	594
179. Town Council of Westonaria: Withdrawal of Exemption from Rating	594
190. Brits Municipality: Alteration of Boundaries	594
250. Brits Municipality: By-laws Relating to the Storage, Use and Handling of Flammable Liquids and Substances	595
251. Correction Notice. Germiston Municipality: Electricity Supply By-laws	636
252. Correction Notice: Potchefstroom Municipality: Adoption of Standard Drainage By-laws	637
253. Ermelo Municipality: Alteration of Boundaries	637
254. Klerksdorp Amendment Scheme 28	637
255. Klerksdorp Amendment Scheme 32	638
256. Klerksdorp Extension 21 Township. Declaration of an approved township	638
257. Alberton Amendment Scheme 2	641
258. Ermelo Amendment Scheme 1/62	641
259. Pretoria Amendment Scheme 638	641
260. Johannesburg Amendment Scheme 155. Correction Notice	642
261. Randburg Amendment Scheme 286	642
262. Deviation and Widening of District Road 115, 869 and other road adjustments: Districts of Thabazimbi and Rustenburg	642
263. Declaration of a Public Provincial Road P219-1 (K43): District of Johannesburg	644
264. Increase and decrease of the road reserve of Provincial Road P219-1 (K43): District Johannesburg	647
265. Declaration of a public road: District Johannesburg	650
266. Declaration of a public district road and relative road adjustments: District Potgietersrus	652
267. Closing of an unnumbered public road over the farm Bok 356-L.S., district of Pietersburg	653
268. Declaration and widening of public district road: District of Klerksdorp	654

General Notices.

161. Middelburg Amendment Scheme 41	655
162. Pretoria Amendment Scheme 699	655
163. Edenvale Amendment Scheme 16	656
164. Nylstroom Amendment Scheme 1/16	656
165. Sandton Amendment Scheme 378	657
166. Brakpan Amendment Scheme 1/72	657
167. Sandton Amendment Scheme 377	658
168. Sandton Amendment Scheme 371	658
169. Pretoria Amendment Scheme 704	659
170. Pretoria Amendment Scheme 703	659
172. Proposed Establishment of Townships: (1) Bryanston Extension 42; (2) Morningside Extension 38; (3) Delmas Extension 12	660
173. Sandton Amendment Scheme 226	661
174. Potchefstroom Amendment Scheme 35	663
175. Alberton Amendment Scheme 34	663
176. Johannesburg Amendment Scheme 451	664
177. Halfway House and Clayville Amendment Scheme 53	664
178. Sandton Amendment Scheme 379	665
179. Pretoria Amendment Scheme 711	665
180. Pretoria Amendment Scheme 712	666
181. Middelburg Amendment Scheme 42	666
182. Klerksdorp Amendment Scheme 27	667
183. Proposed Extension of Boundaries. (1) Hendrina Extension 1	667
Tenders	669
Notices by Local Authorities	671

INHOUD

Administrateurskennisgewings.

159. Transvaalse Raad vir die Ontwikkeling van Buitestedelike Gebiede: Voorgestelde verhoging van status van die Plaaslike Gebiedskomitee van Komatiportoort	593
160. Munisipaliteit Kemptonpark: Verandering van Grense	593
178. Stadsraad van Fochville: Intrekking van Vrystelling van Eiendomsbelasting	594
179. Stadsraad van Westonaria: Intrekking van Vrystelling van Eiendomsbelasting	594
190. Munisipaliteit Brits: Verandering van Grense	594
250. Munisipaliteit Brits: Verordeninge Betreffende die Opberging, Gebruik en Hantering van Vlambare Vloeistowwe en Stowwe	595
251. Kennisgewing van Verbetering. Munisipaliteit Germiston: Elektrisiteitsvoorsieningsverordeninge	636
252. Kennisgewing van Verbetering: Munisipaliteit Potchefstroom: Aanname van Standaard Rioleeringsverordeninge	637
253. Munisipaliteit Ermelo: Verandering van Grense	637
254. Klerksdorp-wysigingskema 28	637
255. Klerksdorp-wysigingskema 32	638
256. Dorp Klerksdorp Uitbreiding 21: Verklaring tot goedgekeurde dorp	638
257. Alberton-wysigingskema 2	641
258. Ermelo-wysigingskema 1/62	641
259. Pretoria-wysigingskema 638	641
260. Johannesburg-wysigingskema 155: Verbeteringskennisgewing	642
261. Randburg-wysigingskema 286	642
262. Verlegging en Verbreeding van Distrikspad 115, 869 en ander padroëlings: Distrikte Thabazimbi en Rustenburg	642
263. Verklaring van 'n Openbare Provinciale Pad P219-1 (K43): Distrik Johannesburg	644
264. Vermeerdering en vermindering van die padreserve van Provinciale Pad P219-1 (K43): Distrik Johannesburg	644
265. Verklaring van 'n openbare pad: Distrik Johannesburg	647
266. Verklaring van openbare distrikspad en verwante padroëlings: Distrik Potgietersrus	652
267. Sluiting van 'n ongenommerde openbare pad oor die plaas Bok 356-L.S.: distrik Pietersburg	653
268. Verklaring en verbreding van openbare distrikspad: Distrik Klerksdorp	654

Algemene Kennisgewings.

161. Middelburg-wysigingskema 41	655
162. Pretoria-wysigingskema 699	655
163. Edenvale-wysigingskema 16	656
164. Nylstroom-wysigingskema 1/16	656
165. Sandton-wysigingskema 378	657
166. Brakpan-wysigingskema 1/72	657
167. Sandton-wysigingskema 377	658
168. Sandton-wysigingskema 371	658
169. Pretoria-wysigingskema 704	659
170. Pretoria-wysigingskema 703	659
172. Voorgestelde dorpstigting: (1) Bryanston Uitbreiding 42; (2) Morningside Uitbreiding 38; (3) Delmas Uitbreiding 12	660
173. Sandton-wysigingskema 226	661
174. Potchefstroom-wysigingskema 35	663
175. Alberton-wysigingskema 34	663
176. Johannesburg-wysigingskema 451	664
177. Halfway House en Clayville-wysigingskema 53	664
178. Sandton-wysigingskema 379	665
179. Pretoria-wysigingskema 711	665
180. Pretoria-wysigingskema 712	666
181. Middelburg-wysigingskema 42	666
182. Klerksdorp-wysigingskema 27	667
183. Voorgestelde Uitbreiding van Grense (1) Hendrina Uitbreiding 1	667
Tenders	669
Plaaslike Bestuurskennisgewings	671

Printed for the Transvaal Provincial Administration, | Gedruk vir die Transvaalse Provinciale Administrasie,
Pta. by Hoofstadpers Beperk, P.O. Box 422, Pretoria. | Pta. deur Hoofstadpers Beperk, Posbus 422, Pretoria.